91553

SDMS US EPA REGION V -1

SOME IMAGES WITHIN THIS DOCUMENT MAY BE ILLEGIBLE DUE TO BAD SOURCE DOCUMENTS.

PAGE 1 OF 62

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY REGION V SITE SAFETY PLAN

| Date: | February 16, 1995 | | |
|-------------------------------------|---|---------|---------|
| Project Name: | Sauget Landfill St. Clair County Sauget, Illinois | | |
| ERCS Delivery Order #: | 5001-05-365 | | |
| TAT Technical Direction Document #: | | | |
| U.S. EPA Site I.D.#: | | | |
| ERCS Job #: | 8165 | | |
| Adopted By: ERCS Response Mar | nager | Date: | 2-2195 |
| Adopted By: E & E Lead TAT Mo | ember | Date: | |
| Adopted By: U.S. EPA On-Scene | Coordinator | Date: - | 2/21/85 |
| Adopted By: ERCS Safety Manage | ~ er | Date: | 2/18/15 |
| Adopted By: E & E Safety Officer | • | Date: | |

DATE:02/16/95

SSP:

Sauget Landfill

TABLE OF CONTENTS

INTRODUCTION AND SITE ENTRY REQUIREMENTS

1.0 SITE BACKGROUND AND SCOPE OF WORK

- 1.1 Roles and Responsibilities
- 1.2 Key Personnel
- 1.3 Site Background
- 1.4 Scope of Work for ERCS
- 1.5 Scope of Work for TAT

2.0 TASK SAFETY AND HEALTH RISK ANALYSES

- 2.1 Task Specific Hazards and Controls
- 2.2 Chemical Hazards
- 2.3 Physical Hazards

3.0 PERSONNEL TRAINING

4.0 PERSONAL PROTECTIVE EQUIPMENT

- 4.1 Level A
- 4.2 Level B
- 4.3 Level C
- 4.4 Level D
- 4.5 Decision to Upgrade/Downgrade PPE

5.0 MEDICAL MONITORING REQUIREMENTS

- 5.1 Pre-employment Physical
- 5.2 Site Specific Physical Examination
- 5.3 Annual Physical Exam
- 5.4 Accidental/Suspected Exposure Physical
- 5.5 Contractor Physical Examination Requirements
- 5.6 Site Documentation

6.0 AIR MONITORING AND ACTION LEVELS

- 6.1 Routine Air Monitoring Requirements
- 6.2 Site Specific Air Monitoring Requirements
- 6.3 Personnel/Monitoring
- 6.4 Noise Monitoring

TABLE OF CONTENTS (cont'd)

- 6.5 Heat Stress Monitoring
- 6.6 Other
- 6.7 Names of Monitoring Technicians
- 6.8 Location of Monitoring Records

7.0 SITE CONTROL AND STANDARD OPERATING PROCEDURES

- 7.1 Work Zones
- 7.2 General Field Safety Rules

8.0 DECONTAMINATION PROCEDURES

- 8.1 Procedures for Equipment Decontamination
- 8.2 Procedures for Personnel Decontamination
- 8.3 Emergency Decontamination
- 8.4 Decontamination Equipment Required
- 8.5 Disposition of Decontamination Wastes

9.0 HAZARD COMMUNICATION

- 9.1 Material Safety Data Sheets
- 9.2 Container Labeling
- 9.3 Chemicals Brought to Site
- 9.4 Employee Training and Information

10.0 EMERGENCIES/ACCIDENTS/INJURIES

- 10.1 Emergency Contacts
- 10.2 Additional Emergency Numbers
- 10.3 Emergency Equipment Available On-Site
- 10.4 Accident Reporting/Investigations

11.0 EMERGENCY RESPONSE CONTINGENCY PLAN

- 11.1 Personnel Responsibilities
- 11.2 Medical Emergencies
- 11.3 Fire or Explosion
- 11.4 Spills, Leaks, or Releases
- 11.5 Evacuation Routes

12.0 CONFINED SPACE

SSP:

MANDATORY ATTACHMENTS

- ATTACHMENT A SITE SAFETY PLAN AMENDMENTS
- ATTACHMENT B SITE MAPS
- ATTACHMENT C CHEMICAL HAZARD INFORMATION
- ATTACHMENT D PERSONAL PROTECTION EQUIPMENT AND RESPIRATORY PROTECTION SOP'S
- ATTACHMENT E DRUG AND ALCOHOL PROCEDURES
- ATTACHMENT F ACCIDENT REPORTING/INVESTIGATION
- ATTACHMENT Z SITE SAFETY PLAN ACKNOWLEDGMENT FORM

OPTIONAL ATTACHMENTS HAZARDS AND SOPS ASSOCIATED WITH:

| | OSHA Guidance and Regulations |
|-------------|-----------------------------------|
| | Confined Space |
| | Drum Handling |
| | Drum Sampling |
| | Opening Drums and Overpacks |
| | Drum Staging and Overpacking |
| | Drum Excavation |
| | Empty Drum Crushing |
| | Drill Rig |
| G | Site Walkthroughs/Entry |
| | Housekeeping and Material Storage |
| | Hazardous Waste Storage |
| | Demolition |
| <u>H</u> | Working Around Heavy Equipment |
| _H_ | General Heavy Equipment Operation |

| <u> </u> | Excavation | |
|-------------|--|---|
| <u>J</u> | Truck Loading | |
| <u>K</u> | Soil Sampling | |
| | Liquid Sampling | |
| | Compatibility Testing and Compositing of Samples | |
| | Lab Packing and Lab Inventory | |
| | Flammable/Combustible Liquid Transfer | |
| | Corrosive Liquid Transfer | |
| | Use of High Pressure Water Cleanup | |
| | Use of a High Pressure Water Cleaner in Vats | |
| | Compressed Gas Cylinders | |
| | Heat Stress | |
| <u>L</u> | Cold Stress | |
| | Electrical Safety | |
| | Traffic Control | |
| | Fire Prevention and Protection | |
| | Work from Elevated Surfaces | |
| | Cranes | |
| | Rigging | |
| | Lockout/Tagout | |
| | Welding/Cutting/Grinding | |
| | Other: | |
| | * | _ |

GLOSSARY OF ACRONYMS

ANSI - AMERICAN NATIONAL STANDARDS INSTITUTE

APR - AIR PURIFYING RESPIRATOR

ACGIH - AMERICAN CONFERENCE OF GOVERNMENTAL

INDUSTRIAL HYGIENISTS

CFR - CODE OF FEDERAL REGULATIONS

CGI - COMBUSTIBLE GAS INDICATOR

CLEAN ZONE - SUPPORT ZONE

CSEP - CONFINED SPACE ENTRY PERMIT

DECON - DECONTAMINATION

ERCS - EMERGENCY RESPONSE CLEAN-UP SERVICES

HNU-PID - HNU PHOTOIONIZATION DETECTOR

HOT ZONE - EXCLUSION ZONE

IAW - IN ACCORDANCE WITH

IDLH - IMMEDIATELY DANGEROUS TO LIFE & HEALTH

MREM/hr - MILLI-ROENTGENS EQUIVALENT IN MAN PER HOUR

NIOSH - NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY &

HEALTH

OSC - ON-SCENE COORDINATOR

OSHA - OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION

LIMIT

OVA - ORGANIC VAPOR ANALYZER

PAPR - POWERED AIR PURIFYING RESPIRATORS

PEL - PERMISSIBLE EXPOSURE LIMIT

PPM - PARTS PER MILLION

RES - RIEDEL ENVIRONMENTAL SERVICES, INC.

RM - RESPONSE MANAGER

SCBA - SELF-CONTAINED BREATHING APPARATUS

SOP - STANDARD OPERATING PROCEDURE

SPCC - SPILL PREVENTION CONTROLS & COUNTERMEASURES

TAT - TECHNICAL ASSISTANCE TEAM

TLV - THRESHOLD LIMIT VALUE
TWA - TIME WEIGHTED AVERAGE

U.S. EPA - U.S. ENVIRONMENTAL PROTECTION AGENCY

INTRODUCTION AND SITE ENTRY REQUIREMENTS

This document describes the health and safety guidelines developed for the Sauget Landfill site, to protect on-site personnel, visitors, and the public from physical harm and exposure to hazardous materials or wastes. The procedures and guidelines contained herein were based upon the best available information at the time of the plan's preparation. Specific requirements will be revised when new information is received or conditions change. A written amendment will document all changes made to the plan. Any amendments to this plan will be included in Attachment A. Where appropriate, specific OSHA standards or other guidance will be cited and applied.

All work practices and procedures implemented on site must be designated to minimize worker contact with hazardous materials and to reduce the possibility of physical injury. All work will be performed in accordance with applicable Federal 29CFR 1910 and 1926 Health and Safety Regulations and the Federal 29CFR 1910.120 Hazardous Waste Site Safety Regulations.

DAILY SAFETY MEETINGS

Daily safety meetings will be held at the start of each shift to ensure that all personnel understand site conditions and operating procedures, to ensure that personal protective equipment is being used correctly and to address worker health and safety concerns.

SITE SAFETY PLAN ACCEPTANCE ACKNOWLEDGMENT

The OSC or designated representative shall be responsible for informing all individuals entering the exclusion zone or decontamination zone of the contents of this plan and ensuring that each person signs the Safety Plan Acknowledgment Form in Attachment Z. By signing the Safety Plan Acknowledgment Form, individuals are recognizing the potential hazards present on-site and the policies and procedures required to minimize exposure or adverse effects of these hazards.

SSP: Sauget Landfill DATE:02/16/95 PAGE 7 OF 62

1.0 <u>SITE BACKGROUND AND **SCOPE** OF WORK</u>

1.1 ROLES AND RESPONSIBILITIES

On-Scene Coordinator (OSC):

The OSC, as the representative of the U.S. EPA, is responsible for overall project administration and for coordinating health and safety standards for all individuals on-site at all times. All U.S. EPA and contractors health and safety guidelines and requirements as well as all applicable OSHA standards shall be applied. The OSC is the overall site safety officer and will be responsible for the health and safety of on-site visitors. However, each contractor (as an employer under OSHA) is also responsible for the health and safety of its employees. If there is any dispute with regards to health and safety, the following procedures shall be followed:

- 1) Attempt to resolve the issue on-site; and,
- 2) If the issue cannot be resolved, on-site personnel shall consult off-site health and safety personnel for assistance and the specific task operation in dispute shall be discontinued until the issue is resolved.

Response Manager (RM):

The Response Manager, as the field representative for the ERCS clean-up contractor, has the responsibility for fulfilling the terms of the delivery order. The RM must oversee the project and ensure that all technical, regulatory and safety requirements are met. It is the RM's responsibility to communicate with the OSC as frequently as dictated by the OSC, but at least daily, regarding site clean-up progress and any problems encountered.

Technical Assistance Team (TAT):

The Technical Assistance Team is responsible for providing the OSC with assistance and support in regards to all technical, regulatory and safety aspects of site activity. The TAT is also available to advise the OSC on matters relating to sampling, treatment, packaging, labeling, compatibility, transport, and disposal of hazardous materials, but is not limited to the above-mentioned.

Site Health and Safety Officer (HSO):

The ERCS and TAT Site Safety Officers will be assigned to the site on a full-time basis with functional responsibility for implementing the Site Health and Safety Plan as it applies to ERCS and TAT personnel. The Response Manager is the designated ERCS HSO. The Lead TAT Member is the designated TAT HSO unless otherwise appointed. Site audits may be conducted by the ERCS Health and Safety manager, TAT personnel and/or the U.S. EPA.

SSP: Sauget Landfill DATE:02/16/95 PAGE 8 OF 62

Specific Duties Include:

- a. Assume responsibility for health and safety of ERCS and/or TAT personnel.
- b. Supervise confined space entries.
- c. Document safety problems.
- d. Supervise decontamination of personnel and equipment.
- e. Ensure that monitoring equipment is calibrated/operational.
- f. Conduct personal air monitoring on all ERCS and/or TAT employees as outlined in 29CFR 1910.120(h)(4).
- g. Perform respiratory fit tests.
- h. Inventory/inspect PPE prior to personnel entries.
- i. Prepare summary letter of personal air sampling results.
- j. Select protective equipment levels based upon chemical properties, method of contact and air sample results.
- k. Prepare and maintain OSHA Log within 3 days of accident.
- 1. Insure all ERCS and/or TAT personnel are fit for duty.
- m. Competent person for excavation/trench entry jobs.
- n. Inspect first aid kits/fire extinguishers/SCBA.

Other:

Any persons who observe safety problems should immediately report observations/concerns to appropriate key personnel listed in Section 1.2.

SSP: Sauget Landfill DATE:02/16/95 PAGE 9 OF 62

SUBCONTRACTORS

| COM | PANY: | | | |
|-------|--------------------------|--------|--------|-------------|
| | CONTACT NAME: | | | |
| | ADDRESS: | | | |
| | | | ··· | |
| | SCOPE OF WORK: | | | |
| | TRAINING REQUIRED: | | | |
| | CONTRACTOR PREQUALIFIED? | [] YES | [] NO | |
| COM | DANV. | | | |
| COIVI | PANY:CONTACT NAME: | | | |
| | ADDRESS: | | | |
| | | | | |
| | SCOPE OF WORK: | | | |
| | TRAINING REQUIRED: | | | |
| | CONTRACTOR PREQUALIFIED? | | | |
| COM | DANIV. | | | |
| | PANY:CONTACT NAME: | | PHONE: | |
| | ADDRESS: | | | |
| | | | | |
| | SCOPE OF WORK: | | | |
| | TRAINING REQUIRED: | | | |
| | CONTRACTOR PREQUALIFIED? | [] YES | [] NO | |
| | | | | |

1.2 Key Personnel U.S. EPA On-Scene Coordinator (OSC)/ Site Safety Officer: Sam Borries U.S. EPA Region V 77 West Jackson Chicago, IL 60604 (312) 353-2886 Alternate OSCs: Principle ERCS Contractor: Riedel Environmental Services, Inc. 18207 Edison Avenue Chesterfield, MO 63005 (314) 532-7660 Response Manager (RM): Ken Braig Subcontractors: ERCS Health & Safety Officer: . Greg Rakers TAT Health & Safety Officer: Technical Assistance Team (TAT): Ecology & Environment, Inc. 111 West Jackson Blvd. Chicago, Illinois 60604 (312) 663-9415 TAT Representatives: Other:

1.3 Site Background

1.3.1 Site Description

The Sauget Landfill site is located in west-central St. Clair County, Illinois, directly across the Mississippi River from St. Louis, Missouri (see Figure 1 - Site Location Map). The DCP site consists of a number of former municipal and industrial waste landfills; surface impoundments or lagoons; surface disposal areas; past excavations thought to be filled or partially filled with unknown wastes; and an areal drainage flowpath known as Dead Creek, which is closed off from the surface water intake at Queeny Avenue.

According to site file information, Site Q is a former subsurface/surface disposal area which occupies approximately 90 acres. The site is located in Sauget and is bordered by DCP site R and the old Sauget Power Plant on the north; the Illinois Central Gulf Railroad and a United States Corps of Engineers (U.S. COE) river levee on the east; agricultural land on the south; and the Mississippi River on the west (see Figure 2 - Site Features Map). Waste disposal activity occurred between 1962 and 1975.

The land surrounding the site is used **primarily** for industrial purposes. Commercial activities are located northeast of the site. The nearest residential area is approximately 1.5 miles southeast from the site and also 1 mile west from the site across the Mississippi River.

1.3.2 Site History

As recorded in site file information pertaining to previous site investigations, the surface of Site Q is littered with demolition debris and metal wastes. Two ponds are located at the south portion of the site. Surface runoff in this area flows toward the Mississippi River, but periodic flooding has occurred along the southern portion of the site over the past 10 years, most notably in 1977 and 1987. The most recent flooding episode occurred during the summer of 1993 when the entire site was inundated by Mississippi River flood waters. It was observed that debris was present over much of the site.

1.4 Scope of Work for ERCS Contractor

- 1) Mobilize and set up site.
- 2) Excavate disintegrated drums and soil.
- 3) Sample and load out for disposal.

1.5 Scope of Work for TAT

SSP: Sauget Landfill DATE:02/16/95 PAGE 12 OF 62

2.0 TASK SAFETY AND HEALTH RISK ANALYSIS

2.1 <u>Task Specific Hazards and Controls</u>

This section is to be addressed in the daily tool box safety meeting as each task is to be attempted. Each Task-Specific Safety Assessment is designed to develop awareness to chemical and physical hazards specific to each task. It would be impractical to repeat in complete detail each control measure and SOP for each job task. Sources and Hazards will be addressed for each job task with reference made to applicable control measures in Sections 2.2, 2.3 and SOP's. The tables in Section 2.2 and 2.3 should be posted in the break area and command post. When the Task-Specific Safety Assessment are discussed additional hazards may need to be addressed.

TASK SPECIFIC SAFETY ASSESSMENT

| JOB TASK: Mobilization PERSONAL PROTECTIVE EQUIPMENT: | | | | | |
|--|--|---|----------|--|--|
| HAZARD | SOURCES | CONTROL MEASURES | REF. | | |
| Cold Stress | Winter Temperatures | Warm break area. Awareness of symptoms. | SOP L | | |
| Heavy Equipment | Trac Hoe/Dozer/Trucks | Controlled work area. Experienced operators. | SOP H | | |
| Noise | Trac Hoe/Dozer/Trucks | Wear proper hearing protection. | Sect 2.3 | | |
| Topography | Uneven Slick Terrain Scattered Debris | Beware of slips, trips and falls. Keep work area organized | Sect 2.3 | | |
| Ergonomics | Lifting and Bending | Proper lifting and bending techniques. | Sect 2.3 | | |

SSP: Sauget Landfill DATE:02/16/95 PAGE 13 OF 62

TASK SPECIFIC SAFETY ASSESSMENT

| JOB TASK: Excavation | | | | | | |
|-------------------------------------|---------------------------------------|--|----------|--|--|--|
| PERSONAL PROTE | ECTIVE EQUIPMENT: Level C | Laborers/Level D Operators | · | | | |
| HAZARD SOURCES CONTROL MEASURES REI | | | | | | |
| Heavy Equipment | Trac Hoe/Dozer/Trucks | Controlled work area. Experienced operators. | SOP H | | | |
| Noise | Trac Hoe/Dozer/Trucks | Wear proper hearing protection. | Sect 2.3 | | | |
| Topography | Uneven Slick Terrain/Scattered Debris | Beware of slips, trips and falls. Keep work area organized. | Sect 2.3 | | | |
| Water | Mississippi River | Wear life jackets when within 20 feet of water. | | | | |
| Cold Stress | Winter Temperatures | Warm break area. Awareness of symptoms. | SOP L | | | |
| Ergonomics | Lifting and Bending | Proper lifting and bending techniques. | Sect 2.3 | | | |
| Dust | Excavation Material | Use water if visible dust is detected. | | | | |
| Excavation | Excavation | No one enter if > 4 foot. Proper sloping. | SOP I | | | |

TASK SPECIFIC SAFETY ASSESSMENT

| JOB TASK: Truck Loading | | | | | | |
|-------------------------|---|--|----------|--|--|--|
| PERSONAL PROTE | PERSONAL PROTECTIVE EQUIPMENT: Level C Laborers/Level D Operators | | | | | |
| HAZARD | SOURCES | CONTROL MEASURES | REF. | | | |
| Heavy Equipment | Trac Hoe/Trucks | Controlled work area. Experienced operators. | SOP H | | | |
| Noise | Trac Hoe/Trucks | Wear proper hearing protection. | Sect 2.3 | | | |
| Cold Stress | Winter Temperatures | Warm break area. Awareness of symptoms. | SOP L | | | |
| Topography | Uneven Slick Terrain/Scattered Debris | Beware of slips, trips and falls. Keep work area organized. | Sect 2.3 | | | |
| Ergonomics | Lifting and Bending | Use proper lifting and bending techniques. | Sect 2.3 | | | |
| Trucks | Truck Loading | Controlled work area. | SOP J | | | |

TASK SPECIFIC SAFETY ASSESSMENT

| JOB TASK: PERSONAL PROTECTIVE EQUIPMENT: | | | | | |
|---|--|--|--|--|--|
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

TASK SPECIFIC SAFETY ASSESSMENT

| JOB TASK: | | | | | | |
|--------------------------------|---------|------------------|------|--|--|--|
| PERSONAL PROTECTIVE EQUIPMENT: | | | | | | |
| HAZARD | SOURCES | CONTROL MEASURES | REF. | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

SSP: Sauget Landfill DATE:02/16/95 PAGE 15 OF 62

TASK SPECIFIC SAFETY ASSESSMENT

| JOB TASK: | | | | | | |
|-------------------|--------------------------------|------------------|------|--|--|--|
| PERSONAL PROTECTI | PERSONAL PROTECTIVE EQUIPMENT: | | | | | |
| HAZARD | SOURCES | CONTROL MEASURES | REF. | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

TASK SPECIFIC SAFETY ASSESSMENT

| JOB TASK: | | | | | | |
|--------------------------------|---------|------------------|------|--|--|--|
| PERSONAL PROTECTIVE EQUIPMENT: | | | | | | |
| HAZARD | SOURCES | CONTROL MEASURES | REF. | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

SSP: Sauget Landfill DATE:02/16/95 PAGE 16 OF 62

2.2 Chemical Hazards

| CHEMICAL | TLV/PEL/ IDLH | Physical Characteristics | Odor Threshold | Routes of Exposure | PPE Polymers | Symptoms Acute/Chronic | First Aid |
|------------------|------------------------------|-----------------------------|-------------------|--------------------|--------------|---------------------------|-------------------|
| PCB's | .5 mg/m ³ | Solid | NA | Skin/Inhalation | Nitrile | Chronic | Flush with water. |
| Phenol | 19 mg/m ³ | Solid/Liquid | 1 ppm | Skin/Inhalation | Nitrile | Skin | Flush with water. |
| Dichlorobenzene | 451 mg/m ³ | Solid/Liquid | l ppm | Inhalation | Nitrile | Headache/dizziness | Fresh air. |
| Trichlorobenzene | 37 mg/m ³ ceiling | Solid/Liquid | 3 ppm | Inhalation | Nitrile | Headache/dizziness | Fresh air. |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

The above listing should not be taken as a complete assessment of the hazards posed by materials at Sauget Landfill. The known and unknown mixed chemical hazards at this site prevent a clear determination of the specific effects of discrete compounds. Therefore, personnel must be alert for symptoms of possible exposure such as unusual smells, stinging, burning eyes, nose and throat, skin irritation, as well as feeling extremely well, depressed, sleepy or tired. Symptoms must be immediately reported to the site supervisor.

See Attachment C for Chemical Hazard Information and MSDS'.

SSP: Sauget Landfill DATE:02/16/95 PAGE 17 OF 62

2.3 Physical Hazards

SSP:

PHYSICAL/ENVIRONMENTAL HAZARD ANALYSIS

| HAZARD | PRE PLANNING TO CONTROL HAZARD | ACTIVE CONTROL MEASURES | |
|-----------------------------|---|---|--|
| Cold Stress | Anticipate possible low temperatures (winter months). Remember the temperature does not have to be below freezing to have a cold stress situation. | Warm break area. Warm decaffeinated drinks. Buddy system/awareness. First aid on site. Medical care if symptoms persist. | |
| Electrical | Locate and mark existing energized lines. De-energize lines if necessary to perform work safely. All electrical circuits will be grounded. All 120 volt single phase which are not a part of the permanent wiring will have a ground-fault interrupter in place. Temporary wiring will be guarded, buried or isolated by elevation to prevent accidental contact by personnel or equipment. Evaluate potential for high moisture/standing water areas and define special electrical wiring needs-typically requirement for low voltage lighting systems. | | |
| Ergonomic | All operations evaluated for ergonomic impact. Procedures written to define limits of lifting, pulling, etc. Procedures to define how personnel will utilize proper ergonomic concepts and utilize mechanical material handling equipment. Necessary mechanical material handling equipment specified and ordered for project. | Proper body mechanics techniques stressed and enforced on a daily basis. Mechanical handling equipment maintained and utilized. Proper body mechanics stressed in scheduled safety meetings. Injuries reported and medically treated if in doubt about severity. Operations changed as necessary based on injury experience or potential. | |
| Existing Site Topography | Survey site prior to layout. Identify areas unsafe for personnel or equipment due to physical conditions. Identify/locate existing utilities. Determine impact of site operations on surrounding properties, communities, etc. Identify mechanized equipment routes both on site and onto and off the site. Layout site into exclusion and contamination reduction zones based on initial site evaluation. | Awareness to work environment - regular inspection/audits to identify changing conditions. Shut down operations when unknown conditions encountered. | |

Sauget Landfill DATE:02/16/95 PAGE 18 OF 62

| HAZARD | PRE PLANNING TO CONTROL HAZARD | ACTIVE CONTROL MEASURES |
|---------------------------|--|---|
| Fires & Explosions | Evaluate all operations for fire and explosion potential. Define specific procedures for unique operations presenting unusual hazard such as flammable tank demolition. Ensure that properly trained personnel and specialized equipment is available. Define requirements for handling and storage of flammable liquids on site, need for hot work permits and procedures to follow in the event of fire or explosion. Define the type and quantity of fire suppression equipment needed on site. Coordinate which local fire fighting agencies to discuss unique fire hazards, hazardous materials, etc. Ensure site operations comply with 29CFR 1910.157G. | Inspect fire suppression equipment on a regular basis. Store flammables away from oxidizers and corrosives. Utilize Hot Work Permit for all hot work on site. Follow any site specific procedures regarding work around flammables. Review and practice contingency plans. Discuss on regular basis at scheduled safety meetings. |
| Flammable Vapor and Gases | Evaluate site to determine sources of likely flammable gas or vapor generation. Develop specific procedures to be followed in the event of exposure to flammables. Specify specialized equipment needs for inerting flammable atmospheres, ventilating spaces and monitoring flammable vapor concentrations. Define requirements for intrinsically safe equipment. Develop contingency plan to follow in the event of fire or explosion. | Calibrated monitoring equipment available and utilized by trained personnel whenever working where flammable gas or vapor is present. Monitoring performed at regular frequency and in all areas where vapor could generate or pool. Equipment and operations shut down when threshold levels are exceeded. Contingency plans reviewed regularly by all involved personnel. Work areas are carefully inspected to look for possible ignition sources. Sources are removed. Operations shut down if specific task procedures can't be followed to the letter. |
| Heat Stress | Anticipate possible elevated temperatures (summer months). Awareness to stress placed on body by specific PPE. Awareness to levels of heat stress symptoms. | Proper work/rest schedule and monitoring. Drink plenty of fluids. Buddy system/awareness. First aid on site. Medical care if symptoms persist. |

Sauget Landfill DATE:02/16/95 PAGE 19 OF 62

SSP:

| HAZARD | PRE PLANNING TO CONTROL HAZARD | ACTIVE CONTROL MEASURES |
|---------------------------|---|--|
| Heavy Equipment Operation | Define equipment routes and traffic patterns for site. Insure that operators are properly trained on equipment operation for all equipment required on project. Define safety equipment requirements, including back up alarm and roll over, for all equipment on site. Define equipment routes and traffic patterns for site. Implement SOP of requiring operators to safety inspect equipment on a daily basis in accordance with manufacturer requirements. Evaluate project requirements to ensure that equipment of adequate capacity is specified. | Equipment inspected as required. Equipment repaired or taken out of service. Ground spotters are assigned to work with equipment operators. Utilize standard hand signals and communication protocols. Personnel wear the proper PPE, utilize hearing protection, gloves for handling rigging, etc. Equipment safety procedures discussed at daily scheduled safety meetings. Personnel do not exceed lifting capacities, load limits, etc. for equipment in question. Personnel follow basic SOP's which prohibit passengers on equipment, activating brakes and grounding buckets, securing loads prior to movement, etc. |
| Illumination | Evaluate all operations and work areas to determine lighting requirements. Specify specialized lighting requirements including explosion proof, intrinsically safe, lighting needs. Determine if nighttime outdoor operations are necessary. Evaluate tasks to be performed and number of light plants necessary to allow operations. Ascertain if outdoor lighting from nighttime operations will have an impact on surrounding communities. | Inspect specialized equipment and discard or replace as needed. Add additional lighting to areas with lighting deficiencies. Inspect drop cords and portable lights on regular basis. Replace or repair as necessary. |
| Noise | Local community noise standards examined. Expected loud operations evaluated to determine compliance with community standards. Loud operations scheduled for approved time periods. Noise level standards established for equipment brought onto site. Hearing protection requirements defined for personnel expected to have excessive exposures. | Personnel receive annual audiogram. Personnel required to wear hearing protection. Routine noise level monitoring and dosimetry performed. Defective equipment repaired as needed. Ongoing hearing conservation education promoted at scheduled safety meetings. Medical evaluation following noise (impact) exposure if symptoms present themselves. |

SSP: Sauget Landfill DATE:02/16/95 PAGE 20 OF 62

| HAZARD | PRE PLANNING TO CONTROL HAZARD | ACTIVE CONTROL MEASURES |
|--------------------------|---|--|
| Personal Injuries | Site operations will be evaluated for exposures with serious injury potential such as falling objects, pinch points, flying objects, falls from elevated surfaces, etc. A written Fall Prevention Program will be developed if workers will be required to work at heights greater than 10 feet from unguarded work locations. PPE requirements will be based on potential for injury. | Personnel will wear required PPE. Specialized equipment such as rope grabs, winches, etc. will be inspected prior to each use. Defective equipment will be immediately replaced. All injury and near miss incidents will be reported to the HSO. First aid/CPR trained person on site at all times. All injuries will be treated on site with advanced medical treatment being sought if doubt about severity. |
| Radiation | Evaluate potential for exposure to radioactive materials. If likely, develop specialized training program for personnel. Develop plan and specify equipment for monitoring potential radiation sources. Establish health physics dosimetry program. If not likely, implement SOP of stopping work should any sign of radioactive materials become apparent. | Perform monitoring as defined in safety plan. Perform necessary calibration and maintenance on monitoring equipment. Employees participate in health physics monitoring program. Notify Project Manager when suspect materials are detected. |
| Small Equipment Usage | Site operations evaluated to determine need for specialized intrinsically safe, explosion-proof and UL approved equipment and instruments. Implement requirement for G.F.I., double insulated tool usage, or assured grounding program in all outdoor operations, will be utilized. Specify equipment needs to ensure that equipment used only for the purpose for which it is designed and to prevent abuse or misuse of the equipment. Specify requirements for the inspections and maintenance of specialized equipment. Specify that all equipment utilized on the project meets all OSHA requirements. | First aid on site. Transport for medical care if necessary. |
| Wildlife | Inspect work environment where tasks are being performed. Awareness to bites. Dogs, animals, poison ivy, etc. | First aid on site. Seek medical attention if symptoms-signs persist. |

SSP: Sauget Landfill DATE:02/16/95 PAGE 21 OF 62

| HAZARD | PRE PLANNING TO CONTROL HAZARD | ACTIVE CONTROL MEASURES |
|--------------------------|---|--|
| Trenching and Excavation | Implement ERCS excavation procedures if entry required into any excavation greater than 4 feet depth. Specify that Competent Person(s) assigned to project be present at all times personnel inside trench(s). Specify that a Professional Engineer design specialized shoring systems for those that are extremely deep. Specify special PPE and monitoring requirements for excavations in soils contaminated with hazardous materials or gases and vapors. Ensure excavations comply with 29CFR 1926, Subpart P. | Competent person in the immediate area at all times that personnel are required to enter trenches. Operations shut down if the excavation shows any sign of cave in, excessive water, unacceptable levels of toxic contaminants, changing weather, or shoring systems have visible defects. Equipment operators keep all personnel inside excavation in sight. No suspended loads or movement of buckets over personnel. Regular monitoring is performed in excavations where toxic gases or vapors are possible. |
| Weather Conditions | Evaluate prevailing weather conditions for the site. Contingency plans developed for likely severe weather conditions such as tornado, and extreme thunderstorm. Provide for daily weather forecast service in extreme weather areas. Plan to weatherize safety systems, such as showers and eye washes, that would be impacted by extreme cold weather. Order necessary specialized cold weather clothing. Grounding and bonding requirements defined for thunderstorm areas. Sheltered air conditioned break areas provided for extreme hot and cold weather zones. | Employees trained in contingency plan for severe weather conditions. Emergency water sources inspected regularly in cold areas. Weather service contacted regularly during storm conditions. Supervisory personnel cease operations during extreme storm conditions (i.e., thunderstorms). Personnel evacuate to safe assembly area. |

SSP: Sauget Landfill DATE:02/16/95 PAGE 22 OF 62

3.0 PERSONNEL TRAINING

[1] **Initial Training**

40 Hour Training a.

All field employees receive forty hours of classroom training on safe work practices and hazardous waste sites.

b. Supervisor/Managers

Manager and Supervisors receive eight hours of training on safe management of hazardous waste sites. All training complies with 29CFR 1910.120.

The following individuals are Site Supervisors:

- Sam Borries [1]
- [2] Ken Braig

[2] Site Specific Training

- a. All assigned personnel will receive site specific training on routes of exposure and adverse health effects associated with the chemicals listed on the attachment.
- At least one member of each work crew shall have training in the use of b. portable fire extinguishers in accordance with 29CFR 1910.157G.
- IAW 29CFR 1910.120, all personnel newly assigned to hazardous waste work c. will receive 3 days of on the job training by an experienced supervisor. This typically is achieved by coordinating the work schedule so that they perform 25% of the expected workload the first day; 50% the second day, and 75% the third day.
- d. Each person entering the site shall sign a statement attesting to the fact that they have read and understand the Site Specific Safety Plan. (Attachment Z)

[3] Annual Refresher

All field employees receive eight hours of refresher training on the above topics within the anniversary date of their initial 40 hour class.

[4] First Aid/CPR

All field employees receive initial and recertification training. Treatment limited to Good Samaritan/minor first aid. All traumatic/major first aid, and cardiac problems will be referred to medical facilities.

DATE:02/16/95 PAGE 23 OF 62 SSP: Sauget Landfill

[5] Subcontractor Requirements All subcontractors entering the contamination reduction zone and exclusion zone will have adequate training satisfying 29 CFR 1910.120.

4.0 PERSONAL PROTECTIVE EQUIPMENT

The following is a brief description of the personal protective equipment which may be required during various phases of the project. The U.S. EPA terminology for protective equipment will be used; Levels A, B, C and D.

Respiratory protective equipment shall be NIOSH-approved and use shall conform to OSHA 29 CFR Part 1910.134 Requirements. Each employer shall maintain a written respirator program detailing selection, use, cleaning, maintenance and storage of respiratory protective equipment. The written Respirator Program will be maintained at the local and regional offices.

4.1 Level A Protection Shall Be Used When:

- The extremely hazardous substance requires the highest level of protection for skin, eyes and the respiratory system;
- Substances with a high degree of hazard to the skin are known or suspected;
- Chemical concentrations are known to be above IDLH levels; or,
- Biological hazards requiring Level A are known or suspected.

4.2 Level B Protection Shall Be Used When:

- The substance(s) has been identified and requires a high level of respiratory protection but less skin protection;
- Concentrations of chemicals in the air are IDLH or above the maximum use limit of an APR with full-face mask:
- Oxygen deficient or potentially oxygen deficient atmospheres (<19.5%) are possible; and/or,
- Confined space entry may require Level B.
- Incomplete identification of gases and vapors, but not suspected to be harmful to skin or skin absorbable.

4.3 Level C Protection Shall Be Used When:

- The same level of skin protection as Level B, but a lower level of respiratory protection is required;
- The types of air contaminants have been identified, concentrations measured, and an air-purifying respirator is available that can remove contaminants; or,
- The substance has adequate warning properties and all criteria for the use of APR respirators has been met.

4.3.1 Level C Protective Equipment at a Minimum Shall Consist of:

| Protective Gear - Level C | (Check and list required type) |
|--|--|
| MSA Air Purifying Respirator or PAPR | Fullface |
| Cartridges (type) | GMC-H |
| Escape Mask | |
| Chemical Resistant/Protective Coveralls (type) | Tyvek-dry/Saranex-liquid |
| Full Body Apron or Other (type) | |
| Inner Gloves (type) | Nitrile |
| Outer Chemical Gloves (type) | Nitrile |
| Outer Work Gloves (type) | |
| Safety Shoes/Boots (type) | Steel toed chemical resistant |
| Hard Hat | <u>X</u> |
| Respiratory Inserts | |
| Other (List) | |
| Modifications: Life jacket if working within 20 | feet of river. |
| | |
| | |
| 4.4 <u>Level D Protection Shall Be Used When</u> : | |
| | n hazard; and, , immersion or the potential for unexpected ardous concentrations of harmful chemicals. |
| 4.4.1 Level D Protection Equipment at a Minim | num Shall Consist of: |
| Protective Gear - Level D | (Check and list required type) |
| Chemical Resistant/Protective Coveralls (type) | Tyvek |
| Rain Suit | 1,7,000 |
| Safety Shoes/Boots (type) | Steel toed |
| Boot Covers (booties) | As needed |
| Work Gloves (type) | |
| Hard Hat | X |
| Face Shield | |
| Safety Glasses | |
| Modifications: Life jacket if working within 20 | feet of river. |
| | |
| | |
| | |

SSP: Sauget Landfill DATE:02/16/95 PAGE 25 OF 62

Specific operating procedures for PPE and Respiratory Protection are in Attachment D.

4.5 <u>Decisions to Upgrade/Downgrade PPE</u>

- [1] All decisions to downgrade from Level B to C or D must be accompanied by air monitoring results. The Regional Safety Managers (ERCS, TAT) must be advised of on-site decisions to downgrade. All decisions must be documented with an Addendum to the Plan.
- [2] The following conditions will necessitate reevaluation of PPE use.
 - a. commencement of a new work not previously identified
 - b. change of job tasks during a work phase
 - c. change of season/weather
 - d. contaminants other than those identified in Safety Plan
 - e. change in ambient levels of contaminants
 - f. change in work which affects degree of chemical contact
- [3] Action Levels (See Section 6.0)

5.0 MEDICAL SURVEILLANCE

5.1 Pre-Employment Physical

- a. Pre-employment and periodic update medical examinations are required for persons working at hazardous waste sites.
- b. All physicals must be completed and documented prior to assignment to this site.
- c. All physical exams will be conducted following parameters established by the respective employee's Corporate Physicians.

5.2 Site Specific Physical Examination

| a. | N/A | |
|----|-----|--|
| h | | |

c. A current Fitness for **Duty** statement will be kept on site for all ERCS personnel.

5.3 Annual Physical Exam

The medical examination must have been within a 12-month period prior to on-site activity and repeated annually.

5.4 Accidental/Suspected Exposure Physical

- a. Following any accidental or suspected uncontrolled exposure to site contaminants, personnel should be scheduled for a special physical examination.
- b. The physical examination will be specific for the contaminants and the associated target organs or physiological system.

SSP: Sauget Landfill DATE:02/16/95 PAGE 26 OF 62

c. <u>N/A</u>

d. Questions regarding the type of physical can be directed to the employer's Directors of Health and Safety or their Corporate Physicians. See Section 10.2 for their respective phone numbers.

5.5 Contractor Physical Examination Requirements

All subcontractors entering the contamination reduction or exclusion zone will have adequate medical surveillance satisfying 29CFR 1910.120.10 (f).

5.6 <u>Site Documentation</u>

All personnel on-site must have the following documentation available on site:

- [1] Copy of 40 hour certificate
- [2] Copy of Manager's/Supervisor's 8 hour certificate
- [3] Copy of 8 Hour Annual Refresher (if > 12 months since 40 hour)
- [4] CPR/First Aid Certificate (annual)
- [5] Respirator Fit Test (annual)
- [6] Medical Fitness For Duty
- [7] Memorandum of Understanding & Consent (RES only)
- [8] Worksite Exposure Documentation

6.0 AIR MONITORING AND ACTION LEVELS

According to 29 CFR 1910.120 (h) Air Monitoring shall be used to identify and quantify airborne levels of hazardous substances and health hazards in order to determine the appropriate level of employee protection needed on-site.

6.1 Routine Air Monitoring Requirements

- Upon initial entry to rule out IDLH conditions;
- When the possibility of an IDLH condition or flammable atmosphere has developed;
- When work begins on a different portion of the site;
- Contaminants other than those previously identified are being handled;
- A different type of operation is initiated;
- Employees are handling leaking drums or containers or working in areas with obvious liquid contamination; and,
- During confined space work.

Air monitoring will consist at a minimum of the criteria listed below. All air monitoring data will be documented and submitted to the OSC and available in the command post site files for review by all interested persons. Air monitoring instruments will be calibrated and maintained in accordance with the manufacturer's specifications. Calibration and maintenance performed will be entered in the site log and/or instrument log book.

6.2 <u>Site Specific Air Monitoring Requirements</u>

| INSTRUMENT | COMPOUNDS TO DETECT | FREQUENCY | COMMENTS/ ACTION LEVEL |
|------------------------------------|--|-----------------|--|
| Combustible Gas Indicator (CGI) | Explosive/ Flammable Atmospheres | N/A | > 10% LEL |
| PID/FID | Organic Vapors and Gases | Scan excavation | Unidentified contaminants* < Background units - Level D Background-5 units - Level C 5-500 units - Level B |
| Asbestos/Fiber Monitoring | Asbestos | N/A | > 0.01 fibers/cc for PCM > 70 structures/mm ² for TEM > 1% asbestos/weight bulk sample |
| Jerome Mercury Analyzer | Mercury Vapors | N/A | > .025 mg/m ³ |
| Detector Tubes | Various | N/A | |
| Radiation Meter | Radiation | N/A | > 2 mR/hr |
| Oxygen Meter Other: | Oxygen | N/A | <19.5% and >23.5% O ² |

^{*} The reading must be sustained for one (1) minute in the breathing zone.

6.3 <u>Personnel Monitoring</u>

Explain strategy or why not required: At start up, all material is solid and wet, therefore personnel air monitoring will not be conducted unless conditions change.

SSP: Sauget Landfill DATE:02/16/95 PAGE 28 OF 62

7.0 <u>SITE CONTROL AND STANDARD OPERATING PROCEDURES</u>

7.1 Work Zones

The primary purpose for site controls is to establish the hazardous area perimeter, to reduce migration of contaminants into clean areas and to prevent access or exposure to hazardous materials by unauthorized persons. At the end of each workday, the site should be secured or guarded, to prevent unauthorized entry. Site work zones will include:

7.1.1 Clean Zone/Support Zone

This uncontaminated support zone or clean zone will be the area outside the exclusion and decontamination zones and within the geographic perimeters of the site. This area is used for staging of materials, parking of vehicles, office and laboratory facilities, sanitation facilities, and receipt of deliveries. Personnel entering this zone may include delivery personnel, visitors, security guards, etc., who will not necessarily be permitted in the exclusion zone. All personnel arriving in the support zone will upon arrival, report to the command post and sign the site entry/exit log. There will be one controlled entry/exit point from the clean zone to the decontamination zone.

[1] Location of Clean Zone och side of Banner quand

7.1.2 Decontamination Zone

The decontamination zone will provide a location for removal of contaminated personal protective equipment and final decontamination of personnel and equipment. All personnel and equipment should exit via the decon area. A separate decontamination area will be established for heavy equipment.

- [1] The decontamination zone is a buffer zone between contaminated and clean areas.
- [2] Identified by yellow banner guard.

7.1.3 Exclusion Zone/Hot Zone

The exclusion zone will be the "hot-zone" or contaminated area inside the site perimeter. Entry to and exit from this zone will be made through a designated point and all personnel will be required to sign the hot zone entry/exit log located at the decon area. Appropriate warning signs to identify the exclusion zone should be posted (i.e. "DANGER - AUTHORIZED PERSONNEL ONLY", "PROTECTIVE EQUIPMENT REQUIRED BEYOND THIS POINT", etc.) Exit from the exclusion zone must be accompanied by personnel and equipment decontamination as described in Section 8.0.

| Wil | be identified by red banner guard. |
|-----|--|
| The | se areas will be defined by rellbanner mark |
| Gen | eral Safety Rules for Exclusion Zone |
| a. | wear the appropriate level of PPE defined in plan |
| b. | do not remove any PPE or break the integrity to pick, scratch, or toucl parts of your body |
| c. | no smoking, eating or drinking |
| d. | no horseplay |
| e. | no matches or lighters in this zone |

implement the communication and line of sight system

A map of the work zones for this site follows.

7.2 General Field Safety Rules

f.

- All visitors must be sent to the command post and referred to the OSC.
- It is EPA policy to practice administrative hazard control for all site areas by restricting entrance to exclusion zones to essential personnel and by using operational SOPs.
- Whenever possible, avoid contact with contaminated (or potentially contaminated) surfaces. Walk around (not through) puddles and discolored surfaces. Do not kneel on the ground or set equipment on the ground. Stay away from any waste drums unless necessary. Protect equipment from contamination by bagging.
- Eating, drinking, or smoking is permitted only in designated areas in the support zone.
- Hands and face must be thoroughly washed upon leaving the decon area.
- Beards or other facial hair that interferes with respirator fit will preclude admission to the hot zone.
- All equipment must be decontaminated or discarded upon exit from the exclusion zone, as determined by the OSC or designate.
- All personnel exiting the exclusion zone must go through the decontamination procedures described in Section 8.0.

SSP: Sauget Landfill DATE:02/16/95 PAGE 31 OF 62

| 6.3.1 | Sampling Methods (media type | e, analyses | es, NIOSH Method Number, etc.):_ | |
|-------|---|-------------|---|-------------|
| 6.3.2 | Describe calibration procedures | s: | | |
| 6.3.3 | Analytical laboratory to be use | <u>:d</u> : | | |
| 6.4 | Noise Monitoring: [|] Yes | [X] No | |
| Descr | ribe monitoring strategy: | | | |
| | Heat Stress Monitoring: [| _ | [X] No | |
| | Perimeter: [| - | [X] No | |
| Descr | Other: [| - | [] No | |
| | | | | |
| 6.7 | Name(s) of Monitoring Techni Steve Skare Samy Sirhan | | | |
| 6.8 | Location of Monitoring Record | <u>ls:</u> | | |
| | les of monitoring records will be itional copies will be maintained | | in the job file upon the completion alth and Safety Department. | of the job. |

- Safety Equipment described in Section 4.0 will be required for all field personnel.
- Personnel will only travel in vehicles where individual seats (for each occupant are provided. Seat belts will be worn as required.
- Fire extinguishers will be available on site and in all areas with increased fire danger such as the refueling area.
- A minimum of two personnel will always be on site whenever heavy equipment is operated. Only necessary personnel need to be on or around heavy equipment.
- Employees will not interfere with or tamper in any way with air monitoring equipment.
- Backhoes or other equipment with booms shall not be operated within 10 feet of any electrical conductor.
- Visitor log will be maintained at the command post or with the security guard. All personnel coming on site will sign in and out on a daily basis.
- Security will be maintained at the site by closing all gates during normal work hours. The OSC will assume responsibility for personnel entering site. Site will be locked up in the evening.
- EPA OSC will allow only those individuals authorized to enter the site. If unauthorized members of the public are found on site, contact security immediately and do not leave the individual unattended.
- Visitors are not allowed in the work areas without authorization and not without appropriate levels of PPE as determined by site safety personnel. Access to the properties is restricted to the EPA and authorized representatives. Persons other than the residents must sign in at the Command Post and receive authorization to enter the site.

■ Buddy System

- [1] The buddy system is mandatory at anytime that personnel are working in the exclusion zone, remote areas, on tanks, or when conditions present a risk to personnel.
- [2] A buddy system requires at least two trained/experienced people who work as a team and maintain at a minimum audible and/or visual contact while operating in the exclusion zone.

Communication Procedures

- [1] Radios will be used for on site communications and Channel 2 will be the designated channel.
- [2] The crews should remain in constant radio or visual contact while on site.

SSP: Sauget Landfill DATE:02/16/95 PAGE 32 OF 62

[3] The site evacuation signal will be 3 blasts on the air or vehicle horn.

8.0 DECONTAMINATION PROCEDURES

In general, everything that enters the exclusion zone at this site, must either be decontaminated or properly discarded upon exit from the exclusion zone. All personnel, including any state and local officials must enter and exit the hot zone through the decon area. Prior to demobilization, contaminated equipment will be decontaminated and inspected by the OSC or OSC designate before it is moved into the clean zone. Any material that is generated by decontamination procedures will be stored in a designated area in the exclusion zone until disposal arrangements are made.

All personnel must be documented on the "HOT ZONE ENTRY/EXIT LOG" when entering and exiting the exclusion zone.

<u>NOTE</u>: The type of decontamination solution to be used is dependent on the type of chemical hazards. The decontamination solution for this site is water. Decontamination solution will be changed daily (at a minimum) and collected and stored on-site until disposal arrangements are finalized.

8.1 Procedures for Equipment Decontamination

Following decontamination and prior to exit from the hot zone, the OSC or a designated alternate, shall be responsible for insuring that the item has been sufficiently decontaminated. This inspection shall be included in the site log.

Equipment decontamination will consist of the following steps:

Wash with water. and rings

Scrap snaked off all surfaces of necessary & wash.

8.2 Procedure for Personnel Decontamination

This decontamination procedure applies to personnel at this site wearing Level B and C protection. These are the minimum acceptable requirements:

Station 1: Equipment Drop

Deposit equipment used on-site (tools, sampling devices and monitoring instruments, radios, etc.) on plastic drop cloths. These items must be decontaminated or discarded as waste prior to removal from the exclusion zone.

Station 2: Outer Boot and Outer Glove Wash and Rinse

Scrub outer boots, outer gloves and/or splash suit with decontamination solution or detergent water. Rinse off using water.

Station 3: Outer Boot and Glove Removal

Remove outer boots and gloves. If outer boots are disposable, deposit in container with plastic liner. If non-disposable, store in a clean dry place.

Station 4: Tank Change

If person leaves exclusion zone to change air tank, this is the last step in the decontamination procedure. Air tank is exchanged, new outer gloves and boot covers donned, joints taped, and person returns to hot zone.

Station 5: Outer Garment Removal

If applicable, remove SCBA back-pack and remain on air as long as possible. Remove Chemical Resistant Outer Garments and deposit in container lined with plastic. Decontaminate or dispose of splash suits as necessary.

Station 6: Respiratory Protection Removal

Remove hard-hat, face-piece, and if applicable, deposit SCBA on a clean surface. APR cartridges will be discarded as appropriate. Wash and rinse respirator at least daily. Wipe off and store respiratory gear in a clean, dry location. (See Attachment D)

Station 7: Inner Glove Removal

Remove inner gloves. Deposit in container for disposal.

Station 8: Field Wash

Thoroughly wash hands and face with soap and water. Shower as soon as possible.

Eating, drinking, chewing gum/tobacco, smoking, or any practice that increases the probability of hand to mouth transfer and/or ingestion of materials is prohibited in any areas where the possibility of contamination exists and is permitted only in the designated break area.

Personnel will not wear or bring dirty/decontaminated clothing into the break areas.

| | Emergency decontamination will consist of the following steps: blood contaminated material will be bag, labeled and accompany the individual to the |
|-----|--|
| | al.) |
| | |
| 8.4 | The following decontamination equipment is required: |
| | , brushes, alconox |
| | |
| | |

8.5 Disposition of Decontamination Wastes

[1] All equipment and solvents used for decontamination shall be decontaminated or disposed of with the established waste streams.

SSP: Sauget Landfill DATE:02/16/95 PAGE 34 OF 62

| [2] | Commercial laundries or cleaning establishments that decontaminate or are used to launder contaminated clothing shall be informed of the presence and potentially harmful effects of the contaminants. | | |
|-------|--|--|--|
| [3] | /A | | |
| | | | |
| A ske | tch of the decon area for this site is shown in Attachment B. | | |
| 9.0 | HAZARD COMMUNICATION PROGRAM | | |
| | contractor will be responsible for maintaining a copy of their Hazardous Communication am and MSDS' on site. The following items are specific to this job site: | | |
| 9.1 | Material Safety Data Sheets | | |
| | [1] Material Safety Data Sheets will be maintained at the Command Post in the Health and Safety Binder. | | |
| | [2] MSDS' will be available to all employees for review during the work shift. [3] See Attachment C and/or the ERCS Health and Safety Binder. | | |
| 9.2 | Container Labeling | | |
| | [1] All containers received on site will be inspected by the contractor using the material to ensure the following: | | |
| | a. all containers clearly labeled | | |
| | b. appropriate hazard warningc. name and address of the manufacturer | | |
| 9.3 | The following chemicals were brought to the site: | | |
| | [1] Alconox | | |
| | [2] Gasoline | | |
| | [3] Diesel Fuel [4] MSA Sanitizer | | |
| | [5] | | |
| | [6] | | |
| 9.4 | Employee Training and Information | | |
| | [1] Prior to starting work, each employee will attend a health and safety orientation | | |

SSP: Sauget Landfill DATE:02/16/95 PAGE 35 OF 62

physical and health effects of the hazardous chemicals

and will receive information and training on the following:

Communication Standard

b. c.

d.

an overview of the requirements contained in the Hazardous

Hazardous chemicals present at the site the location and availability of the written Haz Comm Program

- e. methods of preventing or eliminating exposure
- f. emergency procedures to follow if exposed
- g. how to read labels and review MSDS' to obtain information
- h. location of MSDS file and location of hazardous chemical list

See ERCS Health and Safety Binder for Hazard Communication Program and applicable MSDS'.

10.0 <u>EMERGENCIES/ACCIDENTS/INJURIES</u>

It is essential that site personnel be prepared in the event of an emergency. Emergencies can take many forms; illnesses or injuries, chemical exposure, fires, explosions, spills, leaks, releases of harmful contaminants, or sudden changes in the weather. The following sections outline the general procedures for emergencies. Emergency information should be posted as appropriate.

10.1 Emergency Contacts for Sauget Landfill Site

Fire:

911 Sauget

Police:

911 Sauget

Sheriff:

911 St. Clair

Ambulance:

911 Sauget

*Hospital:

St. Louis University

Address:

Grand at Vista, St. Louis, MO

Telephone:

(314) 577-8000

Chemical Trauma Capabilities?

Yes

Poison Control Center:

(800) S'52 - 2012

Take entrance road back to Route 3. Turn left and go 1 mile. Take I-64 west and cross bridge. Take I-55 south 1 mile to I-44 west. Take I-44 west 2 miles to the Grand exit and turn right and go 1/2 mile. Hospital is on left.

<u>NOTE</u>: Maps and directions to the hospital will be posted in the office +cailec.

SSP: Sauget Landfill DATE:02/16/95 PAGE 36 OF 62

^{*}Directions from Site to Hospital (See Map in Attachment B):

e. methods of preventing or eliminating exposure

f. emergency procedures to follow if exposed

g. how to read labels and review MSDS' to obtain information

h. location of MSDS file and location of hazardous chemical list

See ERCS Health and Safety Binder for Hazard Communication Program and applicable MSDS'.

10.0 EMERGENCIES/ACCIDENTS/INJURIES

It is essential that site personnel be prepared in the event of an emergency. Emergencies can take many forms; illnesses or injuries, chemical exposure, fires, explosions, spills, leaks, releases of harmful contaminants, or sudden changes in the weather. The following sections outline the general procedures for emergencies. Emergency information should be posted as appropriate.

10.1 Emergency Contacts for Sauget Landfill Site

Fire:

911 Sauget

Police:

911 Sauget

Sheriff:

911 St. Clair

Ambulance:

911 Sauget

*Hospital:

St. Louis University

Address:

Grand at Vista, St. Louis, MO

Telephone:

(314) 577-8000

Chemical Trauma Capabilities?

Yes

Poison Control Center:

(800) 852 - 2022

Take entrance road back to Route 3. Turn left and go 1 mile. Take I-64 west and cross bridge. Take I-55 south 1 mile to I-44 west. Take I-44 west 2 miles to the Grand exit and turn right and go 1/2 mile. Hospital is on left.

NOTE: Maps and directions to the hospital will be posted in the office $+ca.|_{2}c$.

^{*}Directions from Site to Hospital (See Map in Attachment B):

The route to the hospital was verified by: Greg Rakers on February 16, 1995. Distance from site to hospital is 5 miles. Approximate driving time is 8 minutes.

The following individuals have been trained in CPR and First Aid:

| Ken Braig | Sum Borries |
|-----------|--------------|
| | Summy Sirhan |

10.2 Additional Emergency Numbers

| National Response Center | 800-424-8802 |
|---------------------------------|----------------------|
| U.S. EPA Region V - E.R. Branch | 312-353-2318 (24 hr) |
| Center for Disease Control | 404-488-4100 (24 hr) |
| AT&F (Explosives Information) | 800-424-9555 |
| Chemtrec | 800-424-9300 |
| State Environmental Agency | 615/ 346-5126 |

Ecology & Environment, Inc. Contacts

| E & E Regional Office (for this site) | |
|---|-----------------------|
| E & E MEDTOX Emergency Medical Hotline | 501-221-0463 (24 Hr.) |
| - | 904-462-3277/3281 |
| Dr. Harbison (Home) | 501-370-8263 |
| E & E Corporate H & S - Dr. Paul Jonmaire | 716-684-8060 |
| E & E Emergency Operations Center Hotline | 716-684-8940 (24 Hr.) |
| - , , | 716-684-8060 |
| TAT Leader Region V - Thomas Kouris | 312-663-9415 |

Riedel Environmental Services, Inc. Contacts

| Riedel Environmental Services | 800-334-0004 (24 Hr.) |
|---|-----------------------|
| Riedel Environmental Services (Chicago) | 708-671-0061 |
| Riedel Environmental Services (St. Louis) | 314-532-7660 |
| RES Corporate H & S - Margaret Cunningham | 800-334-0004 |
| | |

EPA

| Federal Occupational Health Unit 3 | 12-353-0379 |
|------------------------------------|-------------|
|------------------------------------|-------------|

SSP: Sauget Landfill DATE:02/16/95 PAGE 37 OF 62

| 10.3 <u>Emergency Equipment</u> <u>Communications Equipment</u> | ent Available On-Site Location | |
|---|-----------------------------------|----------------------|
| Public Telephones: | MA | |
| Private Telephones: | 618/274-1222 | River City Lindscape |
| Mobile Telephones: | (2) E+E + RES | |
| Two-Way Radios: | At 4 hand he | 11 |
| Emergency Alarms/ Horns: | Autohoin | |
| Medical Equipment | /1 | |
| First Aid Kits: | 1/break van | |
| Inspection Date: | 2-24-95 By: | In fores |
| Stretcher/Backboard: | _fle | |
| Eye Wash Station: (within 100 feet of hazard Safety Shower: | zone) | |
| Fire-Fighting Equipment | | |
| Fire Extinguishers: | 2 (0) | |
| Inspection Date: | 3√95 By: | JAJ |
| Other: | | |
| Spill or Leak Equipment | ÷ | |
| Absorbent Boom/Pads: | NA | |
| Dry Absorbent: | _w/A | |

| Additional | Emergency | Equipment |
|------------|-----------|-----------|
| | | |

- 10.4 Accident Reporting/Investigations (See Attachment F for proper procedures.)
- 11.0 EMERGENCY RESPONSE CONTINGENCY PLAN
- 11.1 Project Personnel Responsibilities During Emergencies

ON-SCENE COORDINATOR (OSC)

As the administrator of the project, the OSC has primary responsibility for responding to and correcting emergency situations. The OSC will:

- Take appropriate measures to protect personnel including: withdrawal from the exclusion zone, total evacuation and securing of the site or up-grading or down- grading the level of protective clothing and respiratory protection.
- Take appropriate measures to protect the public and the environment including isolating and securing the site, preventing run-off to surface waters and ending or controlling the emergency to the extent possible.
- Ensure that appropriate Federal, State and local agencies are informed, and emergency response plans are coordinated. In the event of fire or explosion, the local fire department should be summoned immediately. In the event of an air release of toxic materials, the local authorities should be informed in order to assess the need for evacuation. In the event of a spill, sanitary districts and drinking water systems may need to be alerted.
- Ensure that appropriate decon treatment or testing for exposed or injured personnel is obtained.
- Determine the cause of the incident and make recommendations to prevent the recurrence.
- Ensure that all required reports have been prepared.

SSP: Sauget Landfill DATE:02/16/95 PAGE 39 OF 62

RESPONSE MANAGER (RM)

The RM must immediately report emergency situations to the OSC, take appropriate measures to protect site personnel and assist the OSC as necessary in responding to and mitigating the emergency situation.

TECHNICAL ASSISTANCE TEAM (TAT)

The TAT must immediately report emergency situations to the OSC, take appropriate measures to protect site personnel and assist the OSC as necessary.

11.2 Medical Emergencies:

Any person who becomes ill or injured in the exclusion zone must be decontaminated to the maximum extent possible. If the injury or illness is minor, full decontamination should be completed and first aid administered prior to transport. If the patient's condition is serious, at least partial decontamination should be completed (i.e., complete disrobing of the victim and redressing in clean coveralls or wrapping in a blanket.) First aid should be administered while awaiting an ambulance or paramedics. All injuries and illnesses must immediately be reported to the OSC.

Any person transporting an injured/exposed person to a clinic or hospital for treatment should take with them directions to the hospital and information on the chemical(s) they may have been exposed to. This information is included in Table 2.3. Any vehicle used to transport contaminated personnel, will be cleaned or decontaminated as necessary.

11.3 Fire or Explosion:

In the event of a fire or explosion, the local fire department should be summoned immediately. Upon their arrival the OSC or designated alternate will advise the fire commander of the location, nature and identification of the hazardous materials on-site.

If it is safe to do so, site personnel may:

- Use fire fighting equipment available on site.
- Remove or isolate flammable or other hazardous materials which may contribute to the fire.

11.4 Spills, Leaks or Releases:

In the event of a spill or a leak, site personnel will:

- Locate the source of the spillage and stop the flow if it can be done safely.
- Begin containment and recovery of the spilled materials.

SSP: Sauget Landfill DATE:02/16/95 PAGE 40 OF 62

11.5 Evacuation Routes and Resources:

Evacuation routes have been established by work area locations for this site. All buildings and outside work areas have been provided with two designated exit points. Evacuation should be conducted immediately, without regard for equipment under conditions of extreme emergency. See site map for evacuation routes.

- Evacuation notification will be three blasts on an air horn, vehicle horn, or by verbal communication via radio.
- Keep upwind of smoke, vapors or spill location.
- Exit through the decontamination corridor if possible.
- If evacuation is not via the decontamination corridor, site personnel should remove contaminated clothing once they are in a location of safety and leave it near the exclusion zone or in a safe place.
- The OSC will conduct a head count to insure all personnel have been evacuated safely.
- In the event that emergency site evacuation is necessary, all personnel are to:
 - 1. Escape the emergency situation;
 - 2. Decontaminate to the maximum extent practical; and,
 - 3. Meet at the U.S. EPA command post.
- In the event that the U.S. EPA command post is no longer in a safe zone, meet: River City Landscape trailer.

12.0 <u>CONFINED SPACE</u>

Type of Confined Space Location On-Site Comments

None anticipated.

SSP: Sauget Landfill DATE:02/16/95 PAGE 41 OF 62

ATTACHMENT A SITE SAFETY PLAN AMENDMENTS


SSP: Sauget Landfill DATE:02/16/95 PAGE 42 OF 62

| SITE SAFETY PLAN AMENDMENT | ſ # <u></u> : | | |
|----------------------------|---------------|---------------------|--------|
| SITE NAME: | | | |
| DATE: | | | · |
| TYPE OF AMENDMENT: | | | |
| REASON FOR AMENDMENT: | | | |
| | | | |
| | | | |
| ALTERNATE SAFEGUARD PROCEI | OURES: | | |
| | | | |
| | | | |
| | | | |
| REQUIRED CHANGES IN PPE: | | | |
| | | | |
| | | | |
| | | | |
| ERCS Response Manager | (Date) | ERCS Safety Manager | (Date) |
| E & E Lead TAT Member | (Date) | E & E RSO | (Date) |
| U.S. EPA OSC | (Date) | _ | |

SSP: Sauget Landfill DATE:02/16/95 PAGE 43 OF 62

ATTACHMENT B SITE MAPS

SSP: Sauget Landfill DATE:02/16/95 PAGE 44 OF 62



ATTACHMENT C CHEMICAL HAZARD INFORMATION

SSP: Sauget Landfill DATE:02/16/95 PAGE 45 OF 62

Hazard (liquid): By ingestion and inhalation; skin irritant.

See also polymer, stereospecific.

pelybutene. See polybutylene.

polyisobutene. (polybutene; polyisobutylene; polyisobutene). Any of several thermoplastic isotactic (stereo-regular) polymers of isobutene of varying molecular weight, also polymers of butene-1 and butene-2. Butyl rubber is a type of polyisobutene to which has been added 2% of isoprene, which provides sulfur linkage sites for vulcanization. Isobutene can be homopolymerized to various degrees in chains containing from 10 to 1000 units, the viscosity increasing with molecular weight. Combustible.

the also "Vistanex."

Lubricating-oil additive, hot-melt adhesives, parling tapes, special scalents, cable insulation, selymer modifier, viscosity index improvers, the and coatings.

intriese terephthelate. An engineering placic desired from 1,4-butanediol, it is a thermometic polyester with a bread spectrum of pres-

Yearbonate.

whenste. (COOC,H,C(CH,)C,H,O). synthetic thermoplastic resin derived from b 1, a B omic acid: Cam be fo ri compound and my-carbo z interchan pa. Pri ultion or in no cronive, weather a low eth, heat-sesi cually stable sq earbous and attacked fig. atic hydrocarb uluble in aliphatic alcol ding methods, extrusion, t y fabricated by all w coming and fluidized Molded products, a a, structural parts, t lic devices, meter fa dows, street-light gl

For more carboxyl (COOH) groups a laboration of the carboxyl (COOH) groups a laboration. General name: for synthetic chief hydrocarbons.

polychlorinated hiphonyl. (PCB).

CAS: 1336-36-3. One of several assumatic compounds containing two benzene suchsi with two or more substituent chlorine atoms. They are colorless liquids with d 1.4-1.5. Because of their persistance, toxicity, and ecological damage via water pollution their manufacture was discontinued in the US in 1976.

Hazard: Highly toxic.

polychierograms. See meoprams.

polyubleretrifleereethylene. (PCTFE):
See dibyparilleereethylene polymer.

Polyeta. The for (1) an electio, making pailing other earlier stephing from the polymenthelites of castor off-word in review composition. There tile measurement, and as a polymeria physicism (2) a carter of polyects used in the dispersion and curing of workness polymens has graphylas cauting. Selling insulation, and designations.

And the state of t

The same of the sa

C

iS; a • J. re: ıΙ.

ch m

of 49 ti -

 \boldsymbol{C} pd٠Y٠ 'n; ıal ir-

ndes. H a -*J*.)°.

c,

he; 1. n: r.

tly

9534. Tricarballylic Acid. OH. The calcium sair is beet sugar maple as walls of evaporators in beet sugar maple as walls of exhaust propage 1 1 2 2 map

te walls of evaporators in occi sugar mydrolysis of ethyl propane-1.1,2,3-tern crarke. Murray, Org. Syn. coll. vol. I (2nd ed.) crarke, Murray, Org. Syn. con. vol. 1 (2nd ed from aconitic acid by reduction with sodium tig, Ann. 314, 15 (1901); by hydrolysis of 1 crarke, obtained by reaction tig, Ann. 314, 13 (1304), and an additional bomethoxypropane, obtained by reaction of nate with HCN in the presence of KCN:

pat. 2,992,268 (1958 to Prizer).

Large, orthorhombic prisms from water or ending the state of solve in 100 mt etner. Quite soi in alc. A trum: Bielecki, Henri, Ber. 46, 2596 (1913)

It is neutral to litmus.

Trimethyl ester, C₉H₁₄O₆, d²⁰₄ 1.1822; bp_u 150 9535. Tricetamide. N-[2-(Diethylamine). 9535. Tricetamine. N-(2-(Diethylamine)) 3,4,5-trimethoxybenzamide; N-(diethylcaria, 3,4,5-trimethoxybenzamide; N-(3,4,5-trimethoxybenzamide; N-(3,4,5-trimet 3,4,5-trimethoxybenzamtae; 3,4,5-trimethoxybenzamtae; N-(3,4,5-trimethoxybenzamtae; N-(3,4,5-trimethoxybenzamtae; Riker 548; Trimeglamide; C wt 324,37. C 59,24%, H 7.46%, N 8.64%, O 14,5-trimethoxybenzovl)oluond - 14,5-trimethoxybenzovl wt 324.37. C 39.2476, in the state of the st ylamine: Kuehne, Lambert, J. Am. Chan. ylamine: Kuenne, Lamour, Jam. Chen. (1959); from N-(3,4,5-trimethoxybenzoyl) nitrous acid and diethylamine: Kusserow, D 2,956,081 (1960 to Riker).

Crystals from water, mp 133-134°. THERAP CAT: Sedative.

9536. Trichlorfon, (2,2,2-Tricklero-1-4 phonic acid dimethyl ester; O.O. -trichloroethylphosphonate; 0.0-de uro-1-hydroxyethylphosphonate; chlorate trichlorphene; Bayer L 13/59; Vermicide bot Equine: Danex; Dipterex; Neguvos. Dylox; Bilarcil; Tugon; Proxol; Forchlor, wt 257.45. C 18.66%, H 3.13%, Cl 41.128 12.03%. Prepd by reaction of chloral with Phite: Lorenz, U.S. pat. 2,701,225 (1955 to et al., J. Am. Chem. Soc. 76, 4186 (1954); Le et al., J. Am. Chem. Soc. 76, 4186 (1954); Le Entomol. 52, 44 (1959). Identification of the state Lange, Z. Chem. 20, 446 (1980).

$$\begin{array}{ccc} \operatorname{CH_3O} & \operatorname{O} & \operatorname{OH} \\ & & & \\ & &$$

White crystals, mp 83-84°. dp 1.73 press at 20°: 7.8 × 10⁻⁶ mm Hg g/100 ml; chloroform 75 g/100 mbenzene 15.2 g/100 ml. Very hexane. Dec by alkali. LD g 630, 560 mg/kg, T. B. Gaines. Tested 515 (1960) 515 (1969).

Note: Neguvon A contains trick gredient, coumaphos, q.v. USE: Insecticide for the control of anthelmintic compositions for and U.S. pat. 3,111,457 (1963 to Am. 8

A cholinesterase inhibitor. THERAP CAT (VET): Antheim worms.

dex before using this section.

hornethiazide. 6-Chloro-3-(dichloromethorgenium-3-(dichlorometh-pH-1,2,4-benzothiadiazine-7-sulfonamide 2H-1, 3-dichloromethyl-7-sulfamyl-3,4-di-hibdiazine 1,1-dioxide: 3-dihloro-surramyl-3,4-di-nothiadiazine 1,1-dioxide; 3-dichloromethand this diazine 1,1-moxide; 3-dichloromethismy 1-3,4-dihydro-1,2,4-benzothiadiazine ndichloromethiazide: \$4.4-benzothiadiazine Jaichloromethiazide; Achletin; Anatran; richloromethiazide; Achletin; Anatran; richioromethiaziue; Achletin; Anatran; Carvacron; Diurese; Triclordiuride; Flutra; Flutran; Intromena.

Apaorini; Carvacron; Diurese; Triclordiuride; Apaorini; Flutra: Intromene; Kubacron; Diurese; Triflumen; Gangesol; Tachionini; Tolcasone; Triflumen; Gangesol; Tachionini; N.O.S.; mol wt 380.67. C 25.24%, C.H. Cl., N.O. 16.81%, S 16.85%. Prepn: 0.754%. N. 11.04%, O 16.81%, S 16.85%. Prepn: 0.754%. Septementia 16, 113 (1960); Sherlock OF Experientia 16, 113 (1960); Sherlock et al. E. I. Goldenthal, Toxicol. Appl. Phar-1000(y: 1 10 (1971).

methanol + acetone + water, dec 266-med as 248-250°. Soly (mg/ml) at 25°: water water mil at 25°: water ungrmi) at 25°: water produced as 240°20°C. LD₉₀ orally in rats: > 20,000

Diaretic, antihypertensive.

cetaldehyde. Chloral; anhydr chloral. 147.40. C 16.30%, H 0.68%, Cl 72.16%, O Made by chlorinating alcohol, treating CyCHO. Made by chlorinating alcohol, treating dendicatilling: Liebig, Ann. 1, 189 (1832); then distilling: Liebig, Ann. 1, 189 (1832); I had chim. [4] 10, 350 (1869); 11, 205 [18]. Soc. Chim. France [3] 17, 228 (1897); Trillat, Bull. Soc. Chim. [7] 18, 332 (1897); Besson, Ger. pat. 133,021 (1902); II, 353 (Ohse, Ger. pat. 734,723 (1943), 1943). Prepn by chlorination of a mixture of childholds: Société d'Electrochimie. Fr. pat. dehyde Société d'Electrochimie, Fr. pat a ladustrie 21, 567 (1929). Prepn from the smootropic distric Mahoney, Pierson, U.S. 1992 to Merck & Co.). From hypochlorous shylene: Stevens et al., U.S. pat. 2,759, Charles Southern). In the laboratory anhydr be eachly obtained by shaking pharmaceutical leave eth concel H₂SO₆, separating the two cf. Gattermann, Wieland, Praxis des Canters (de Gruyter, Berlin, 40th ed., 1961) Charal Hydrate.

1.510; d² 1.5050. 1.510; d² 1.5050. 1.510; d² 1.45572; n² 1.45412. Freely chloral hydrate. Sol in alcohol forming and in ether. Polymerizes under the influind in process. ce of sulfuric acid forming a white

nce may be habit forming and is list-Cale of Federal Regulations, Title 21 Part

al hydrate, DDT.

mate Add, TCA, C.HCl₃O₂; mol wt & # 462%, Cl 65.10%, O 19.58%. CCl₃distion of chloral hydrate with nitric neise of acetic acid: Eaker, U.S. pat. mto).

K slight characteristic odor. 16-197. Sol in 0.1 part water; very de by heating with caustic alkalies into the extense. Its aq soln is very acid to 1.2. Keep tightly closed in a cool to 1.2. Keep tightly closed in a ided. Decompn products ric acid, carbon dioxide and carm rata: 5000 mg/kg, G. W. Ren. 10, 97 (1965). Clear liq;

1.383. bp 168°. np 1.4507.

Sodium salt. C2Cl3NaO2, sodium trichloroacetate, Konesta, Varitox. Yellow deliquesc powder, mp > 300°, water at 25°: 1.2 kg/l. Sol in ethanol. Soly in

Caution: Very corrosive! When sufficient penetration has occurred, the parts should be irrigated with sodium carbonate soln.

USE: As a decalcifier and fixative in microscopy; also as a precipitant of protein. As herbicide.

THERAP CAT: Caustic.

THERAP CAT (VET): Caustic, vesicant.

9540. Trichloroacetonitrile. Trichloromethylnitrile: Tri-tox. C₂Cl₃N: mol wt 144.40. C 16.63%, Cl 73.66%, N 9.70%. CCl₃CN. Prepared from ethyl trichloroacetate and aq ammonia: Davies, Jenkin, J. Chem. Soc. 1954, 2374; by action of phosphorus pentoxide on trichloroacetamide: Carpenter. J. Org. Chem. 27, 2085 (1962). Manuf by reaction of methylnitrile, HCl and chlorine gas: Käbisch. U.S. pat. 2,745,868 (1956 to Degussa). Physical and thermodynamic

2,173,000 (1730 to Legussa). Physical and thermodynamic properties: Davies, Jenkin, loc. cit.
Liquid, bp₁₆₀ 85.7; d¹/₂ 1.4403, d¹/₂ 1.4223; n²⁰⁰/₂ 1.4409, n²⁷⁰/₂ 1.4375. LD₅₀ orally in rats: 0.25 g/kg, H. F. Smyth et al., Am. Ind. Hyg. Assoc. J. 23, 95 (1962).

USE: Insecticide. Caution: A strong irritant to eyes, skin.

9541. 2,4,6-Trichloroanisole. Tyrene. C₇H₃Cl₃O; mol wt 211.49. C 39.75%, H 2.38%, Cl 50.30%, O 7.57%. Prepd by reaction of 2,4,6-trichlorophenol with dimethyl sulfate: Kohn, Heller, Monatsh. 46, 91 (1925).

Monoclinic needles from alc, mp 60°, bp738,2 240°, bp28 132°. Faint odor similar to that of acetophenone. Sublimes slowly at room temp. Volatile with steam. Practically insol in water. Sol in methanol, dioxane, benzene, cyclohexanone. USE: Formerly as a dye assistant for polyester fibers.

9542. 1.2.3-Trichlorobenzene. vic-Trichlorobenzene. C.H.Cl.; mol 181.46. C 39.71%, H 1.67%, Cl 58.62%. Prepared from 3,4,5-trichloroaniline by diazotization: Cohen, Hartley, J. Chem. Soc. 87, 1365 (1905); Holleman, Rec. Trav. Chim. 37, 196 (1918); from 2,3,4-trichloroaniline by diazotization: Dadien et al., Monatsh. 61, 431 (1932); from 2,3,4-trichloroaniline by treatment with ethyl nitrite: Beilstein. Kurbatow, Ann. 192, 234 (1878).

Platelets from alc, d 1.69. mp 52.6°. bp 221°. np 1.5776. Flash pt 113° (235.4°F). Volatile with steam. Insol in water. Sparingly sol in alc. Freely sol in benzene, carbon disulfide. USE: A commercial grade (mixture of isomeric trichlorobenzenes) is used to combat termites. Caution: Irritating to eves, mucous membranes

9543, 1,2,4-Trichlorobenzene. unsym-Trichlorobenzene. C₄H₃Cl₃; mol wt 181.46. C 39.71% H 1.67%, Cl 58.62%. Prepd from 2,4-dichloroaniline or 2,5-dichloroaniline or 3,4-dichloroaniline by diazotization and treatment with Cu2-Cl₂: Beilstein, Kurbatow, Ann. 192, 230 (1878); van der Lande, Rec. Trav. Chim. 51, 104, 110 (1932); from 1,3-diaminobenzene by tetrazotization and treatment with Cu2Cl2: Cohn, Fischer, Monatsh. 21, 278 (1900).

7212. p-1

acid; sulfoc:

41.37%, H

able as a 6

p-bromobe

pat. 1,321, Byrne, Bri

Prepn of a

Delia

Amn

Bari

Monot

in alce

Cau

USE:

721

In the

al-3-1

droxy

drox -ed:

1.39

10pher 6, 94 pat. Du

fonate.

7205. Phenoctide. N,N-Diethyl-N-[2-[4-(1,1,3,3-tetramethylbutyl)phenoxy]ethyl]benzenemethanaminium chloride; benzyldiethyl-2-{(p-1,1,3,3-tetramethylbutyl)phenoxylethyl-ammonium chloride; β-p-tert-octylphenoxyethyldiethylbenammonium chloride; p-p-teri-detylphenoxyculyaniculyiouz-zylammonium chloride; Octaphen. C₂₇H₄₂ClNO; mol wt 432.11. C 75.05%, H 9.80%, Cl 8.21%, N 3.24%, O 3.70%. Prepn: Goldberg, Besly, Brit, pat. 703,477 (1954 to Ward Blenkinsop); Erekaev, C.A. 54, 12483i (1960).

$$\begin{bmatrix} \mathsf{CH}_3 & \mathsf{CH}_3 & \mathsf{CH}_3 \\ \mathsf{CH}_3 & \mathsf{CCH}_2 & \mathsf{C} \\ \mathsf{CH}_3 & \mathsf{CH}_3 & \mathsf{CH}_3 & \mathsf{CH}_2 & \mathsf{C}_2 \mathsf{H}_5 \\ \mathsf{CH}_3 & \mathsf{CH}_3 & \mathsf{CH}_3 & \mathsf{C}_2 \mathsf{H}_5 \end{bmatrix} \mathsf{C1}$$

Crystals from ethyl acetate. mp 112-114 (Goldberg, Besly); mp 95° (Erekaev).

USE: Orthophosphate as lubricant: Semmens, Summers-Smith, Brit. pat. 790,056 (1958 to I.C.I.). THERAP CAT: Topical anti-infective.

7206. Phenol. Carbolic acid; phenic acid; phenylic acid; phenyl hydroxide; hydroxybenzene; oxybenzene. C.H.O; mol wt 94.11. C 76.57%, H 6.43%, O 17.00%. Obtained from coal tar, or made by fusing sodium benzenesulfonate with NaOH, or by heating monochlorobenzene with aq NaOH under high pressure. The crystalline article of NaOH under high pressure. The crystalline article of commerce contains at least 98% phenol. Review of mfg processes: A. Dierichs, R. Kubicka, Phenole und Basen, Vorkommen und Gewinnung (Akademie-Verlag, Berlin, 1958) 472 pp; Faith, Keyes & Clark's Industrial Chemicals, F. A. Lowenheim, M. K. Moran, Eds. (Wiley-Interscience, New York, 4th ed., 1975) pp 612-623. Use in treatment of presticity. rew 101k, 4th ed., 1973) pp 612-623. Use in treatment of spasticity: D. E. Garland et al., Clin. Orthop. 165, 217 (1982); eidem, Arch. Phys. Med. Rehab. 65, 243 (1984). Review of use in pain relief: K. M. Wood, Pain 5, 205-229 (1978). Review of toxicology: H. Babich, D. L. Davis, Regul. Toxicol. Pharmacol. 1, 90-109 (1981). Toxicity: W. B. Deichmann, S. Witherup, J. Pharmacol. Exp. Ther. 80, 233 (1944). Review: C. Thurman in Kirk. 233 (1944). Review: C. Thurman in Kirk-Othmer Encyclopedia of Chemical Technology vol. 17 (Wiley-Interscience, New York, 3rd ed., 1982) pp 373-384.

Colorless, acicular crystals or white, crystalline mass; characteristic odor. Poisonous and caustic! Prone to redden on exposure to air and light, hastened by presence of alkaon exposure to air and light, hastened by presence of alkalinity. d 1.071. When free from water and cresols it congeals at 41° and melts at 43°. Ultrapure material mp 40.85°. The commercial product contains an impurity which raises the mp. bp 182°. Flash pt, closed cup: 175°F (79°C). nft 1.5425. pKa at 25° = 10.0. pH of aq solns about 6.0. It is liquefied by mixing with about 8% water. One gram dissolves in about 15 ml water. 12 ml bearens very cold in alecsolves in about 15 ml water, 12 ml benzene; very sol in alcohol, chloroform, ether, glycerol, carbon disulfide, petrolatum, volatile and fixed oils, aq alkali hydroxides. Almost insol in petr ether. LD50 orally in rats: 530 mg/kg (Deichmann, Witherup). Keep well closed and protected from light. Do not handle with bare hands.

Incompat. Phenol coagulates collodion; liquefies or becomes semiliquid when triturated with acetanilide, butylchloral hydrate, camphor, monobromated camphor, chloral hydrate, diuretin, lead acetate, menthol, naphthalene, naphthol, acetophenetidin, pyrogallol, resorcinol, salol, sodium phosphate, thymol, urethane, chloralamide, terpin hydrate.

Ammonium salt, C.H.NO. ammonium phenate, ammonium carbolate. White to pink cryst masses. Sol in water. Sodium salt, C6H5NaO, phenolate sodium.

Aqueous solution with phenolate sodium. Chloraseptic. Human Toxicity: Ingestion of even small amounts may cause nausea, vomiting, circulatory collapse, tachypnea,

paralysis, convulsions, con urine, necrosis of mouth and G1 respiratory failure, sometimes for fatal dose is 15 g but death from been reported. Fatal possessing absorption following applica poisoning with renal and he industrial contact. See C. J. Po cal Toxicology (Lippincott, Deichmann, Keplinger in Patty)
Toxicology vol. 2A, G. D. Cayton, P. ley-Interscience, New York, 3rd

USE: As a general disinfectant, slaked lime, etc., for toilets, stab etc.; for the manuf of colories or resins, many medical and med dyes; as a reagent in chemical (preservative)

THERAP CAT: Aqueous soln antiseptic; topical antipruritic.

THERAP CAT (VET): Antiseptic c pruritic skin conditions. Has be ternally as an antiseptic.

7207. Phenoldisulfonic Acid. 44 sulfonic acid; 4-hydroxy-m-benz nol-2,4-disulfonic acid. C.H.O.S. 28.34%, H 2.38%, O 44.05%, \$ 25.225. by hydrolysis of the dichloride which s tion of chlorosulfonic acid on phenol at w et al., Monatsh. 46, 395 (1925). Mone Sulfonation and Related Reactions (Im 1965) 529 pp.

Deliquescent needles, vague melting fi 100°. Decomp above 100°. Freely sol # Practically insol in ether, petr ether. USE: In the manuf of aminophenok are intermediates in the dye industry

3,3-Bis(44 7208. Phenolphthalein. (3H)-isobenzofuranone; 3,3-bis(p-hydroxy) α-(p-hydroxyphenyl)-α-(4-οxο-2.5-cycle ene)-o-toluic acid: Chocolax: Darmoi: Lamoi wt 318.31. C 75.46%, H 4.4%, O acondensing phone of the condensing phone of the condension phone of the co condensing phenol with phthalic anhydragon, 69 (1880); Herzog, Chem. Zig. 51, 84 (1980); Chem. Zig. 51, 84 (1980); Herzog, Chem. Zig. 51, 84 (U.S. pat. 2,192,485 (1940 to Ex Lax); 04 2,522,939 (1950 to Monsanto).

Minute, triclinic crystals, often twinned. 1.299. Color: White or yellowish walls Phenolphthalen. Almost insoluble in walts solves in 12 ml alcohol, in about 100 ml ethers sol in chlorof

USE: A 1% alcoholic soln as an indicator mineral and organic acids and most alkaling for ammonia. Very sensitive to CO₂, and bonates the lig must be a constant. bonates the liq must be boiled. Borax

ntor only when glycerol is presalkaloids. Colorless to pH 8.5;

used as a laxative.

Sodium. 3,3-Bis(4-hydroxyphendisodium salt. C₂₀H₁₂Na₂O₄. H 3.34%, Na 12.70%, O 17.67%. on of 1 mol phenolphthalein by OH. Structure: Buu-Hoi, Bull.

ar mass with coppery luster, or pale Soluble in water, giving a deep-red 550-555 nm. The unstable enol be the trisodium salt.

2-[Bis(4-hydroxyphenyl)methyl]-2-[Bis(4-hydroxyphenyl)metnyl] mind phenolphthalein; phthalin; 4',4''-hthane-2-carboxylic acid. C₂₀H₁₆O₄; had by Made by 19.9%, H 5.04%, O 19.98%. Made by their with zinc dust in alkaline soln. regent" when in soln. Prepd by dishalin + 20 g KOH in a desired amt of and diluting with an equal vol of 95%
directions for prepn of test soln and its lac Chim. Belge 54, 186-202 (1945), C./

mp 237°. Insol in water; sol in alcohol. The alkaline solns gradually become pink or other oxidizing substances for oxidases, blood, HCN, peroxides,

thalol. 2-[Bis(4-hydroxyphenyl)methyl]fbis(p-hydroxyphenyl)methyl]benzyl al-Tots(p-hydroxyphenyl)methyljbenzyl ali-nylmethenylbenzyl alcohol: 2-(4,4'-di-nylmethenylbenzyl alcohol: 2-(4,4'-di-nylbenzyl alcohol: bis(4-hydroxyphenyl)-lbenylmethane: Egmol: Regolax. Co-105,34. C 78.41%, H 5.92%, O 15.67%. Arh. Pharm. 288, 234 (1955): Bulcsu. Ger. (1962 to Iromaics). C 4 50 1535b (1963). 1962 to Iromedica). C.A. 59, 1535b (1963).

alcohol, mp 201-202° The Hao, crystals from benzene or chloro-boluble in dil NaOH nctically insol in dil alkali.

Consult the cross inde

of chlorobenzene: Engelsma et al., Rec. Trav. Chim. 76, 325 (1957). Separation of mixture contg m-, o-, and p-dichlorobenzenes by distillation and crystn: Mueller, Wolz, Fr, pat. 1,374,863 (1964 to Bayer), C.A. 62, 4936e (1965), corresp to Brit. pat. 999,845,

Liquid, bp 173°. mp -24.76°. d2 1.2884, d2 1.2828. n3 1.5459. Practically insol in water; sol in alcohol, ether.

3044. o-Dichlorobenzene. 1,2-Dichlorobenzene: orthodichlorobenzene. Empirical formula, prepn, and separation from m- and p-dichlorobenzenes, see m-isomer above. Manuf: Faith, Keyes & Clark's Industrial Chemicals, F. A. Lowenheim, M. K. Moran, Eds. (Wiley-Interscience, New York, 4th ed., 1975) pp 258-265.

Liquid, bp 180.5. mp - 17.03. dp 1.3059, dp 1.3003. nf 1.5515, nf 1.5491. Flash pt, closed cup: 151°F (66°C). Practically insol in water; miscible with alc, ether, benzene.

USE: Solvent for waxes, gums, resins, tars, rubbers, oils, asphalts; insecticide for termites and locust borers; fumigant; removing sulfur from illuminating gas; as degreasing agent for metals, leather, wool; as ingredient of metal polishes; as heat transfer medium; as intermediate in the manuf of dyes. Caution: Can cause injury to liver, kidneys. High concus cause CNS depression.

3045. p-Dichlorobennene, Paracide; PDB; Paradichlorobenzene; Para-zene; Di-chloricide; Paramoth. Empirical formula, prepn, and separation from m- and o-dichlorobenzene, see m-isomer above. Crystal structure of triclinic form (β-modification): Housty, Clastre, Acta Cryst. 10, 695 (1957); of monoclinic form (a-modification) and its transformation to triclinic form: Panatoni et al., Gazz. Chim. Ital. 93, 813 (1963). Manuf: Paith, Keyes & Clark's Industrial Chemicals, F. A.Lowenheim, M. K. Moran, Eds. (Wiley-Interscience, New Yok, 4th ed., 1975) pp 258-265.

Volatile crystals with a characteristic penetrating odor Sublimes at ordinary temps. mp 53.5° (α-modification). 54° (β-modification). bp 174.12°. πβ 1.5285. Flash pt (closed cup) 150°F. Practically issol in water; sol in alcohol, ether, benzene, chloroform, carbon disulfide. Non-corrosive; nonstaining. LD₃₀ orally in rats: 500 mg/kg, Toxic Substances List, H. E. Christensen, Ed. (1973) p 321.

USE: Insecticidal funnigant. Popular for domestic use against clothes moths. Caution: Vapors may cause irritation to skin, throat, and eyes. Prolonged exposure to high conens may show weakness, dizziness, loss of weight; liver injury may develop.

3046. 2,2'-Dichlorsbenzidine. 2,2'-Dichlorof1,1'-bi-phenylj-4,4'-diamine: C.H. Cl.N.; mol wt 253.13. C 56.94%, H 3.98%, Cl 28.01%, N 11.07%. Prepn from m-Laubenheimer, Ber. 8, 1625 (1875); chloronitrobenzene: Cain, May, J. Chem. Soc. 97, 723 (1910).

Needles from water or prisess from alc, mp 165°. Almost insol is water; moderstaly sol in alc; readily sol in ether. Hydrochloride, C12H21C12N22HCl, leaflets from water, moderately sol in water. USE: Manuf azo dyes.

3047. 3,3'-Dichlorobenzidine. 3,3-Dichloro-(1,1'-biphenyl)-4,4'-diamine; 3,3'-dichloro-4,4'-biphenyldiamine; DCB. C₁₂H₁₆C₁N₂; mol wt 253.13. C 56.94% H 3.98%, Cl 28.01%, N 11.07%. Prepn from o-chloronitrobenzene: Colin, Ber. 33, 3552 (1900). Review and evaluation of studies of carcinogenicity is laboratory animals and in humans: IARC Monographs 4, 49-55 (1974).

of arsi the ting the 431. Jewis 23); Lewis

Johns Chemistry

mint odor

organic

olyzed by powder, Extremel

rubber. sufficient

may ca

J.Dichlore

dioxo-1,4

Q.N.O.; mi

iker, Waug

so orange c

viene chlor

tchlorodiff

12: Freo CCl₂F₂: m He

m. Zentr.

ndustrial C

Wiley-1 practical

able B

Grable V

bp

Has !

Propt.

e dioxai

93 bP 93 0: 0.087

systemic

Needles from aic or benzene, mp 132-1 in water. Readily sol in alc, benzene, Hydrochloride, C₁₂H₁₀Cl₂N₂.2HCl, n water, readily in alc.

Note: This substance may reasonably carcinogen: Fourth Annual Report on 85-002, 1985) p 79.

USE: Manuf azo dyes; as an intermedia Yellow pigments.

3048. Dichlorobenzyl Alcohol. 2,4 methanol; Dybenal. C,H_cCl₂O; mol m II H 3.42%, Cl 40.05%, O 9.04%. Prepn: Trav. Chim. 51, 98 (1932); Metayer, Dat. Chim. France 1954, 615.

Crystals, mp 59.5°. THERAP CAT: Antiseptic.

3049. 1,1-Dichloro -2,2-bis(p-ch -(2,2-Dichloroethylidene)bis[4-ch rodiphenylethane; TDE; dichlorod DDD; p.p'-DDD; p.p'-TDE; Rhot 320.05. C 52.54%, H 3.15%, Cl 44. pesticide; a component of technical condensing dichloroacetaldehyde v ler et al., J. Am. Chem. Soc. 67, 19

Crystals, mp 109-110°. The ch are similar to those of DDT. LE mg/kg, T. B. Gaines, Taxicol,

USE: Insecticide. Caution: Acute toxicity symptoms: lethargy by mated fatal oral dose 5 g/kg be symptoms: atrophy of adrenal cor toms similar to DDT, q.v.

3050. 1,1-Dichloro-2,2-b (2,2-Dichloroethylidene)bis[4-el phenyl)-1,1-dichloroethane, di ane; Perthane; Q-137. C₃₈H₃₈Cl H 6.56%, Cl 23.08%. Prepn: I 2,917,553 (1955 to Rohm &

Crystals from ethanol mp water; sol in acetone, kerosen, persistence in the soil. LD of T. B. Gaines, Toxicol Appl. USE: Insecticide. Caution

3051. Dichlore(2-chlore) arsonous dichloride; 2-chiorovi nylarsine dichloride; Lewisite. C 11.59%, H 0.97%, As 34:13% AsCl₂. Obtained together with sine and tris(2-chlorovinyl)arsi



THE: SOP-SITE ENTRY

Category: GENERAL TECHNICAL 2.2

Revised: JANUARY 1990

In addition, each team member should closely adhere to the following guidelines:

- o Each member should have his or her name written on the hard hat or coverall for ease of identification when respiratory protective equipment is worn;
- o Extraneous conversation is forbidden;
- o Standard procedures and nomenclature will be used;
 - Each transmission is begun by identifying the party being reached, followed by identification of the initiator; and
 - This is followed by a pause for acknowledgment.
 - Each word must be pronounced clearly; language should be plain and direct; and
 - Each transmission should end with "over" or 10-4.

ATTACHMENT H WORKING AROUND HEAVY EQUIPMENT GENERAL HEAVY EQUIPMENT OPERATIONS

SSP: Sauget Landfill DATE:02/16/95 PAGE 56 OF 62

GENERAL HEAVY EQUIPMENT OPERATIONS

- · Organize site, set up staging area, and designate routes for equipment.
- All operators must be trained and experienced with the equipment they are operating.
- All equipment must be maintained in accordance with 29 CFR 1926 regulations.
- Equipment requiring back-up or swing alarms must have an alarm or a spotter.
- Equipment capacity must be designated and not exceeded.
- Operators must wear seat belts unless the equipment does not have roll-over protection.
- Standard hand signals should be utilized when communicating with the equipment operator.
- No unnecessary personnel should be on the equipment.

WORKING AROUND HEAVY EQUIPMENT

- · No unnecessary personnel should be in the area of heavy equipment operation.
- · No personnel should be within 10 feet of the equipment when it is in operation.
- Anyone approaching a piece of heavy equipment must make visual contact with the operator.
- · No one except the operator should ride on heavy equipment.
- · Organize site, set up staging area, and designate routes for equipment.
- Standard hand signals should be utilized when communicating with the operator.

ATTACHMENT I EXCAVATION

SSP: Sauget Landfill DATE:02/16/95 PAGE 57 OF 62

FEDERAL REGISTER PART 1926.650 (AMENDED)

PART 1826-(AMERICED)

Subsert M-(Amended)

L By reviewe the eatherity citation for SUDDER MI OF PART 1828 to FREE 44 'auawer

A MAGNET See 107. Contract Work Hours Led Salety Standards Act (Compresses Salety Act (40 U.S.C. 1131: Sees. 4. 8. 8. Commence Salety and Hearth Ad of 1979 28 U.S.C. M.S. ALE SECTION OF LABORS Order No. 13-FT (30 FR 6734), 6-78 (41 FR :30001, or 0-40 (40 FR 35736), 44 applicable. LANGE BOTH HERE

2. By revising subpart P of part 1838 to read as fallower

Subport P-Lastrations

: SELAND. Sampa, applies tion, and definitions plantic to this subpart.

ISMAN CAMPE PROPERTY

SELACE Acquirements for protective

Appendix A to Subpart F-Sell Classification Apparelle 8 to Subport P-Sloping and

Appendix C to Subpart P-Timber Sharing

Appendix D to Subport F-Abeni Hydroxic Shoring for Translet

Appendix 2 to Subpast P—Alternatives to Teles theres

product for Subport F-Scientes of Transport Springer

Subpart P-Essevations

Ambanya See, 107. Contrast Worker House and Safety Standards Ant |Constructor Safety Ant (40 U.S. 257) Sees. 4 & & Onespeciant Salety and Health Ast of 1970 129 U.S.C. ASS. SAL SET: Secrety of Labor's Order No. 12-71 [26 FR 8750], 6-70 [41 FR 12500], or 6-60 [40 FR 38730], as applicable. IN HOTE PAR SELL

- § 1976.600 Scope, conficulties, and conficulties applicable to this expect.
- (a) Scope and explination. This subpart applies to all open expercitors made in the earth's surface. Expercitors ere defined to testade trans
- (b) Deflactions applicable to this support.

Accepted engineering precious means these requirements which are competible with standards of prootes required by a registered preferenced

Alemana Hydroulie Sharing massa a pre-remeered shoring system comprised of alumnous hydroulis cytindere (crossbraces) used in continued with vertical ratio (uprights) or horizontal ratio (waters). Such system

sidewells of an excevetion and prevent CAVE-IRS.

Bell-bettem pier hele meens a type of their or footing excavation, the bottom of which is made larger than the cross testion above to form a period shape.

Benching (Senening system) meens a method of presecting employees from cave-tee by exervetting the rides of an ezerveden to form one or a series of bertanecal levels or scope, esselly with vertical or man-vertical surfaces permees levels

Cave-is means the separation of a e of sail or rook mesons from the side of an experience or the ions of soil from under a trunch chiefe or support system, and its sudden movement into مدد ند the excevation, either by falling or eliding, in redictions quantity so that it aid entrop. bury, or otherwise injure

and immebilize a person.

Compount person means one who is capable of identifying exacting and prodictable beauties in the st or working conditions which are uncontary, honorates, or deager ployees, and who has embergation to take prempt corrective measures to maste them.

Cross broase moss the herisantal sais of a spaint shows inversed lender to the ender of the mavester, the ends of which bear person either uprights or weign.

Constitute moone any man-mode cut. at depression in an earth many, man ies, fer ed by sorth removed

.Feese or sides means the an the vertex or mit of encoveries week.

Patters means the breakes displacement, or permanent deformation of a structural member or connection so es to rednes its street wai intensity and lts supportive espabilities.
Henerolous consephere masse on

copiers which by reases of be emplosive, Hammann, process, eryper corrective, emidiate, lettering, eryper deficient, tente, or otherwise hammal, may cause death, illness, or injury, "Tabase wasen the accidental reion

Flanous mouse broom or failure of a cross broom a crossod of presenting compleyees from coroling and from from motorial that sould fall or rail from en excevetion term the enlique of excevetion, or from the enlique of exception of the enlique of lactude support systems, stoping and benefiting systems, shield systems, an other systems that provide the ecoary protoc

one on tackned weight or Remp me working ourless that is used to gate serves to one point from season

IVECTORE BRISTIALS SUCE ES SIEST OF

Registered Professional Engineer SPECIO E POTOCE WOO IS TOURISTY prefessional engineer in the stat. the were to to be performed. Howeve prefessional engineer, requitered in a state is deemed to be a 'repatered prefessional engineer" within the seems of this standard were approving danger for teamfactured processive systems" or "about the da le be used in intervisie commerce.

Sheeting means the members of a shortes system that retain the cares in and in turn are supported by her members of the sharing system.

Shield (Shield system) money & revenue that is this to withstand the as impered as it by a arro-is and thereby protest employees within the streams. Shields one be permanen: perceble and moved along as work progresses. Additionally, shields can subst promountained or job-built in gancy opposed to the gancy person (cile) Spings mad in tempers and called (cile) or second contract of the second

Sharing (Sharing system) means a service as a mount by drawite. banical or timber shoring system that supports the sides of an exegues:

Sides See Trees."

Sloping (Sloping system) means a school of processing amployees trans cave-ten by encavering to form sides o a construction that are tactioned away from the exervence so as to prevent seve-ins. The angle of incline required 10700 4 0070-16 76500 mth differences in such feature as the soil 1790, coverencessal conditions of sure and application of suresure

Stable real means natural solid marai meteroj that can be exceveta His vertical sides and will remain latest while expessed. Unstable rock is dered to be seable when the rock nartal on the side or sides of the reproduce is someon against envingtest by rock balls or by cook protective system that has been designed by a registered professional

Streetered ramp mount a ramp built read or weed, usually used for venicie comes. Ramps made of soil or rock ar net considered (Commissi remps.

Support system moons a structure sent so underputate, brecase, or shorter, which provides support.

excenence of the signs of ele

Tobusted data means tables and charts approved by a registered professional engineer and used to design and construct a protective eyetem.

French (French excession) makes a carrow excession (us release to the length) made below the surface of the ground. In general, the depth is greater than the width but the width of a greater than 15 feet (4.6 m). If forms or other are then are unusided or resourced in an excession so as to reduce the dimension measured from the forms or surreture to the side of the excession to 15 feet (4.6 m) or less (measured at the bottom of the excession), the excession is also considered to be a creater.

Trench box. See "Shield."
Trench shield. See "Shield."

Uprights theses the vertical members of a vessel sharing system placed in contact with the earth and usually positioned so that individual members do not contact each other. Uprights placed so that individual members are ciscoly special, in contact with or interestructed to each other, are often cailed "shorters."

Water means herizontal members of a shoring system placed parallel to the extervation last whose sides bear against the verseal members of the shoring system or earth.

§ 1938.461 General requirements

(a) Surfece commirmons. All surface encushreness that are leasted so as to crease a hazard to employees shall be removed or supported, as assessary, to safeparté estpisyees.

(b) Underground installations. (1) The estimated leasting of utility installations, such as sever, telephone, fuel, sinciple, were lines, or any other underground installations that reasonably may be expensed to be ensembled to determined prior to opening an experience.

(2) Utility companies or owners shall be contained within cotabilated or customery local response times, advised of the proposed work, and asked to cotabilate the inaction of the utility underground installations prior to the start of actual excurvation. When utility companies or owners examet respond to a request to leasts underground utility installations within 24 hours (unless a length period is required by state or least law), or exampt cotabilet the exact least of these unstallations, the

econgrable means to locate unity

(3) When excavation operations approach the estimated location of underground installations, the exect location of the installations shall be determined by sale and asceptable means.

(4) While the excavation is openunderground installations shall be protected, supported or removed as necessary to saleguera employees.

(c) Access and agrees—(1) Structural remps. (i) Structural remps that are used solely by employees as a means of source or oppose from annovations shall be designed by a compensat person or oppose of equipment shall be designed by a compensat shall be designed by a compensat parson qualified in structural design, and shall be conserved in accordance with the design.

(ii) Ramps and runways measurated of two or more structural members shall have the structural members connected topother to provent displacement.

(iii) Strangeri members used for rampe and recursys shall be of uniform thirtness.

(iv) Clooks or other appropriate means used to estimant regovey expensival members shall be attached to the bottom of the regovey or shall be attached in a memory to groves. Thesian.

manner to provent tripping.

(v) Structural ramps wood in You of stope shall be provided with elects or other surface transments on the top ourface to provent aliquing.

entions to provent alipping.

(2) Mouse of agrees from creash expressions. A stateway, ledder, ramp or other ends manus of agrees shall be leasted in trush exervations that are 4 fast (1.52 m) or more in depth so so to require up more than 25 fast (7.52 m) of leasted travel for ampiorses.

lateral travel for employees.

(d) Exposure to redirector craffs.

Employees exposed to public retirector
traffs shall be provided with and shall
week, warring years or other retirits
perturbs marked with or made of
referencement or high-rightity material.

(e) Exposure to fulfille tends. Mr.

makens of the contents of the contents of the contents.

(c) Expresse to fulling leads. No captoyee shall be permitted undermost leads handled by lifting or digging equipment. Employees shall be required to stand every from any vehicle being leaded or unleaded to aveid bring execute by any epillage or falling movertals. Operators may remain in the cabe of vehicles being leaded or unleaded when the vehicles are equipmed, in amortaneous with § 1930.071(b)(0), to provide educate presentes for the operator during

possible the grade should be away from machanical signature or stop logs. If the operator does not have a clear and direct view of the edge of the approach the edge of the approach the edge of the approach the edge of the scenario special state.

(g) Hearrows atmosphere—1)
Teeting and controls in sedition to the
requirements set forth to respect D and
E of this part (20 CFR 1928-30-1928-107)
to prevent exposure to harmful levers of
atmospheric contaminants and to secure
acceptable authospheric conditions, the
following requirements shall apply:

fallowing requirements shall apply:

(1) Where expend deficiency
(atmospheres containing less than 19.2
persons expend or a hazardous
atmosphere exists or could reasonably
be expected to exist, such as in
excessvations in leastful areas or
excessvations in areas where hazardous
substances are sucred assrby, the
atmospheres in the excessvation shall be
toosed before employees exist
excessvations greater than 4 feet (1.22 m)
in deasts.

(II) Adoquate pressutions shall be laken to prevent employee exposure to atmospheres containing less than 19.5 persons expopen and other hazardous atmospheres. These presentens include providing proper respiratory protection or ventilation in accordance with subparts D and E of this part responsively.

(III) Adequate presentes shell be taken such as providing vestiones, to provent employee exposure to an emosphere consuming a emocentration of a flammable gas in excess of 20 persons of the lower flammable limit of

(Iv) When controls are used that are intended to reduce the level of atmospheric contaminate to acceptable levels, moving shall be encounted as often as economy to recure that the atmosphere remains safe.

(2) Emergency researce equipment. (i)
Emergency researce equipment, such as
broaching apparatus, a safety harness
and line, or a backet seventher, shall be
readily evallable where harneste econsupplieric annillions exist or may
reasonably be expressed to develop
during work in an examption. This
equipment shall be exceeded when in

(III Employees entering beil-bottom pier beies, er other sentiar deep and confined feeting expressions, and) wen homes and allfalles comment

TO SERVICE OF SERVICES OF SERVICES OF we now have see -(3) Schweitz perso

a seed led for dawn policy -P of Perender or per A (vi) AN MARKET BAY

odi med bereite vi odi si sa sa sa material odi ed basediran sal sa sa salema ad tal manage P OFF PRINCES OF نجيما ه berg benessger A (III) so abon sides of al ambresso self (ii)

A BANKE IN intery of employees and the conbillty of

analor agains bestiering of toe Sadi os dans analogs transper A (1) analos of behroom & generalizable. o seed or personal man of the medition pateter. A feet be proposed to seaso adi la lovel ad weled antisvant (5)

TOLONGE: door to relitates ats servers at babwers of liab principality to general AN INCHES SERVICE AND anniation miscrams (4 bemplater) buildings, wells, or other strangers to Where the statetty of select

(1) TARREST PER (i) Stability of car (BKS) of the com has (f)(4) separated for manige as served temespass a ve seknopen. as enaper him caust resad and has de madernand assertion

act of temacine area odl in sysamet STRANGE OF PER SPECIES od garnino met mere maken meren to seems of here more distance to the MOST) WHEN CHANGE IN COMMENT INVESTIGATION

and sormed amongs to be described and the sound of the so od linds umbrues bes temptieps DATE OF THE PARTY OF THE Des Processi SOUND TO SON OUT LE SERVICE batevers to ballerann at surev Il (5)

of a salety bareaus and Molina the level of semisimes weres, or take Serence of Loveston reside Animals Series tociore of emittys binids to modeus indes sheinel hives ter ann amit Asse dire The Visiges adove seek maiere di Tracuman accamasore all' Saturds peece by wells temperatelles. o present sessent sessent of BALAI BOOD WAS LAAB MANE SIRUBIDI WALLE WELL IS SECTIONS BING BILL A SESTERATION WITH SECRETARIES IS

A WALL SHOW A REDUSTANT A STOW HAS LAND WAY NIGHT (1) WHITE BEEN COMMERCIAL (1) when we would be AND THE PROPERTY OF THE PERSON

cavered. Upon completion of experience. FIR thefte one that he berreaded or Aller IA Amaderia to because Therefore lis is bebrieff of Lists in Artist merced exception (%)

behiven of links of parallised to green over cases with the season ----Me W (1) 🖚

men Tel (i) spine to ceres day safety. most ovad and حددها ادد ad and bown of Lade meyel -MAL IN 1600 TA APPL tellure of protective systems, her to enstantial ai-even old or himse had: gottomin a he day Di BON THE REPORT (E)

37 4400 4 500 100 the stranger solopies U) BOOK! manuscript posterior part the be sade that every retenting or اللا لأن بفائل أهج conducted by the component and as nonconfidence As inspection that he A OF SHAPE LEADING processor eveness beaning to orning to contrading an over ry at theser blace tods mobseth 170 THE IN SECTION a ye show of links asserts overser to alon tenents the sentences in (2) Proboundary (2)

Special of both if sements. Te to annual time commences, or by the security or equipment haven et tanbiller ens tadt sentrab gainterer the of tenentation or by the use of n aletraten dem gebest ben ed: gerif (m. 79.) 1001, 8 1000 is mengupo passed of bahaven of last mesoner der er reffer we pallie To branch a weed blows tods kengalismps TO SACRETAGE WARRY TO BOLDWARDE. most becomeny of linds coverigns (5)

STATES SECURIOR shreet tadi anone miso to dormi sa the focus to seep and contain falling SO Transcent to alerthis to enhanced ev matery to mutationed Marmage presi prager of palitue to latera חבבו במושפו לושב לושבה ביות המושב במוחב במ as mort sailion se sailiel yd brasari COM 10000 HERE OF SOUL LABOR COULE SOUP 6 see to less meters of bearing of field Des er seel (1) Adequate pretocues Con morning to make the

Armera dans to segaine eldinos; adi met meralami mares di baberer.

(9) Identafication of the literal of use the details of use 1179 Was man analy motels & --movement of he solvedbeath! (A)

4) to the electrical finds have grown as at he hade stab benefation of? (II)) ده نماشه محا شودی sessions of made 52 berseint of links amatory g a deta. (1) Designs est stages of stages

in ab a li A september of dried too de sandiben of fire so at theil be describe meand has printed and sometime. olderedle has an ah aldows grass emergy/ees has a grantel A has A malon to metioneration (2) material (2)

audi at 8 atheogy. at less D ogy? wi an stools of der ma 18 de Lema configuraciones tales à belliff of this section, that he Agreement at believen some (9)

spinyer mes one of the other u finiseered of med ber SATES OF LABOUR SED OF ME THE RES PER SEAL PROPERTY. 90% M In as is begin to had assert at an arr (i) Tables per supp

0/00-40/0-(1) may (1) wordled as follower MD PRINT OF IN THE STEELS CAN WE ASSESSED ON IN AN ATLANTA to manufacture of the second of lasts has sempered the to write Personal beat beatings of 事なす THE STATE SALES de affi of chapter and remains

matrices of all betterm soligies and al bemorem of Tidentes laces to behavior the table And organic impacts in the culture of the J oved hade semiste oversett (2) to traine tes es permetal cave-un

M på e comment haven blane to maintenance has droped at (affil.) sal & and and ove sembovenia [U]

TO THE MAN WINDS SAME OF MEDITALIST (1) (c) or (c) at this seems except where TO FIRST AND SOMEON OF PRESIDENT STILL SARAMEN MEMBERS ES AN ST Semester of last sources A P. SPINISH COAS (1) AMAGENTARY el mortoleres de estadore (s'

Greek of Street, Street, 5

TIED BU DE

שנת שנפשת (השכחפש demage or defects that magni mo egemeb

IDENTIC BIN 1850 WEREEN & EL BOS edi dirw insistance si tedi tennem e n: penistare pue pern eq fiets bas sismsism beumbalensM [5]

empioyee exposure to betruck Templatures of the meautecourt.

IGISSOS & TO GOOD OF CHANGE OF CHANGE

PFE

سد ملور

MY (E)

A sed there ere no undications

on to sheet list out set bes

I Alus Ing Potential of Hotel

Hodder s je sledens oft je t

sti weled (m Il.) seel & met w

amoires rangent to lavanare ods de

1930) services linde guillideal (IV)

printages of he emile! of

western Members shall be referen

noustranes of the sales of the exception

14.00 PG 10 AUG

no lement the

pergress from the bottom of the

besiden a banjeb men

der of the liads a

bes is much link broman (v)

Marry magger oil as become about

3 level a of Latestan to and

JOJ STUDIESTADO POR

2018ABST 10008 M

algressed to sales

BUT AUTO OI COM

3001 Gt B81500

שמש פו ושומותי

Tue:tipps suifee siegt

--:uses et emilet ed liede et

IN INDOCEST LEMBARY DIS

ned these which these member:

nogers to enderse lastivibel (M)

TRANSPORT THE COLOR TO THE COLOR

sliatent of Made emerge Fraque (4)

to ensurem (i) Members of

austrian e de panandes per perseran

bed indes toposphisms to lead their better their best their best and their best their better their best the best the best their best the best their best the best the best their best the best the best the best their best the best the best the

soft and side sol eldalure servicing

el side el tanamplante se larretam adi

demaged, a competent person tatal

of the said authorate so; post of

Ameri severa weeks periodina og n

to besidence to! Tilldaline all esaulave

ans impreguipe to latteram edi seamane

st to absol behantal oil moques

Anibile resvers as malages be

pared brakes beneg

and removed in a manner that protect.

folling, historica or other products big

support systems shall be securify

to investe and maistinated (a)

TOTAL IS POSSIBLE

THE PROPERTY OF

moieys repport system.

component or from point surect by

STIOL BILL I SHOWN OF BEEN

TEDIELLE SANDSIGES SOJ POEN IBBESINDS

(1) When meteral or rempment to

Beilly Silbers seass semissinus ser will bewells so time the JANGO OL MEGE DY UNE MERNISCIUTE TCOMMENCALIONS. SAG LIMITEUOSS. (ii) Devietion from the specificational

can or aidalisve cham od links very data may be stared off the jobella, but a ald sell ist volla Aller dan time this at the jobotte during construction of the enel asimu ai ed liade enedalizii bas the specifications, recommends of menulecturer a approval to devices (rom bas anoustimit bas snausbassimore: anousofines a sewissiumaM (in) TRACICAL

because of links emalege evitoerere inveceme abield systems, or other (3) Option (3)—Continu uning other

at od linds atab botalodat aff (ii) tabulated data, anali as tables and dily mastroops at 96 bas mon

ed to its shoulded has send service.

that affort the selection of a protective gamello) sol (A) enstanged of the potential

mish men men mersh maiere

to see to attend out to antiantistable (5)

YOUR OF MODERNIOUS TRESORY

30 99

betained out to your one seed SA (iii) Anah odi men) on of a brocody's system des ineme: s garden at year off bus of Tree

edi ei eldeliove abaze ed liade atei HOT PORT I COME OF FREE ed you atch out cent tody walls a evinencia edi la nei overings adm to dol nat is bonic beningen såt solli

mades o Aq y i i al Oblas I shar a 440 77 M (1) NO.

particular o de il

611

SEN SHIPM IS OF EACH **a** (H)

n without things on ha our po da

o per manage (7) off or eldelerys show of links a let od! No berois 100 per 1 may 200 ab adi amit tadi wild of the processive of that stade of 16 bears m od lied. (iii) At least one copy of the dos

noge ils som constructs at od limbs geab betalods? that are drawn from manufactures to special or state protective systems Design of support systems, shield MAN CANADA

Seigl ampiend-(5) among (5) A Air nantrumes at od links or ed seases etab hotologal s'ww

serbit man --in this of D has A small PAT DES SOCIEDAS DO EL POURENDISP

men al parade redmit

principle of it in 40 (cX3) designation

pergraph (cXX) on in the element

out of baservance has betreion of liad: Designs of support systems shield systems, and other protestive eyes

(c) Design of emplore systems, shield

the slope is being constructed. After that

alidw strade; and to bematanam od lieds

(iii) At least one copy of the design

PERSONAL CONTROL SERVICES

benetiges of the registered

(II) IFE CONTENTION OF [II]

BOILD TROUBLE

entransed to be set for the perturbes

innessalere beminiger a Té beverque

od linds mottoon sidt to (d) darmers c

(1) or Option (2) and (0) under

mougo gainlius see emerce gainseed

professional engineer (i) Sloping sad

an or sidelisve sham of lians at at

מתעום כפעום בחכת פנן תום שנפנינתם

Benelatan atu asilunabi dolma atat

tioned off the jobette, but a capy of the

ed yam alab an seu tan rails assey be

sited of an is bemained of uses sist

ed bevorgge one seemens tenoisseions

בסעובבן ופופכחסם מן ש שנמופבחגה פגפופם:

a garage to tock the bis of Tassaten so

You so notismoter Trotansign ??

becauses out to your one seed to lit.

TOTALE WOLD ATTALEOS

Denoisige o To Agreed--(1) mouto (1)

(ii) Designs shall be in avrittes long:

name and other promestic state

el **anda Lianamos de**l el elégistrak

obest a test seed be made

and to od ton boon agreed out sat!

the off at an Athal despend

lel ee (1)(2) sermane

on all this manipulation

ind the mysical

2000 SAME IN (E.X.S.) J PM T teriesed then these مكملا كو تو محد A Card & Des 10-(1) mand() (1)

M bossie

and and sook in the *** -Willer te

A COS COS COS COS COS COS COS COS COS 44 and 44 is see 44 less (a) less 4. ----240

in the said CASSESSION DESCRIPTION OF PERSONS at the late of the see has baser sidestress : THE -M 171 W 400 ---the ten on bread it -PPM alf ages (1)—animalique la

N | 10 TANK 100 M

(a) Contra Sent Complement

S Amples of A mineral A

binish off in emitted off woled ed med has he seel alderson a he maps at desert adt allem aventration depth of the green, and there are no Bel od tol betalesten servel adi suser rang of liads blaids to member but only if the chick is desired ad wated (m 23.) seel 5 mad watery see lovel a ti larathe draw to conservated Additional repersons for thirds ---

Allester breez m bover at bowells of ten links moveletal (vi), believes gained see skinks and we skinks.

made teneral is beautiful as the beautif my and Marks survey **(m)**

أدنعها أمعطم ad: al bioles of the services and he serve

water to largest to the water of the a at beliarem of lines abloid? (U)

mainty of interest the system of burn, so the al barroldes of see lads emajors biolic (1) Served (1) Connect bloods (1)

Pulleg, or eliding maierial er oquipment. gailiel to brasad att med betreifer, TIGURDADAD OTO BIOVO! TOWO! A.C. SESSIONERS EXCENT MAN CARPAINERS AL SELEVELORE EL TOTAL EDGTE CLICE work on the faces of sloped or beached at bemierred od ma lians seevoign. America Supposed by angole (

adi dire betallismen Tramb ed liad. moret marres a la maladada (U)

among to (aft Mr) (M) (as) or a of extension seek over day, silly TIPE . Valu

8 1 AND STATE OF

POMER 7 00L Y 0 900 أحناء ٣Ò٩

to comment has the proper one of a country to be present the property of the country of 787 777 d week mean for I of table in the same in

iis ma --) **|**

نظ جمثان n jari s dan b -

ه الا الحلة ها طبقة هذا ها s make street to have sever ---رمنعهم فلا

400 a les mas aviv bibles or married by n state W -

10 MP ... p) q

the day on the -40 r down in **100** 000 7 water sell, who cannot the break to Albei To general year dight a day leas to Albei

* the tree is an expense of the second ness a 44 marger han on enterna the sales of best a tennes here best

Property descent Standards from MAN TO MANAGE AND THE STREET (ADZU) St. CESO demand (ATTEA) demand geben. Bereiten D abad bedart aff anito me

Action of this expension. The fall of the fall of the second control of the second contr ¥ (2) T THE 100 E . ALD MALL A MARK A MARK A 7 14 pay of body money the feet free dead A

The same man man mander bed cont and with the state , o desse al list and the comme Pirt on a pe

Les Bow ton a debit of some list. Tel bostometro est men il an MINE INTERNAL BAL A LAMP

morry brayel depole of the state of the con-latery can be been d rock that it and rachle, or

desires mort hors to have be . Person Personal Superson of the Co.

نفاو **8** m

software to the live bet 961 بالغة و الغة و

in the sed EV (1944) leaders can at it bolloosis of assertable bisses less orti sam gab yanyal sai sender massya baseyal mai mai yansa sani sepia a sa ambaransa ---Award dat to part of a named. ---

MA COL --w many and wat in -and the pass and had (vi)

cond: serme dans hademath (mi). D sept as because of securates bissen dails And the bear . 4 ---الأحصلة بنط well (elected to even) معا عملة اعطونوي

TO THE PERSON IN STREET basilemen as Giv las eri DE

jo dii and a st believes of at it supported FIGURE ST BRIDGE & LEISTERN SAT (V)

S MAN OF THE PARTY OF THE PARTY OF or imperiors and to spoke a ma anderesser of the de stored of smen moters bears! Assess a be man at less saft fall

mediately temperated most and box off (Bi)

RITTLE MINERS IN ABOVE AND ARREST (TOPIC) grent and serious at these saft (in w many of her off (!)

TI V MALL P

The A Harris S. C. L. SACTIVE IN THE LE CASON IN MAN PAR -WIG. AND ARREST PAY MANN AND ARROWS THEFT


The state of the s


The state of the s


Trember Statement. To district the con-


Appendix 8 to Subpan P

Comments of the control of the contr











med Verdeally Sided Lewer Pa B & Foot in Dopth

THE ROTE WHERE INCH IS FOR IN COME WHICH HE M stad have a



B LL Free In De

ith here versiably sided beaut parties. Freeze cases excess so beauty size.



Separad or Shielded Vertially Sided Laws Parts

Parenti Laye In

I-8 3-84 TABLE SLOPES


| (-06) JADTAZV (-52) J: 4\£ (-65) J:#J (-36) | STABLE ROCK TYPE A 121 TYPE B TYPE C |
|--|--------------------------------------|
| FOR EXCAVATIONS LESS THAN 20 FEE | מסוד מא אסכא ועםE |


MOTES

- I. Numbers shown in parentheses next to maximum allowable slopes are angles expressed in degrees from the horizontal. Angles have been rounded off.
- A shore-cerm maximum alluwable slope of I/2M:IV (63°) is allowed in oxenvations in Type A soil that are 12 feet (3.67 m) or less in depth. Shore-cerm maximum alluwable slopes for excavations greater than 12 feet (3.67 m) in depth shall be 3/6M:IV (53°).
- 3. Sloping or benching for excavations greater than 20 feet deep shall be designed by a registered professional angineer.

the sample of the second of the second party of the second second

and in ways in water termination in the state of the state of the section of the state of the st







Total height of vertical side Support or spield system 9

Votted fided Land Anderson and the construction has

The state of the s





Color Charles Property Color Charles Color Charles Cha

MATCHES STATES S

ATTACHMENT J TRUCK LOADING

SSP: Sauget Landfill DATE:02/16/95 PAGE 58 OF 62

TRUCK LOADING

- If drivers must enter the exclusion zone, they must have the proper level of HAZWOPER training.
- Personnel covering the load must have the proper level of Personal Protective Equipment. The specific level will be contaminant specific. The Health and Safety Manager should be consulted if the level of PPE is not designated in the Health and Safety Plan.
- Proper equipment must be provided to personnel for getting in and out of the truckbed for lining and covering (ladder, etc.).
- Proper equipment and experienced operators must be utilized for loading trucks.
- The load must be centered and evenly distributed on the truck.

ATTACHMENT K SOIL SAMPLING

SSP: Sauget Landfill DATE:02/16/95 PAGE 59 OF 62

SOIL SAMPLING

- Proper level of Personal Protective Equipment is required. Sampling would not be conducted if a hazard did not exist. If the level of PPE is not designated in the Health and Safety Plan, the Health and Safety Manager must be consulted.
- Specific sampling protocol for the contaminant must be must be followed (grab, 95% sampling).
- Proper ergonomics should be followed when sampling—bend at the knees, not the
 waist.
- Prevention of cross-contamination is important when sampling; therefore, methods to prevent it should be addressed.
- Proper shipping of samples must be addressed. Consult the Transportation and Disposal Coordinator or Regulations Compliance Manager for assistance.

2.1.14 Hazards and SOPs associated with Soil Sampling:

Hazards:

- 1. Contact with or inhalation of contaminants, potentially in high concentrations in sampling media.
- Back strain and muscle fatigue due to lifting, shoveling and auguring techniques.
- 3. Contact with or inhalation of decontamination solutions.

SOPS

- Proper awareness of chemical contaminants and review of suspected contaminants should be completed and implementation of adequate protection program as well.
- 2. Proper lifting (pre-lift wight assessment, use of legs, multiple personnel) techniques will prevent back strain. Use slow easy motions when shoveling, auguring, and digging to decrease muscle strain.
- 3. Material Safety Data Sheets for all decon solutions should be included with each Site Health and Safety Plan.

| SSP: | DATE: | PAGE | 53 | OF |
|------|-------|------|----|----|
| 38 | | | | |

Revision No. . . Cate: -/1.86

-.9 SOIL SAMPLING

-.9.1 General

The objective of this section is to give general guidance for the collection of soil samples during Branch field investigations. Guidance for preparing soil sampling protocols, including statistical sampling methodology are included in the EPA publication "Preparation of Soil Sampling Protocol, Techniques and Strategies" (22). Specific standard soil sampling and field techniques used by Branch personnel are included as Appendix H.

4.9.2 Sampling Location/Site Selection

Areas selected for soil sampling shall be strategically located in order to collect a representative fraction of the soils with the minimum number of samples and effort. A surface inspection of the subject area shall be made to locate pertinent features (e.g., rock outcrops, drainage patterns, surface runoff, ponds, lakes, wet areas, seeps, springs, permanent structures, fill areas, erosional areas, etc.) and to evaluate the relationship between these features and potential sources of pollution. The location of sediment depositional areas are good indicators of surface runoff direction. If the direction of surface runoff or drainage is difficult to detect, observation of new deposition or sediment movement following a rain may prove helpful in establishing this direction. The spreading or fanning out of the sediment body will indicate direction of flow.

In most instances, the first investigation of a site will be a reconnaissance type survey. Soil sampling in these instances will generally be confined
to surface or near-surface soils and/or sediments with hand equipment. For
screening purposes, sampling of this type should be conducted in depositional
areas on the periphery of the study area, primarily at the downstreas or downgradient portion(s) of the area of interest; however, an upgradient location
should also be selected for obtaining background and/or control samples. Investigators should be aware that sampling in depositional areas tends to bias the
sampling toward elevated concentrations which is useful as a screening tool, but
should not be construed as representative of the area conditions.

More in-depth investigations are usually conducted after a preliminary study or reconnaissance survey has been completed. Review of previous investigations will aid in selection of suitable sampling locations and these studies should be examined when the study plan for the more detailed study is prepared. The number of samples and the number of test pits and/or borings and the specific depth that samples are collected will vary according to the site conditions and the scope of the investigation.

Section (a. 1.9)
Revision No. 1
Date: 4/1/86
Page 2 of 4

1.9.3 Equipment Available

The indowing Branch equipment is available for field use in soil sampling: stainless steel spoons; stainless steel hand augers; stainless steel shovels; Shelby tural; portable power augers (Little Beaver²); stainless steel scoops; glass pan; and drill rigs and associated equipment (i.e., split spoon samplers) which may to occasion be rented or borrowed for special projects.

-.9.4 Saleling Techniques

1.9. .. General — Sampling is often conducted in areas where a regetative turf has sen established. In these cases a clean stainless steel shovel should be used to circiully remove the turf so that it may be replaced at the conclusion of sampling. Then the soil sample is obtained, it should be deposited into a glass pan for a xing (or compositing, if applicable) prior to filling the sample containers. Axing of the soil sample for chemical analysis should be performed in accordance with the procedures outlined in Section 4.6.3.3.4. If an undisturbed sample is needed, the Shelby tube sampler may be used as described in Section 4.9.4.2.

If practical, and at the project leader's discussion, all trenches or holes that were excavated for sampling should be filled in and the turf replaced.

- 4.9 4.2 <u>Surface Soil Sampling</u> Prior to sampling, leaves, grass, and surface abris should be removed from the area to be sampled using a clean stainless stati apoon or shovel. Surface soil samples shall then be collected using a precleaned, stainless stael scoop or spoon.
- 4.9.4.3 Shallow Subsurface Soil Sampling Shallow subsurface soil samples may be collected by digging a hole of tranch with a stainless steel shovel, then removing all of the loose soil and collecting a sample at the desired depth using a stainless steel spoon, a stainless steel hand auger, or a Shelby tube.

The stainless steel hand auger consists of three basic parts: (1) the bucket, (2) extension, and (3) handle. At the bottom end of the bucket are two cutting edges. The extensions are three feet long. When sampling deeper subsurface soil (Section 4.9.4.4), a number of extensions may be joined end to end to increase the depth from which soil may be sampled.

The Shelby tube is a stainless steel tube approximately 12 inches long and 2 inches in diameter. One end of the tube has the edges beveled into a cutting edge. The other end can be mounted on an adapter which allows attachment to the end of the hand auger. The Shelby tube is pushed into the soil to be sampled and then removed. The tube can then be removed from the adapter and the soil pushed out using a decontaminated piece of equipment such as the handle of a stainless steel spoon. If an undisturbed sample is required, the Shelby tube with its sample factor may be chipped directly to the laboratory for analyses.

4.7.4.4 <u>Deeper Subsurface Soil Sampling</u> — For deeper sampling using hand equipment, a stainless steel suger (see Section 4.9.4.3) is used to hore a sampling hale intil the desired depth is reached. Another clean auger bucket or a

Revision No. . . Date: -- 1/85 Page 3 of -

Shelby tube is then used to collect the sample which is placed in a glass an as described in Section -.9.4.1. Surface debris should be removed from the location of the sampling hole using a clean, stainless steel shovel or spoon before augering operations are initiated.

Often the depth which can be reached using a hand auger is limited due to the soil having low conesion which leads to the hole collapsing or to the soil being very tightly packed which can make turning and removing the auger difficult. In cases such as these, a portable power auger Little Beaver may be used to reach the desired depth. The sample can then be collected as described in the previous paragraph. The portable power auger consists of an powered drive unit (hand-held) used by sampling personnel to drive crew-like auger flights. The auger flights should be cleaned using the same procedures as for the other soil sampling equipment (Appendix B). For safety reasons, the Little Beaver portable power auger should never be used with less than two sampling personnel present.

The split spoon sampler may be used for sampling at greater depths. Because of its weight, the split spoon sampler is generally used with power equipment, i.e., drilling rig. A hollow stem auger is used to advance the hole to the desired depth. The split spoon is added to the correct length of drill rod and forced into the undisturbed soil by means of a 140-pound weight or hammer. The split spoon is retrieved from the hole and opened to reveal the sample. The top two or three inches of the sample normally will be disturbed and should be discarded. The undisturbed portion should be placed in a glass pan by means of a clean stainless steel spoon or spatule. The procedure is repeated until the desired amount of sample is collected. The sample should then be thoroughly mixed.

4.9.5 Special Precautions for Trace Contaminant Soil Sampling

The procedures outlined in Section 4.2.11 shall be followed. All soil sampling equipment used for sampling for trace contaminants should be constructed of stainless steel where possible. In no case will chromium, cadmium, or galvanized plated or coated equipment be used for soil sampling operations. Similarly, no painted equipment shall be used. All paint and primer must be removed from soil sampling equipment by sandblasting or other means, before such equipment can be used for collecting soil samples.

4.9.6 Soil Samples Collected for Purgeable Organic Compounds Analyses (VOA)

Soil samples collected for purgeable organic compounds analyses should be thoroughly mixed and containerized as soon as possible after sampling. The sample should be placed in the sample container so that no head space is left in the container after the container is closed.

4.9.7 Specific Sampling Equipment Quality Assurance Techniques

Drilling rigs and other major equipment used to collect soil samples shall be intentified so that this equipment can be traced through field records. A log book shall be established for this equipment so that all cleaning, maintenance

Section No. -.? Revision No. . Date: -/1.86 Page - of -

repair procedures can be traced to the person performing these procedures and the specific repairs made. Sampling spoons, hand augers, Shelby tubes, and other minor his osable type equipment are exempted from this equipment identification requirement.


All equipment used to collect soil samples shall be cleaned as outlined in Appendix 8 and epaired, if necessary, before being stored at the conclusion of field studies.

Any cleaning conducted in the field (Appendix 3) or field repairs should be thoroughly commented in field records.

-.9.8 Auxiliary Data Collection

In addition to information pertaining to an area or specific site/location that may be available in EPA files from previous investigations (i.e., site screenings, tater quality, well monitoring studies, etc.) information and data may be obtained from various city, county, state, and other federal agencies.

A system of logging all pertinent data collected during drilling and sampling operations should be maintained. The test hole locations should be recorded and remarked to the site map and/or datum base so that each location can be permetically established. Samples should be accurately tagged and labeled with all retrinent site information at the time of sampling. See Section 3 for sample heling and field recording procedures. Also, refer to the section on drilling in the Groundwater Sampling Section (Section 4.7.9.3). The latitude and ongitude shall be obtained for each site for future STORET data entry.



SOIL SAMPLING

GBUESTIVE - TO PRESENT THE DIFFERENT METHODS AND TECHNIQUES USED IN COLLE SOIL SAMELES DURING HAZARDOUS WASTE SITE INVESTIGATIONS AND RELATED STUD INVOLVING RORA AND SUPERFUND ACTIVITIES.

SITE SELECTION

- o MAKE A RECOM OF THE AREA OF INTEREST
- o DETERMINE THE BOUNDARIES OF THE AREA
- OR ANIMALS, GROUND STAINING, LEACHATE STREAMS, ODORS, SOURCES POLLUTION, ETC.
- DETERMINE SURFACE DRAINAGE FLOW DIRECTION(S)
- DITCHES, DEPOSITIONAL AREAS, FILL AREAS, PONDS, SPRINGS, ETC.
- O EVALUATE SOIL CONDITIONS SANDY SOILS, CLAY SOILS, ROCKY SOI!
- DETERMINE THE DEPTH TO THE SHALLOW GROUNDWATER TABLE.
- DETERMINE THE TYPE OF SAMPLE(S) NEEDED COMPOSITE OR INDIVIDUAL SAMPLES
- DETERMINE THE EXTENT OF SAMPLING SURFACE SAMPLING, SHALLOW SAMPLING OR DEEP DEPTH SAMPLING.
- OR BOTH.

DESTINATE THE NUMBER OF SAMPLES MEEDED AND ANALYSIS REQUIRED - S COLLECT A REPRESENTATIVE FRACTION OF THE SOILS WITH THE MINIMUM MUMBER OF SAMPLES.

SAMPLING EQUIPMENT

- o POWER EQUIPMENT SHALLOW AND DEEP SAMPLING
 - A) POWER AUGERS AND DRILLING RIGS
 - 1) SPLIT SPOCH SAMPLERS
 - 2) LARGE DIAMETER PUSH TUBES
 - B) BACKHOE

- a HAND EQUIPMENT SHALLOW SAMPLING
 - A) SPOOMS STAINLESS STEEL
 - B) SPATULAS STAINLESS STEEL
 - C: SDOOPS STAINLESS STEEL
 - D) SHOVELS
 - E) PUSH TUBES (SHELEY TUBES) SHALL DIAMETER
 - F) POST-HOLE DIGGERS
 - G) HAND AUGERS

SAMPLING METHODS

- o SURFACE AND SHALLOW DEFTH (<10 FT.) SAMPLING
 - A) PUSH TUBES HAND EQUIPMENT
 - B) CHUNK SAMPLING
 - C) SPOON, SPATULA, AND SCOOP SAMPLING
 - D) SHOVELS, POST-HOLE, DIGGERS, PICKS, ETC.
 - E) HAND AUGERS
- O SHALLOW AND DEEP DEPTH SAMPLING
 - A) SPLIT SPOON SAMPLING POWER EQUIPMENT
 - B) PUSH TUBES POWER AND HAND EQUIPMENT
 - C) CHUNK SAMPLING BACKHOE AND HAND EQUIPMENT

Site Selection

Areas selected for soil sampling shall be stratigically located in order to collect a representative fraction of the soils with the minimum number of samples and effort. A surface inspection of the subject area shall be made to locate pertinunt features (e.g., rock tuttrops, trainage patterns, surface runcif, poncs, lakes, wer areas, seeps, oprings, permanent structures, fall areas, erosional areas, depositional areas, etc.) and to evaluate the relationship between these features and potential sources of pollution. The locations of sediment depositional areas are good indicators of surface runoff direction. If direction of surface runoff or drainage is difficult to detect. observation of new deposition or sediment novement following a rain may prove helpful in establishing this direction. The spreading or fanning out of the sediment body will indicate direction of flow.

In most instances, the first investigation of a site will be a reconnaissance or screening type study. Sampling in these instances will generally be confined to surface soils or shallow coming using hand equipment such as shovels. post hole diggers, or hand sugers. For streening purposes, surface soil/sediment sampling shall be conducted in depositional areas on the periphery of the study area, primarily in the downstream or downgradient portion of the area of interest; however, an upgradient sample is often valuable as a control site. (Note: sampling at depositional areas tends to bias the sampling toward high concentracions - this is a valuable screening tool but should not be construed as representative of the area conditions).

Following initial screening, more sophisticated investigations may involve the use of power equipment such as drilling rigs or backhoes. The number of samples or test holes and the specific depth of sampling will vary according to site conditions and the scope of the investigation. In general, a minimum of three sampling sites or test holes shall be installed in order to adequately determine subsurface conditions. Test holes or sites selected for soil sampling should be located where the water table is far, enough below the ground surface so as not to interfere with the sampling operation unless the study involves groundwater sampling.

Sampling of undisturbed soils may be achieved by both hand and power equipment. Hand equipment such as spoons, scoops, shovels, hand augers, and small dismeter push tubes are available and shall be used for sampling at shallow depths. Hand equipment is limited even at shallow depths when the soils are difficult to penetrate. Power equipment such as augers and backhoes may be used for sampling at shallow depths when hand boring equipment cannot be utilized. Drilling rigs can be used for both shallow and deep soil sampling.

Shelby tubes or thin wall push tubes can be used with both power and hand equipment to sample undisturbed soils. Stainless steel construction is recommended for most types of sampling. Soils can be extruded from the tubes for logging and selective sampling or sealed and sent directly to the laboratory in the tubes. When using drilling rigs for collecting relatively undisturbed soil samples. split spoon samplers shall be the preferred WSB method. These sampler are made of sceel tubing that will spile open to reveal the soil sample. The

sample then can be examined, logged, and placed in appropriate sample containers. Hollow stemmed augers shall be used when possible in boring test holes to eliminate potential caving problems and contamination from both soil and water. Shelby tubes or split spoons shall be used with the hollow stemmed augers for sampling. If test holes need to be used for groundwater sampling purposes at a later date, well casing shall be set inside the hollow stemmed augers before augers are pulled out of the hole (see well installation procedures in the Groundwater Sampling section of this chapter).

Sampling Techniques

Undisturbed/uncontaminated (Note: contamination in this context refers to the introduction of foreign materials into the sample through collection methodology) samples of surface exposures such as road banks, creek banks, shallow soil horizons, test pits and tranches may be obtained as push tube samples and "chunk" samples. A push tube sample is collected by pressing or pushing a tube firmly into the soil until the tube is full of sample; the sample is extracted by digging to a depth below the sample, while making sure that the sample is not disturbed. The sample is cut off at the bottom of the tube with a showel or knife and removed from hole. The sample may then be shipped to the laboratory or extruded and placed in sample containers. A "chunk" sample is obtained by smoothing the ground or face sufface to remove any disturbed soil, and marking the outline of the chunk to be taken. A tranch is then excavated around the chunk. The chunk is our off with a knife or trowel, trimmed, removed from the hole and placed directly into the appropriate sample container(s) for shipment to the laboratory (19).

Another method of obtaining an uncontaminated (see previous note) soil sample from the soil surface is to use a spoon or scoop. Shallow depth samples may be collected by digging a hole with a shovel, then removing all the loose soil and collecting a sample at the desired depth using a sampling spoon.

For deeper sampling using hand equipment, a large diameter auger is used until the desired depth is reached. A small diameter auger is then used to collect the sample an undisturbed sample is required, a Shelby tube can be placed on a sampling head connected to the correct length of push rod and pushed into the undisturbed soil. The sample is extruded, the portions that are disturbed and/or contaminated are discarded, and the remainder is placed in the appropriate sample container(s). The Shelby tube and sample may also be shipped intact to the laboratory for analyses. These procedures shall be repeated until the desired number of samples are collected.

The split spoon sampler is used mostly with power equipment because of its weight. The hollow stem auger is used to advance the hole to the desired depth. The split spoon is added to the correct length of drill rod and forced into the undisturbed soil by means of a 140 pound weight or hammer. The split spoon is retrieved from the hole and opened to reveal the sample. The top two or three inches of the sample normally will be disturbed and should be discarded. The undisturbed portion should be placed in a sample container by means of a clean stainless steel spoon or spatule. The procedure is repeated until the desired number of samples are collected.

Sediment samples can be obtained by means of grab sampling. This method consists of collecting sediment in a sample container by scooping or by using

a spoon, small showel, spatula, jar, or bottle to place the sediment in the container. There are also various types of mechanical samplers available, especially where sestment sampling in water is required. Refer to the section on surface water sampling in this chapter for information on sediment sampling equipment and techniques.

Specific Sampling Equipment Quality Assurance Techniques

All sampling equipment utilized to collect soil samples including hand augers, split spoons, hollow stem augers, drilling rigs, Shelby tubes, etc., will be numbered so that this equipment can be traced through field records. A log book shall be established for this equipment, so that all cleaning, maintenance and repair procedures can be traced to the person performing these procedures and to the specific repairs made. It should be noted that quality control procedures for certain pieces of equipment, such as sediment sampling equipment, are contained elsewhere in this chapter and that sampling spoons and other minor disposable type equipment exempted from this requirement.

All equipment utilized to collect soil samples shall be cleaned as outlines in Appendix C and repaired if necessary before being stored at the conclusion of field studies.

All such equipment shall be tested before being issued for field studies.

Any cleaning procedures conducted in the field (Appendix C) or field repairs should be thoroughly documented in field records.

Auxiliary Data Collection

Before and after sites have been selected, additional information and data can be collected from various city, county, state, and federal agencies. Most areas of concern to EPA usually have data from surveys or studies that have been previously made. Water quality studies, hydrologic and geologic data, soil surveys, and well monitoring studies are examples.

A system of logging all pertinent data collected during drilling and sampling operations should be used and maintained. The test hole locations should be recorded and referenced to the sits map and/or datum base so that each location can be permanently established. Samples should be accurately tagged and labeled with all pertinent site information at the time of sampling. See Chapter III for sample labeling and field recording procedures. Also, refer to the section on drilling logs in the Groundwater Sampling section of this chapter.

ATTACHMENT L COLD STRESS

COLD EMERGENCIES

On days with low temperatures, high winds, and humidity ansone can suffer from the extreme cold, Severe cold exposure can be life-threatening. Several factors increase the harmful effects of cold being very young or very old, wet clothing, having wounds or fractures, smoking, drinking alcoholic beverages, fatigue, emotional stress, and certain diseases and medications. People exposed to severe cold can suffer from hypothermus or frostitite.

Hypethermia

Signs and Symptoms

The signs and symptoms of hypothermia include shivering, dizziness, numbress, confusion, weakness, impaired judgment, impaired vision, and drowsiness (Pig. 47). The stages are—

- 1. Shivering.
- 2. Apachy.
- 3. Loss of consciousness.
- 4. Decreasing pulse rate and breathing rate.
- S. Death

As hypothermia progresses, the victim may move clumsily and have trouble holding things. In the later stages, he or she may stop shivering.

First Ald

As the action guide shows, call EMS. You should get a victim of hypothermia out of the cold and isso dry clothing. Warm up his or her body slowly. Give nothing so out or drink unless the victim is fully conscious. Monisor ABCs.

Prochle

Prosthing is the most common injury caused by exposure to cold. It happens when ice crystals form in body tissues, usually the nose, earn, chin, cheeks, fingers, or toes. This restricts blood flow to the injured parts. The effect is worse if the frostbitten parts are thereof and then refronten.

Signs and Symptoms

The first sign of frostbite may be that the skin is slightly flushed. The skin color of the frostbitten area then changes to white or grayish yellow and finally grayish blue, as the frostbite develops. Pale is sometimes full early on but laster goes away. The frostbitten part fools very cold and numb. The victim may not be aware of the injury.



Figure 47 Hypothermia

Semperature Extremes Action Guides

Cold Emergencies

Survey the scene Do a primary survey Phone EMS if necessary Do a secondary survey Was the victum exposed to cold?

Type of exposure?

No. Continue secondary survey

Hypothermia

Remove from cold and get to warm place Remove wer clothes and cover with dry clothing or blankers

Warm body slowly

Give nothing by mouth unless victim is fully conscious Monitor ABCs

Procebias

Remove from cold and get to warm place Rewarm frozen part by immersing in warm (not hot) water; do not rub or massage Put dry, sterile gause between warmed toes of fingers

Loosely bandage

For hypothermia, warm the victim slowly. Rapid warming could cause serious heart proble or increase circulation so body surface, causing additional cooling of vital organs. Do not give beverages commissing alcohol or caffeins. Give warm broth or water

should be used when estimating the combined cooling effect of wind and low air temperatures on exposed skin or when determining clothing insulation requirements to maintain the deep body core temperature.

2. Unless there are unusual or extenuating circumstances, cold injury to other than hands, feet, and head is not likely to occur without the development of the initial signs of hypothermia. Older workers or workers with circulatory problems require special precautionary protection against cold injury. The use of extra insulating ciothing and/or a reduction in the duration of the exposure period are among the special precautions which should be considered. The precautionary actions to be taken will depend upon the physical condition of the worker and should be determined with the advice of a physicial with knowledge of the cold stress factors and the medical condition of the worker.

Evaluation and Control

For exposed skin, continuous exposure should not be permitted when the air speed and temperature results in an equivalent chill temperature of ~32°C (~25.6°F). Superficial or deep local tissue freezing will occur only at temperatures below ~1°C (30.2°F) regardless of wind speed.

At air temperatures of 2°C (35.6°F) or less, it is imperative that workers who become immersed in water or whose clothing becomes wet be immediately provided a change of clothing and be treated for hypothermia.

TLVs recommended for properly clothed workers for periods of work at temperatures below freezing are shown in Table 3.

Special protection of the hands is required to maintain manual dexterity for the prevention of accidents:

- If fine work is to be performed with bare hands for more than 10–20 minutes in an environment below 16°C (80.8°F), special provisions should be established for keeping the workers' hands warm. For this purpose, warm air jets, radiant heaters (fuel burner or electric radiation), or contact warm plates may be utilized. Metal handles of tools and control bars should be covered by thermal insulating material at temperatures below -1°C (30.2°F).
- If the air temperature falls below 16°C (80.8°F) for sedentary, 4°C (39.2°F) for light, -7°C (19.4°F) for moderate work and fine manual dexterity is not required, then gloves should be used by the workers.

To prevent contact frostbite, the workers should wear anticontact gloves.

- When cold surfaces below -7°C (19.4°F) are within reach, a warning should be given to each worker by the supervisor to prevent inadvertent contact by bare skin.
- If the air temperature is -17.5°C (0°F) or less, the hands should be protected by mittens. Machine controls and tools

for use in cold conditions should be designed so that they can be handled without removing the mittens.

Provisions for additional total body protection are required if work is performed in an environment at or below 4°C (39.2°F). The workers should wear coid protective ciotning appropriate for the level of cold and physical activity:

- If the air velocity at the job site is increased by wind, draft, or artificial ventilating equipment, the cooling effect of the wind should be reduced by shielding the work area or by wearing an easily removable windbreak garment.
- 2. If only light work is involved and if the clothing on the worker. may become wat on the job site, the outer layer of the clothing in use may be of a type impermeable to water. With more severe work under such conditions, the outer layer should be water repellent, and the outerwear should be changed as it becomes wetted. The outer garments should include provisions for easy ventilation in order to prevent wetting of inner layers by sweat. If work is done at normal temperatures or in a hot environment before entering the cold area, the employee should make sure that clothing is not wet as a consequence of sweeting. If clothing is wet, the employee should change into dry clothes before entering the cold area. The workers should change socks and any removable felt insoles. at regular daily intervals or use vapor barrier boots. The optimal frequency of change should be determined empirically and will vary individually and according to the type of shoe worn and how much the individual's feet sweet.
- If exposed areas of the body cannot be protected sufficiently to prevent sensation of excessive cold or frostbite, protective items should be supplied in auxiliary heated versions.
- 4. If the available clothing dose not give adequate protection to prevent hypothermia or frostbite, work should be modified or suspended until adequate clothing is made available or until weather conditions improve.
- 5. Workers handling evaporative liquid (gasoline, alcohol or cleaning fluids) at air temperatures below 4°C (39.2°F) should take special precautions to avoid scaling of ciothing or gloves with the liquids because of the added danger of cold injury due to evaporative cooling. Special note should be taken of the particularly acute effects of splashes of "cryogenic fluids" or those liquids with a boiling point that is just above ambient temperature.

Work-Warming Regimen

If work is performed continuously in the cold at an equivalent chill temperature (ECT) or below =7°C (19.4°F), heated warming shelters (tents, cabins, rest rooms, etc.) should be made available nearby. The workers should be encouraged to use these shelters at regular intervals, the frequency depending on the

TABLE 3. Threshold Limit Values Work/Warm-up Schedule for Four-Hour Shift®

| | Air Temperature – Sunny Sky | | No Noticeable Wind | | 5 mph Wind | | 10 suph Wind | | 15 mph Wind | | 10 mph Wind | |
|---|-----------------------------|--------------|------------------------|------------------|------------|------------------|------------------------|------------------|-------------|------------------|-----------------|------------------|
| | *C (approx.) | °F (approx.) | Mex. Work Period | No. of Breaks | | No. of Breaks | Max. Work Period | No. of Breaks | | No. of Bresks | | No. of Breaks |
| | 26° to 28° | -15° to -19° | (Norm. Br | r eaks) (| (Norm. B | reaks) (| 75 min | 2 | SS min | 3 | 40 min | 4 |
| , | -29* 10 -31* | -20° to -24° | (Norm. Br | eaks) i | 75min | 2 | 55 min | 3 | 40 min | 4 | 30 min | 5 |
| | -32° to -34° | -25° to -29° | 75 min | 2 | 55 min | 3 | 40 min | 4 | 30 min | 5 | Non-emer | • |
| | - 35° to -37° | -30° to -34° | 55 min | 3 | 40 min | 4 | 30 min | 5 | Non-emer | gency | work should cea | |
| | -38° to -39° | -35° to -39° | 40 min | 4 | 30 min | 5 | Non-emer | gency | work shin | old cease | <u> </u> | 1 |
| | -40° to -42° | -40° to -44° | 30 min | 5 | Non-emer | gency | work show | ild cesse | • | | 1 | |
| | -43° & below | -45° & below | Non-emerg | | work show | uld cease | | \downarrow | | \ | | ↓ |

Notes for Table 3:

8

- † 1. Schedule applies to any 4-hour work period with moderate to heavy work activity, with warm-up periods in a warm location and with an extended break (e.g., lunch) at the end of the 4-hour work period in a warm location. For Light-to-Moderate Work (limited physical movement): apply the schedule one step lower. For example, at -35°C (-30°F) with no noticeable wind (Step 4), a worker at a job with little physical movement should have a maximum work period of 4) minutes with 4 breaks in a 4-hour period (Step 5).
- 2 The following is suggested as a guide for estimating wind velocity if accurate information is not available: 5 mph. light flag moves; 10 mph. light flag fully extended; 15 mph: raises newspaper sheet; 20 mph: blowing and drifting snow
- If only the wind chill cooling rate is available, a rough rule of thumb for applying it rather than the temperature and wind velocity factors given above would be: I) special warm-up breaks should be initiated at a wind chill cooling rate of about 1750 W/m²; 2) all non-emergency work should have ceased at or before a wind chill of 2250 W/m². In general the warm-up schedule provided above slightly under-compensates for the wind at the warmer temperatures, assuming acclimatization and clothing appropriate for winter work. On the other hand, the chart slightly over-compensates for the actual temperatures in the colder ranges, since windy conditions rarely prevail at extremely low temperatures.
- 4 TLVs apply only for workers in dry clothing.

^{*} Adapted from Occupational Health & Safety Division, Suskatchewan Department of Labour

severity of the environmental exposure. The onset of heavy shivering, frostnip, the feeling of excessive fatigue, drowsiness, irritability or euphona are indications for immediate return to the shelter. When entering the heated shelter, the outer layer of clothing should be removed and the remainder of the clothing loosened to permit sweat evaporation or a change of dry work clothing provided. A change of dry work retribing should be granded as necessary to prevent workers from returning to work with wet clothing. Dehydration, or the loss of body fluids, occurs insidiously in the cold environment and may increase the susceptibility of the worker to cold injury due to a significant change in blood flow to the extremities. Warm sweet drinks and soups should be provided at the work site to provide calonc intake and fluid volume. The intake of coffee should be limited because of the diuretic and circulatory effects.

For work practices at or below -12°C (10.4°F) ECT, the following should apply:

- The worker should be under constant protective observation (buddy system or supervision).
- The work rate should not be so high as to cause heavy sweating that will result in wet clothing; if heavy work must be done, rest periods should be taken in heated shellers and opportunity for changing into dry clothing should be provided.
- New employees should not be required to work fulltime in the cold during the first days of employment until they become accustomed to the working conditions and required protective clothing.
- The weight and bulkiness of clothing should be included in estimating the required work performance and weights to be lifted by the worker.
- The work should be arranged in such a way that sitting still or standing still for long periods is minimized. Unprotected metal chair seets should not be used. The worker should be protected from drafts to the greatest extent possible.
- The workers should be instructed in safety and health procedures. The training program should include as a minimum instruction in:
 - a. Proper rewarming procedures and appropriate first aid treatment.
 - b. Proper clothing practices.
 - c. Proper eating and drinking habits.
 - d. Recognition of impending frostbite.
 - Recognition of signs and symptoms of impending hypothermia or excessive cooling of the body even when shivering does not occur.
 - . Sate work practices.

Special Workplace Recommendations

Special design requirements for refrigerator rooms include

the following:

- 1 In refrigerator rooms, the air velocity should be minimized as much as possible and should not exceed 1 meter/sec (200 fpm) at the job site. This can be achieved by properly designed air distribution systems.
- 2. Special wind protective dothing siroug be provided based upon existing air velocities to which workers are exposed

Special caution should be exercised when working with toxic substances and when workers are exposed to vibration. Cold exposure may require reduced exposure limits.

Eye protection for workers employed out-of-doors in a snow and/or ice-covered terrain should be supplied. Special safety goggles to protect against ultraviolet light and glare (which can produce temporary conjunctivitis and/or temporary loss of vision) and blowing ice crystals should be required when there is an expense of snow coverage causing a potential eye exposure hazard.

Workplace monitoring is required as follows:

- Suitable thermometry should be arranged at any workplace where the environmental temperature is below 16°C (60.8°F) so that overall compliance with the requirements of the TLV can be maintained.
- Whenever the air temperature at a workplace falls below =1 °C (30.2°F), the dry bulb temperature should be measured and recorded at least every 4 hours.
- In indoor workplaces, the wind speed should also be recorded at least every 4 hours whenever the rate of air movement exceeds 2 meters per second (5 mph).
- In outdoor work situations, the wind speed should be measured and recorded together with the air temperature whenever the air temperature is below -1°C (30.2°F).
- The equivalent chill temperature should be obtained from Table 2 in all cases where air movement measurements are required; it should be recorded with the other data whenever the equivalent chill temperature is below ~7°C (19.4°F).

Employees should be excluded from work in cold at -1°C (30.2°F) or below if they are suffering from diseases or taking medication which interferes with normal body temperature regulation or reduces tolerance to work in cold environments. Workers who are routinely exposed to temperatures below -24°C (-11.2°F) with wind speeds less than five miles per hour, or air temperatures below -18°C (0°F) with wind speeds above five miles per hour, should be medically certified as suitable for such exposures.

Trauma sustained in freezing or subzero conditions requires special attention because an injured worker is predisposed to cold injury. Special provisions should be made to prevent hypothermia and freezing of damaged tissues in addition to providing for first aid treatment.

ATTACHMENT Z
SITE SAFETY PLAN
SITE SAFETY PLAN
ACKNOWLEDGMENT FORM



SITE SAFETY PLAN ACKNOWLEDGMENT FORM

I have been informed and understand and will abide by the procedures set forth in the Safety and Health Plan and Amendments for the Sauget I and fill site i nave been informed and understand and will ablue by the procade and Health Plan and Amendments for the Sauget Landfill site.

| | Jarstand and Sauge | Land | | Dale | |
|--|-----------------------|--------|------------|----------------|------|
| I have been informed and u and Health Plan and Amen | indersta for the Subs | | | | |
| informed and | dments 100 | | presenting | | |
| been line and Amen | | Re | Drescient | , , | o- |
| I have Joh Plan and | | - | | 3/200 | ? 7, |
| and Health | | | | 3/20/3 | 1_ |
| and | Signature | | 065. | - 3/21 | 193 |
| | 3162 | | B. E. S. | 500 | 715 |
| Printed Name | . // | ' // . | | 7 | • |
| and Name | n - (1/0) | all | | | |
| Printed | I KIN | | XCS | | |
| | 1 | | | | |
| | 1. 21 | مليبده | | | |
| Nach | Vo me De | | | | |
| Rosela 1 | A latter | | | | |
| Basil Nagal | Bajel has | | | | |
| | | | | _ | |
| (2) | | | | | |
| A | - | | | | |
| | | | | - | |
| | | | | _ | |
| | _ | | | | |
| | | | | | |
| | | | | | |
| | _ | | | | |
| | | | | | |
| | | | | | |
| | | | | | _ |
| | | | | | |
| | | | _ | | |
| - | | | | | |
| | | | | | |
| | | | _ | | |
| | | | | | _ |
| | | | | | |
| | | | | | |
| _ | | | | | |
| | | | | _ | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| _ | | | | | |
| | | | | | _ |
| _ | | | | | |
| | | | _ | | |
| | - | | | • | |
| _ | | | | | |
| - | | | _ | | |
| | | | _ | | |
| | | | | | |
| _ | | | | | _ |
| | | | | _ | |
| | | | | | |
| _ | | | | | _ |
| | _ | - | | | |
| | | | | | |
| _ | | | | | |
| | _ | | | _ | |
| | | - | | | |
| _ | | | | | |
| | _ | | | | |
| | | | | | |
| | | | - | - ' | |
| | | | | | |

ATTACHMENT D

PERSONAL PROTECTIVE EQUIPMENT AND RESPIRATORY PROTECTION SOP'S

INSPECTION OF PERSONAL PROTECTIVE CLOTHING

- [1] Determine that clothing material is correct for specified task
 - a. compatibility chart
 - b. chemical hazard chart in Safety Plan
 - c. MSDS
- [2] Visually inspect material for:
 - a. imperfect seams
 - b. non-uniform coatings
 - c. tears
 - d. discoloration/degradation
 - e. malfunctioning closures
- [3] Hold up to light and check for pinholes.
- [4] Flex material:
 - a. observe for cracks
 - b. other signs of shelf deterioration
- [5] If the material has been used previously, inspect inside and out for signs of chemical penetration/degradation
 - a. discoloration
 - b. swelling
 - c. stiffness
- [6] During the work task:
 - a. evidence of discoloration/degradation
 - b. closure failure
 - c. tears
 - d. punctures
 - e. seam discontinuities

RESPIRATORY PROTECTION

General Guidelines

- [1] All personnel required to use respirators will select and use the respirators based upon guidelines established by OSHA, NIOSH, and the RES Respiratory Protection Program.
- [2] All individuals required to wear respirators will have received a documented pre-issue qualitative fit test for the MSA full-face.
- [3] Each individual will be responsible for conducting a positive/negative fit check each time the respirator is donned.
- [4] Each individual shall be responsible for cleaning his/her own respirator at least once daily and is permitted to leave the work area to wash his/her own respirator as needed.
- [5] Cartridges or filters shall be changed after each daily use or whenever an increase in breathing resistance/odor is detected, or if they become wet. All changes will be made in uncontaminated areas.
- [6] No RES employee shall wear a respirator until he/she has been examined by a physician and determined to be physically able to wear respiratory protection. This examination shall be documented at the site.
- [7] All personnel must be qualitively fit test every six months.

Air Purifying Respirator Inspection and Checkout

- [1] Visually inspect the entire unit for any obvious damages, defects, or deteriorated rubber.
- [2] Make sure the facepiece harness is not damaged.
- [3] Inspect lens for damage and proper seal in facepiece.
- [4] Exhalation Valve
 Pull off plastic cover and check valve for debris, tears, or deformities in the neoprene valve.
- [5] Inhalation Valve
 Screw off cartridges/canister and visually inspect neoprene valves for tears.

 Make sure than inhalation valves and cartridge receptacle gaskets are in place.
- [6] Insure that the speaking diaphragm retainer ring is hand tight.

- [7] Make sure than you have the correct cartridge.
- [8] Don and perform positive and negative pressure check.

Storage of Air Purifying Respirators

- [1] OSHA requires that respirators be stored to protect against:
 - * Dust
 - * Sunlight
 - * Heat
 - * Extreme Cold
 - * Excessive Moisture
 - * Damaging Chemicals
 - * Mechanical Damage
- [2] Respirators must be stored in a clean area which is not likely to be contaminated by the work in progress.
- [3] Respirators should not be hung from their headbands for prolonged periods of time.

SCBA Inspection and Checkout

- [1] Monthly Inspection
 - a. check cylinder label for current hydrostatic test date
 - b. inspect cylinder for large dent or gouges
 - c. inspect cylinder gauge for damage
 - d. complete routine inspection
 - e. fill out inspection documentation card
- [2] Routine Inspection
 - a. Pre-Operational
 - high-pressure hose connector is tight on cylinder fitting
 - * by-pass valve is closed
 - * mainline valve is closed
 - * regulator outlet is not covered or obstructed
 - b. Backpack and Harness Assembly
 - inspect backpack/harness straps for wear, damage, secure
 - * check wear and function of belts
 - * check backplate and cylinder holder for damage

SSP: Sauget Landfill DATE:02/16/95 PAGE 49 OF 62

Cylinder and High Pressure Hose Assembly c.

- check cylinder to insure firmly attached to backplate
- open cylinder valve; listen or feel for leakage around packing and hose connection
- check high pressure hose for damage or leaks

d. Regulator

- cover regulator outlet with palm of hand
- open mainline valve
- remove hand from regulator outlet
- open by-pass valve slowly to assure proper function
- close by-pass valve
- open mainline valve
- note pressure reading on regulator gauge
- close cylinder valve while keeping hand over regulator outlet
- slowly remove hand from outlet and allow air to flow
- note pressure when low pressure warning alarm sounds; it should be 550-650 psi
- close mainline valve
- check regulator for leaks by blowing air into regulator for 5-10
- draw air from outlet for 5-10 seconds
- if a positive pressure or vacuum cannot be maintained, there is a leak.

Facepiece & Corrugated Breathing Hose e.

- inspect head harness and facepiece for damage, serrations, and deteriorated rubber
- inspect lens for damage and proper seal in facepiece
- inspect exhalation valve for damage and dirt buildup
- stretch breathing hose and carefully and inspect for holes and deterioration
- inspect connector for damage and presence of washer
- perform negative pressure test with facepiece donned

f. Storage

- refill cylinder to 2216 psi
- close cylinder valve
- tightly connect high pressure hose to cylinder
- bleed pressure from high pressure hose by opening mainline valve
- close by-pass valve
- close mainline valve
- fully extend all straps
- store facepiece in a clean plastic bag for protection

PAGE 50 OF 62 DATE:02/16/95 SSP: Sauget Landfill

ATTACHMENT E

ALCOHOL AND DRUG PROCEDURES (Riedel only)

SSP: Sauget Landfill DATE:02/16/95 PAGE 51 OF 62

ALCOHOL AND DRUG POLICY (Riedel only)

- [1] No personnel are to report to the site under the influence of drugs or alcohol.
- [2] Failure to comply will result in being barred or removed from the site and/or other disciplinary action.
- [3] All RES employees will receive, and pass, a drug screen prior to work beginning.
- [4] A drug screen will be required of any personnel involved in an accident requiring medical attention.
 - a. The Response Manager is responsible for assuring that they have a copy of all Riedel employee's signed consent forms.
 - b. The supervisor will accompany the injured worker to the clinic for medical treatment and collection of the drug urinalysis.
- [5] Response Manager will insure that they have Med-Tox Drug and Alcohol Kits on site.

SSP: Sauget Landfill DATE:02/16/95 PAGE 52 OF 62

ATTACHMENT F ACCIDENT REPORTING/INVESTIGATIONS

SSP: Sauget Landfill DATE:02/16/95 PAGE 53 OF 62

RIEDEL ACCIDENT REPORTING/INVESTIGATIONS

- All injuries or accidents must be reported to the Response Manager or Site Safety Officer immediately.
- The Response Manager will conduct an immediate investigation of the accident and document all results on the Supervisor's Accident Investigation Report and State Worker's Compensation Form.
- The Response Manager will assign a supervisory individual to accompany all injured personnel to the clinic and follow guidelines outlined in the RET Return to Work Program.
- Copies of all Supervisor's Accident Reports will be sent to the Riedel Corporate Director of Health and Safety.

ATTACHMENT G SITE WALKTHROUGHS/ENTRY

SSP: Sauget Landfill DATE:02/16/95 PAGE 55 OF 62



ecology and environment, inc.

Thie: SOP-SITE ENTRY PROCEDURES

Category: GENERAL TECHNICAL 2.2

Revised: JANUARY 1990

Approved: H. Van Cleave

STANDARD OPERATING PROCEDURES FOR SITE ENTRY

JANUARY 1990

Prepared by

Ecology and Environment, Inc. 368 Pleasantview Drive Lancaster, New York 14086



Title: SOP-SITE ENTRY

Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

CONTENTS

| Section | <u>n</u> ' | Page |
|---------|--|------|
| 1 | INTRODUCTION | 1 |
| | 1.1 OBJECTIVES | 1 |
| | 1.2 SCOPE AND LIMITATIONS | 1 |
| 2 | POLICIES AND DOCUMENTATION | 2 |
| | 2.1 POLICIES | 2 |
| | 2.2 DOCUMENTATION | 3 |
| 3 | PIELD OPERATIONS | 4 |
| | 3.1 SITE SAFETY CONSIDERATIONS | 4 |
| | 3.1.1 Background Search | 4 |
| | 3.1.2 Site Categorization | 5 |
| | 3.1.3 Site Safety and Work Plan Development | 5 |
| | 3.1.4 Heetings and Training | 12 |
| | 3.1.5 General Safety Rules and Requirements | 13 |
| | 3.1.6 Radiological Hazards | 14 |
| | 3.2 ORGANIZATION OF THE FIELD INVESTIGATION AREA | 14 |
| | 3.2.1 Exclusion Area (Control Area) | 17 |
| | 3.2.2 Hot Line | 17 |
| | 3.2.3 Contamination Reduction Area | 17 |
| | 3.2.4 Contamination Control Line | 18 |
| | 3.2.5 Support Area (Administrative) | 18 |
| | 3.2.6 Vind Direction | 18 |
| | 3.3 ORGANIZATION FOR WORK | 18 |
| | 3.3.1 Command and Control | 18 |
| | 3.3.2 PDS Operator | 20 |
| | 3.3.3 Safety Officer | 20 |
| | 3.3.4 Work Party (Sampling Team) | 20 |
| | | 20 |
| | | 21 |
| | 3.4.1 Explosimeter | 21 |
| | 3.4.2 Oxygen Detector | |
| | 3.4.3 Draeger Tubes | 23 |
| | 3.4.4 Radiation Instruments | 23 |
| | 3.4.5 HNU Photoionizer | 24 |
| | 3.4.6 Organic Vapor Analyzer (OVA) | 24 |
| | 3.4.7 OVA in the Gas Chromatographic (GC) Hode | 24 |
| | 3.4.8 Other Equipment | 26 |



THE: SOP-SITE ENTRY

Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

LIST OF FIGURES

| <u> Pigure</u> | | Page |
|----------------|---|------|
| 3-1 | Site Type I Characteristics | 6 |
| 3-2 | Site Type II Characteristics | 7 |
| 3-3 | Site Type III Characteristics | 8 |
| 3-4 | Decision Guidance for Assigning PEL on Type III Sites | 9 |
| 3-5 | No Apparent Respiratory Hazard | 10 |
| 3-6 | Site Safety Procedures | 15 |
| 3-7 | Organization of the Field Investigation Area | 16 |
| 3-8 | Organization for Work | 19 |
| 3-9 | Considerations for Air Toxics Honitoring Strategies. | 22 |
| 3-10 | Primary Field Air Quality Survey Instruments | 25 |
| 3-11 | Initial Site Entry Action Levels | 27 |
| 3-12 | Federal Standards for Radiation Vorkers | 28 |
| 3-13 | Check List for Entry into a Hazardous Vaste Site | 30 |
| 3-14 | Egress from the Hazardous Waste Site | 31 |
| 3-15 | Level A PDS | 33 |
| 3-16 | Level B PDS | 35 |
| 3-17 | Decontamination Solutions | 36 |



THE: SOP-SITE ENTRY

Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

1 INTRODUCTION

A key element in any hazardous vaste site investigation is actual entry into the site. A safe and proper entry requires a careful and coordinated team effort before, during, and after actual entry.

The entry team must conduct and complete reconnaissance of the site, as well as undertake other tasks in unfamiliar surroundings, in a variety of situations, and with unknown hazards. The goals are to complete the tasks while maintaining and protecting the health and safety of E & E and subcontractor personnel.

E & E has established Standard Operating Procedures (SOPs) to serve as training and guidance tools during the planning and implementation of all phases of a site investigation. Of primary concern is the health and safety of personnel. This is organized under the Corporate Health and Safety Program and blueprinted in the Corporate Health and Safety Plan for Toxic and Hazardous Substances. Other phases of investigations are addressed in other SOPs, thus, those SOPs should be carefully reviewed prior to a site investigation.

This document presents site entry procedures and guidelines for all E & E personnel working on hazardous waste sites.

1.1 OBJECTIVES

The primary objective of the Site Entry SOP is to provide operating guidelines and to establish procedures for the entry and inspection of hazardous waste sites. It encompasses preplanning, site safety considerations, entry procedures, on-site guidelines, site egress, and decontamination procedures. This document is not designed to present site-specific procedures, but describes procedures applicable to a wide variety of hazardous waste sites.

1.2 SCOPE AND LIMITATIONS

The procedures outlined in this SOP are applicable to all E & E personnel who participate in the inspection or investigation of sites where chemical or biological contamination is known or suspected.

The provisions of this document are not binding on non-E & E personnel, unless otherwise specified under contractual agreement. However, non-E & E personnel will be encouraged to follow these procedures.

This document is applicable only to the conditions and limitations specified within and does not address operations at radioactive or asbestos sites, or barrel-opening operations. For asbestos inspection,



Calogory: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

assessment, or abatement oversight projects, please refer to <u>E & E</u> Corporate Guidelines for Asbestos Inspection/Assessment, Laboratory Analysis, and Abatement Oversight, October 1987.

2 POLICIES AND DOCUMENTATION

2.1 POLICIES

The health and safety of site inspection personnel has precedence over all other considerations in dealing with hazardous materials. When inspection personnel must be exposed to hazardous substances, every effort should be made to ensure that concentrations are as low as reasonably achievable. E & E has established specific health and safety policies and guidelines, set forth in the E & E Health and Safety Plan for Toxic and Hazardous Substances.

Entry into a known or suspected contaminated waste site will be conducted only when such entry is required to gather information not obtainable by any nonentry means. The time on site will be kept as short as possible. Entry onto any hazardous waste site is expressly forbidden unless conducted as part of a work assignment.

The Regional Manager/Supervisor and/or his or her designated assistant will appoint a Site Safety Officer (SSO) for each on-site inspection or investigation where there is suspected hazardous substance contamination.

The SSO, in consultation with the Project Team Leader (PTL) will, in accordance with this and other SOP documents, make decisions regarding:

- o The potential hazards present;
- o The type of protective clothing to be worn;
- o The type of respiratory protection to be worn;
- o The type of decontamination solution(s) to be used;
- o The distance to the exclusion area boundary; and
- o The location of the Command Post (CP), the personnel decontamination station (PDS), and the contamination control line (CCL).

The PTL vill assume full responsibility for the action of E & E personnel only. The PTL vill assume no responsibility for the action of non-contractor personnel. Non-contractor personnel entering the



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

hazardous vaste site vill be advised of the hazards present and safety precautions deemed necessary. If non-contractor personnel choose to enter the hazardous vaste site in disregard of the PTL's advice, then official written notification will be made in the daily log, and the Regional Hanager/Supervisor will be advised of the situation. The PH or regional manager will be advised of the situation. If the actions of non-E & E personnel result in a threat to the welfare of E & E personnel, the PTL can choose to cease on-site operations until the situation is resolved.

2.2 DOCUMENTATION

Before site entry, documentation should be completed to address the legal, health, and safety issues of site access. Legal issues concerning E & E's right to enter the site are resolved by obtaining permission to access the property(ies) that incorporate the site. This permission may be granted by the property owner(s) or by appropriate judicial authorities. Documentation of permission, in the form of a court order or written authorization, should be available for disclosure at the site during the investigation.

The PTL, PM, and SSO vill be responsible for maintaining all records, logs, and reports required for, or generated by the on-site activities (refer to E & E's logbook SOP). Records vill be kept of the following:

- o A log of all information (i.e., calibrations) and all data from personnel monitoring devices and instruments (e.g., dosimeters and personnel air sampling devices);
- o An on-site activity log (updated hourly) to record the progress of each activity, field data from each sample collected, tracking numbers, and other information for all samples; and
- o An on-site safety log of all personnel, safety activities (e.g., monitoring activities and results), changes from the original safety plan, protective steps taken, special problems encountered, and solution measures taken.

In addition, photo-documentation of site conditions is vital in any investigation and can prove to be indispensable for later use in site evaluations, reports, or litigation proceedings. It is important that all information concerning each photograph be recorded in the field logbook.



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

3 FIELD OPERATIONS

3.1 SITE SAFETY CONSIDERATIONS

Upon initial entry into a site, the investigation team performs a variety of tasks in unfamiliar surroundings with unknown hazards. The team members wear protective clothing and respiratory protection devices that restrict and hinder both movement and vision. If the entry is to be performed smoothly and safely, proper planning and procedures must be established.

The necessity to enter a site must first be evaluated before any other site questions can be addressed. Site access will be considered a work alternative only if it is to gather information that is not available from other off-site sources.

Assurance of a safe investigation hinges on proper planning and implementation. The following are four fundamental site-safety components:

- o Thorough background search for site characterization,
- o Development of a comprehensive Site Safety Plan (SSP) and work plan,
- o Implementation of approved site-specific safety plan, and
- o Use of common sense in safe work practices.

3.1.1 Background Search

The background search occurs during the planning stages of the projects and is inherently linked to the formation of the SSP and work plan (Section 3.1.2). Staff conduct a review of all background material and available data, focusing on the past history of the site, the materials used or disposed of at the site, data and information from previous investigations, past site conditions, as well as present activity and condition of the site. This information is available from a variety of sources:

- o Client records;
- o Aerial photographs;
- o Federal, State, or local agency files; and
- o National or regional data bases.



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

3.1.2 Site Categorization

Because there are so many, varied sites, E & E has developed three categories or types of sites for planning purposes. Using these types provides a viable means of selecting levels of personnel and respiratory protection:

- o Site Type I: Apparent No-Problem Site (see Figure 1). All background information indicates that there is no hazard associated with this site. If the correct response to all of the items depicted in Figure 1 can be obtained, then E & E personnel may conduct the investigation in Level D protection.
- o Site Type II: Industrial Vorkplace Site (see Figure 2). Team members must conduct extensive research to determine if the safety precautions in force at the industrial vorkplace sites are adequate for E & E personnel. (See Figure 2 for the review process.) If the review process indicates that the existing level of protection is adequate, then the team may enter the site in the same level of protection as the industrial worker. If review indicates a higher level of protection is required, these findings should first be discussed with the proper site authorities. It would not be prudent for team members to appear at a site in a higher level of protection without first informing the site managers.
- o Site Type III: Legitimate Uncontrolled Hazardous Substance Facility (see Figure 3). For a legitimate uncontrolled hazardous substance facility, the need for higher levels of protection should be evaluated against the potential of skin contact and inhalation. To assist in this evaluation, E & E has developed decision guidance matrices for assigning personnel equipment levels on a Type III site (see Figure 4). These decision matrices require simple "yes" or "no" answers to achieve succeeding levels of decision. After determining the proper clothing for site entry, teams must determine if there is an apparent respiratory hazard. Figure 5 lists conditions that should be considered in determining if there is an apparent respiratory hazard. If no respiratory hazard is present an initial entry survey should then be conducted. In cases for which no background information is available to determine respiratory hazard, the SSO should require use of respirators for site entry.

3.1.3 Site Safety and Work Plan Development

Hany health and safety concerns associated with the inspection or investigation of a hazardous waste site are related to the nature of the site and the extent of the work to be performed. Consequently, the SSP is a site-specific document that lists the objectives of the on-site



TRID: SOP-SITE ENTRY

Calegory: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

SITE TYPE I: "APPARENT NO-PROBLEM SITE"

REVIEW PROCESS:

- 1. ATTEMPT TO COMPLETE INVESTIGATION WITH PERIMETER INSTRUCTIONS
- 2. IF THERE IS A NEED TO ENTER, DO SO (LEVEL D) ONLY IF THE FOLLOWING APPLY:
 - a. Task limited to brief visual inspection
 - b. No containers of unknown or known hazardous substances visible
 - c. No unknown odors or known odors of hazardous substances
 - d. Good natural air circulation
 - e. Visible or historic evidence of accessibility to humans; no ill health effects
 - f. No visible dead animals or vegetation



The: SOP-SITE ENTRY

Calegory: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

SITE TYPE II: INDUSTRIAL WORKPLACE SITE

REVIEW PROCESS:

- 1. REVIEW SITE HISTORY; ESTABLISH TYPE OF WORKPLACE
- 2. INVENTORY WORKPLACE CHEMICAL HAZARDS
- 3. ESTABLISH APPLICABLE INDUSTRY STANDARDS (CONSULT REGIONAL OSHA/NIOSH OFFICES)
- 4. IF FACILITIES ONGOING HEALTH AND SAFETY PROGRAM IS ACCEPTABLE AND IF INVESTIGATIVE TASK PRESENTS NO ADDITIONAL RISK, USE WHAT THEY USE AS A MINIMUM

Figure 3-2 SITE TYPE II CHARACTERISTICS



This: SOP-SITE ENTRY

Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

SITE TYPE III: LEGITIMATE UNCONTROLLED HAZARDOUS SUBSTANCE FACILITY

- 1. EVALUATE NEED FOR LEVEL A EMERGENCY ACTION
- 2. SPLASH PROTECTION NEEDED FOR INITIAL ENTRY?
- 3. CONDUCT INITIAL ENTRY
- 4. IS THERE AN APPARENT RESPIRATORY HAZARD?

YES - Continue investigation in SCBA s and any necessary splash protection

NO - Continue investigation without respiratory protection

5. WORK CONTINUES WITH AMBIENT MONITORING AND REVALUATION OF PERSONAL PROTECTION NEEDS



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

DECISION GUIDANCE FOR ASSIGNING PEL ON TYPE III SITES




Figure 3-4 DECISION GUIDANCE FOR ASSIGNING PEL ON TYPE III SITES

9



Calegory: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

NO APPARENT RESPIRATORY HAZARD

- 1. NO DRUMS, LAGOONS, OR OTHER CONTAINERS OF UNKNOWN CONTENTS IN CLOSE PROXIMITY TO WORK AREA
- 2. SITE HAS GOOD AIR CIRCULATION
- 3. NO ILL HEALTH EFFECTS ASSOCIATED WITH SITE
- 4. INVESTIGATION DOES NOT REQUIRE EXCAVATION, DRILLING, OR DRUM OPENING
- 5. HISTORICAL REVIEW GIVES GENERAL IDEA OF SUBSTANCES PRESENT
- 6. OTHER?



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

work and describes the health and safety procedures and protocols that will be followed during the completion of those work objectives. (See Appendix A - Site Safety Plan).


The plan provides a written outline of the steps that are to be followed, eliminates the uncertainties of memory, and provides a checklist for preparing the site entry. It forces the writer to identify and organize the available data and then to construct a logical, coherent, and workable plan based on the data. As a written report, it is to be reviewed by peers, who should identify inadequacies.

First, the plan must include site background information, safety information, and instructions and procedures for both routine and emergency situations to ensure that the risk of accident or injury is minimized. Second, it should allow for contingencies that vill permit adaptations, at the discretion of the PM and the SSO, as new information is gathered and field conditions fluctuate. Finally, the plan must be presented in a concise, written format so that it is available as a source of site-specific safety and health information to team members.

Under certain conditions, safety plans may be subject to modifications by the PTL and SSO on site. If the danger appears to be greater than originally anticipated, the SSO has the option of immediately withdrawing the team or increasing the level of protection. If the danger was overestimated, the SSO can allow the site to be examined at a lower level of protection, provided that the SSP describes the rationale and the specific protection level to which the site can be downgraded.

When site conditions varrant modification to the operating procedure or the level of personal protection required, the changes and conditions should be thoroughly documented. If the modification results in significant changes, such as downgrading to a lower level of protection, the RSC will be informed. The SSO must present the rationale for making the changes and must provide sufficient monitoring data to justify the reduction in the level of protection. Team members will not use a level of protection less than that required in the SSP for each specific exclusion area or subarea until that decision has been approved by the RSC.

The work plan, like the safety plan, is a written outline of the work to be performed on site and the methods used to complete the investigative tasks. Because it is peer reviewed, inadequacies or unsafe procedures should be identified and modified. In many cases, the work plan is produced as part of the project proposal, or for review by the client.



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

A work plan should contain details of the site investigation that include, but are not limited to the following:

- o Initial entry and characterization;
- o Inventory of site materials and conditions;
- o Sampling plan and analysis required;
- o Geophysical explorations:
- o Groundvater monitoring-well installation;
- o Decontamination methods; and
- o Disposal of site-derived materials (drill cuttings, decontamination fluids, disposable gear).

3.1.4 Meetings and Training

Before on-site activities are initiated, the SSO will coordinate to the degree necessary (based on the site hazard level as determined by the PM) with local medical and emergency authorities to inform them of planned activities and special treatment or response needs in the event of injury or exposure.

Before the site entry, the SSO will conduct as many meetings or training sessions as necessary to ensure that all personnel who enter the site have a thorough understanding of health, safety, and operational aspects of on-site activities. Issues to be addressed during these meetings and training sessions may include, but are not limited to the following:

- o Potential hazards associated with the site:
- o Safety procedures (including the route to the designated emergency medical facility), specific hazards associated with on-site contaminants (as presented on the Hazard Evaluation of Chemicals worksheet), and team response organization and responsibilities in the event of an injury or contamination incident:
- o Monitoring instrument operation and monitoring frequency requirements;
- o The level(s) of personnel and respiratory protection required in each phase of planned on-site activity;
- o Protective equipment fit and operation;



This: SOP-SITE ENTRY

Category: GENERAL TECHNICAL 2.2

Revised: JANUARY 1990


- o Decontamination requirements and procedures;
- o Site-control procedures, including the designation of work and exclusion zones, and site-entry and -exit procedures; and
- o Contingency plans to protect the public and the environment in the event of an emergency.

All team members (including subcontractors and supervisory personnel) vill sign the On-Site Safety Meeting Form in the SSO's copy of the SSP at the end of the safety meeting(s). By signing the form, each team member indicates that the on-site hazards and site safety procedures and protocols have been explained by the SSP to his or her understanding. The form must be signed before site entry.

3.1.5 General Safety Rules and Requirements

Team members are aware of their responsibility to follow the general on-site safety practices and regulations that are necessary to meet the goals of E & E's Health and Safety Plan. These include the following:

- 1. There will be no eating, drinking, or smoking in the exclusion area or the contamination reduction area.
- 2. All personnel must pass through the contamination reduction area when entering or exiting an exclusion zone at sites where an exclusion zone has been established.
- 3. All monitoring requirements specified in the SSP will be carried out by trained personnel with properly maintained and calibrated equipment.
- 4. Emergency equipment (e.g., portable showers, eye vashes, fire extinguishers) will be on the hot line side of the contamination reduction area for quick access when such equipment has been included in the SSP.
- 5. Specific emergency equipment requirements for the clean side of the contamination reduction area will be specified in the SSP.
- 6. At the end of the workday, all personnel who have worked inside the exclusion zone (including the contamination reduction area) will take a hygienic shower, regardless of perceived exposure possibilities.
- 7. All supplied breathing air shall be certified Grade D (American National Standard, Commodity Specification for Air) or better.





Category: GENERAL TECHNICAL 2.2

Revised: JANUARY 1990

- 8. Where practical, all tools and equipment shall be spark-proof, explosion resistant, U.L. (Underwriters Laboratory) bonded and grounded.
- 9. Fire extinguishers, for use on equipment or small fires, will be on all sites in a location familiar to all site personnel.
- 10. All team members will be aware of emergency response and emergency evacuation responsibilities, procedures, protocols, and signals. Deviations from standard emergency protocols will be specified in the SSP. Personnel responsibilities will be outlined before site entry.
- 11. A first aid kit, which has been stocked to handle all of the first aid situations covered in the Red Cross standard first aid course, will be available in a marked location on site at all times. Additional first aid equipment needs and procedures will be specified in the SSP, as needed.
- 12. Safety and training meeting(s) will be held before site entry and, if necessary, each morning, to cover or review all site specific safety issues.

Additional guidelines are presented in Figure 6.

3.1.6 Radiological Hazards

At known or suspected contaminated vaste sites, radiological hazards are not necessarily isolated from other hazards which may be physical, chemical, or biological. The inspection team must always be alert to the potential presence of radiological hazards which may represent an equal or greater threat to health and safety than the hazardous waste.

If the historical background study does not indicate that radiological materials are present and the initial entry survey shows that there is radiation above the background level, all E & E personnel will leave the site; and the SSO will notify the E & E RSC.

3.2 ORGANIZATION OF THE FIELD INVESTIGATION AREA

There are no absolutes in organizing the layout of the field investigation area. Distances between each of the various components at the field site will vary depending on the weather, terrain, location, and types of contaminants on the site. The knowledge acquired through planning, together with an off-site reconnaissance around the perimeter of the suspected site, generally will provide the information needed to establish a rough boundary for the site. See Figure 7 for standard organization of the field investigation area.



Calegory: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

SITE SAFETY PROCEDURES

- . OBSERVE BUDDY SYSTEM
- PLAN YOUR ACTIONS—BE DELIBERATE
- . MAINTAIN CONTACT WITH SAFETY OFFICER
- PRACTICE CONTAMINATION AVOIDANCE

Don't sit or kneel on ground

Don't ground equipment

Avoid obvious contemination

- DON'T CLIMB OVER BARRELS OR OBSTACLES
- FOLLOW PREDESIGNATED ROUTES
- . MONITOR (AS REQUIRED) FOR

Radiation

O, levels

Explosive hezard .

Buried metal

• MONITOR WEATHER CONDITIONS

Heat stress

Cold (frostbite)

Electrical storms

Wind direction

Figure 3-6 SITE SAFETY PROCEDURES



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

ORGANIZATION OF THE FIELD INVESTIGATION AREA




Figure 3-7 ORGANIZATION OF THE FIELD INVESTIGATION AREA



This: SOP-SITE ENTRY

Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

When establishing the organization and layout of the area, the two prime objectives are to minimize the potential for exposure and to restrict the spread of contaminated materials outside of the hazardous vaste site.

3.2.1 Exclusion Area (Control Area)

The first priority in approaching the area of an uncontrolled chemical or biological vaste site is to establish an exclusion or control area. This area acts as a buffer zone between the known or suspected contaminated area and the clean area. Initially, it is always assumed that the surface within the exclusion area is contaminated. The size of the exclusion area will vary depending on the nature of the site. The factors considered in establishing the exclusion area are:

- o Nature and toxicity of the site contaminants,
- o Explosive potential,
- o Meteorological condition,
- o Topography,
- o Concern for the unprotected public, and
- o Emergency egress routes from the site.

Safety is the primary consideration to be followed in the establishment of the exclusion area boundary. After an initial assessment of the site has been made by an initial entry party, it is always possible to reduce or increase the size of this area.

3.2.2 Hot Line

The hot line is located on the outer exclusion area boundary near the chemically or biologically contaminated area. This line is arbitrarily selected as the point at which a deliberate attempt is made at controlling any contamination picked up by personnel as they work on the hazard site. The access control point on the hot line is the point established through which all personnel are to enter and egress the exclusion area. The hot line can be adjusted down-range to reflect additional information learned about the site.

3.2.3 Contamination Reduction Area

The contamination reduction area lies between the outer exclusion area boundary and the contamination control line. In this area, a deliberate attempt is made to control and reduce contamination picked up by personnel returning from the exclusion area. This area, designated



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

for decontamination operations, is called the personnel decontamination station (PDS). Operations within the PDS are discussed in Section 3.7.

3.2.4 Contamination Control Line

The contamination control line is the rear boundary of the contaminated reduction area and is the line separating the possibly contaminated area from the clean area. Entry from the clean support area to the contamination control area is always made through an access control point on the contamination control line. No person may cross this line unless he or she has the proper level of protection.

3.2.5 Support Area (Administrative)

The support area is always established in a clean area. It contains the command post (CP) and other support elements. The distance from the contamination control line to the CP is approximately 50m, adjustable according to known site conditions. The CP is the center of command and control for the entire operation; it is always upwind of the contamination area and, if possible, on high ground to provide visual observation of the entire area.

3.2.6 Wind Direction

The guiding principle in organizing the field site is a simple one. If at all possible, the CP should be located upwind from the hazard area. If terrain or water will not accommodate this arrangement, a cross wind is acceptable. If the CP must be located downwind from the site, all personnel may have to don appropriate breathing apparatus. Significant variations in normal prevailing winds can be monitored through maintaining on-site weather status reports and making use of local weather reports for daily planning and updating.

3.3 ORGANIZATION FOR WORK

The personnel requirements for conducting operations on a hazardous substances site are dependent on a number of factors. For simplicity, the present discussion focuses on a five-member team (see Figure 8).

3.3.1 Command and Control

Command and control of the work site is exercised from the CP, which is manned by a CP supervisor or team leader. The CP will maintain radio contact with other team personnel and, by radio, will direct their actions. The CP supervisor also maintains contact with the PM and other personnel not on site. In a five-person team, only one team member (usually the team leader) will remain in the CP.



Thue: SOP-SITE ENTRY

Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990




Figure 3-8 ORGANIZATION FOR WORK

crongs due continuer



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

3.3.2 PDS Operator

One team member will be designated as the PDS operator. This team member processes work teams into the hazard site and decontaminates personnel returning from the hazard site. He or she also is responsible for equipment checkout and recharging of respirator tanks. In a five-person team, the safety officer must help the PDS operator during in-and-out processing of team members.

3.3.3 Safety Officer

The safety officer is positioned on the hot line, where he or she can observe the actions of work parties down range. Line of site between the safety officer and sampling team should be maintained at all times. The safety officer directs withdrawal of the work parties if, in his or her judgment, actions are being performed that may be unsafe. The safety officer is the primary advisor to the team leader on all matters relating to safety.

3.3.4 Vork Party (Sampling Team)

The final element of this hypothetical team is the work party. The work conducted by the two-person team provides the reason for being onsite; this team performs the necessary tasks called for in the site investigation. It can be given the following designations:

- o The initial entry party if it is the first team on site. It serves as a reconnaissance team, gathering information about the site.
- o The work party if performing general work or making general observations.
- o Sampling team when sample collection is the sole purpose for being on site.

The work party will never consist of less than two individuals, but may be larger if required to accomplish the work directed.

3.4 AIR HONITORING AND CHARACTERIZATION EQUIPMENT

Specialized equipment is used to measure and characterize air contaminants on a hazardous waste site. This information determines the nature and condition of the wastes present, the locations of "hot spots," and the level of worker protection required. This equipment is also used to monitor the site for changes in air contaminant concentrations during investigator work and to screen samples.

Although the instruments are designed for field investigations. they are inherently sensitive to environmental conditions and have



Title: SOP-

SOP-SITE ENTRY

Category:

GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

defined limitations and interferences, which may cause elevated or suppressed readings. In some cases, a measurement from one instrument may substantiate measurements from another; but in all cases, the information obtained from all instruments should be used to determine the overall picture of the site.

Monitoring instruments should be operated only by trained and experienced personnel who have a proper understanding of the use, limitations, and implications of these instruments and the vastes present at the site. Considerations for developing air monitoring strategies at hazardous waste sites are shown in Figure 9. The following subsections describe monitoring equipment.

3.4.1 Explosimeter

- o Description and Use: The explosimeter determines the level of flammable vapors or dusts present in an atmosphere as a percentage of the lower explosive limit (percent LEL) by measuring the change in electrical resistance in a Whetstone bridge circuit.
- o Operation: (See Appendices B and C.)
- o Limitations: The explosimeter cannot be used in atmospheres where the oxygen level is below 19.5 percent or above 25 percent. Silicanes, silicanes, silicates, and leaded gasoline vapors can destroy the instrument's sensitivity. The explosimeter does not indicate if a given atmosphere is toxic. The instrument must be calibrated daily. It will respond with varying sensitivities to various compounds.

o Action Levels:

- If less than 20 percent LEL, continue site inspection.
- If between 20 and 50 percent LEL, continue site inspection with continuous and careful monitoring; identify source, if possible.
- If greater than 50 percent LEL, evacuate site immediately, notify proper emergency agency.

3.4.2 Oxygen Detector

- o Description and Use: The oxygen detector measures the atmospheric oxygen concentration directly by means of a galvanic cell.
- o Operation: (See Appendix C.)

P SOP-SITE ENTRY Title: GENERAL TECHNICAL 2.2 JANUARY 1990 Category: Revised: Sensitivity/Limits of Detection sample injection, tools, etc.) INSTRUMENT FACTORS Specificity/Interferences Support Equipment (calibration, recorders, Ruggedness/Durability Power Requirements Westlier Resistance Response Time Serbent Media Sampling Time Service Life Versettly Accur acy Precision Flow Rate Mobility 3 Motor : 0 • Changing Wind Direction and Speed Beremetric Pressure METEOROLOGICAL FACTORS Stability Class Wind Direction Seler Loading Temperature Wind Speed Humidity On-Sile Traffic and Equipment Emissions Disposal Method (surface Impoundment, Concentration of Contaminent (current) Vehicular Traffic (location and volume) Physical/Chemical Properties of Agents Agents (number, class, compatibility) Lavel and Frequency of Site Activity Beseline Pollutant Levels (downwind) Predicted Emissions from Remedial landilli, drums, landiarm, etc.] Ambient Air Quelity (upwind) Inter-Sile Emission Locations SITE CONDITIONS Type of Remodial Activity Surface Area Expessed Centainment Integrity Tepography Age of Site Activity

Figure 3-9 CONSIDERATION FOR AIR TOXICS MONITORING STRATEGIES



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

3.4.5 HNU Photoionizer

- o Description and Use: The HNU photoionizer is used to determine the concentration of organic and inorganic vapors and gases with an ionization potential (IP) of less than 11.7 electron volts or 10.2 electron volts, depending on probe in use.
- o Operation: (See Figure 10.)
- o Limitations: The HNU photoionizer does not respond to compounds with ionization energies greater than the probe's potential, such as methane (CH₄), or hydrogen cyanide (HCN). The instrument's sensor cannot be immersed, and it functions poorly in cold or moist weather. The response will vary with different compounds.
- o Action Levels: Calibration to zero on "standby." The following action levels are for "above background" concentrations.

0 - 1 ppm: Level D protections generally sufficient

1 - 5 ppm: Don air purifying respirator (APR)

5 - 500 ppm: Don self contained breathing apparatus (SCBA)

3.4.6 Organic Vapor Analyzer (OVA) in the Survey Hode

- o Description and Use: The OVA provides a continuous readout of the total concentration of organic vapors and gasses by using a flame ionization detector.
- o Operation: (See Figure 10.)
- o Limitations: The OVA needs to be varmed up prior to use, and loses sensitivity in humid or moist conditions. The OVA can be used only by specially trained operators. It does not respond to inorganic vapors (most importantly HCN) but it does respond to methane (CH_L).
- o Action Levels: The following levels are action for "above background," non-methane concentrations.

0 - 1 ppm: Level D protection generally sufficient

1 - 5 ppm: Don APR 5 - 500 ppm: Don SCBA

3.4.7 OVA in the Gas Chromatographic (GC) Mode

o Description and Use: In the GC Mode, the OVA is used to characterize and identify specific organic compounds on site. It can be operated in conjunction with gas-tight syringes, Hylar bags, and air sampling pumps. In this mode it is also used to



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

PRIMARY FIELD AIR QUALITY SURVEY INSTRUMENTS

I. EQUIPMENT USED TO LOCATE "HOTSPOTS"

- o Photoionization Detector (PID)
 - The photoionizer by HNU is used to determine the concentration of organic and inorganic vapors and gases with a ionization potential (IP) less than 11.7 electron volts (ev).
 - The photoionizer does not respond to methane (CH₄) or hydrogen cyanide (HCN). The instrument's sensor is water soluble and cannot be immersed.
- o Organic Vapor Analyzer (OVA)
 - The OVA provides a continuous readout of the total concentration of organic vapors and gases by the use of a flame ionization detector.
 - The OVA can be used only by specifically trained operators. It does not respond to inorganic vapors (most importantly, HCN), but it does respond to methane.

II. EQUIPMENT USED IN AMBIENT AIR CHARACTERIZATION AND SAMPLE SCREENING

- o OVA in Gas Chromatographic (GC) Mode
 - In the GC mode, the OVA can be used to characterize and identify specific organic compounds on site. It can be operated in conjunction with gas-tight syringes, Mylar bags, and sampling pumps. In this mode, it is also used to screen samples before submitting them to the laboratory for analysis.
 - In the GC mode, additional specialized training is needed by the operator, and field standards have to be produced.

Figure 3-10 PRIMARY FIELD AIR QUALITY SURVEY INSTRUMENTS



Category: GENERAL TECHNICAL 2.2

Revised: JANUARY 1990

screen samples prior to submitting them to the laboratory for analysis.

- o Operation: (See Figure 10.)
- o Limitations: The OVA can be used only by personnel trained in gas chromatography.

3.4.8 Other Equipment

Other equipment which may be used to further evaluate personal protection requirements include:

- o Air particle counter (Dust meter),
- o pH meter,
- o H,S monitor (Hydrogen sulfide), and
- o HCN monitor (Hydrogen Cyanide).

3.4.9 Initial Site Entry Action Levels

These action levels are specifically established in the SSP. Each E & E employee is responsible for knowing the initial site entry action levels and the appropriate actions to be taken while on a hazardous substance site. See Figure 11 for a summary of the action levels.

3.4.10 Action Level for Radiation

When there is a reading indicating the presence of any radiation above the background level, E & E employees are to leave the site and report their findings to the RSC. Figure 12 provides the Federal Standard for Radiation Workers. These standards are NOT to be exceeded at any time.

3.4.11 Instrument Training

Each E & E employee must be familiar with the equipment used for site characterization. The following training aids are attached:

- o Appendix B: MSA Model 2A Explosimeter
- o Appendix C: MSA Combustable Gas and Oxygen Alarm (Hodel 260)
- o Appendix D: Draeger Tube Samplers
- o Appendix E: Radiation Alert-Mini

3.5 INITIAL ENTRY

An initial entry is conducted to confirm whether the historical background review is correct or whether the site conditions have changed the extent of the hazards. If limited or no information is available, the entry team will determine conditions and hazards.



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

INITIAL SITE ENTRY ACTION LEVELS

o EXPLOSIMETER

- less than 20% LEL: Continue site inspection
- between 20% and 50% LEL: Continue site inspection, Continuous/careful monitoring to identify the source, if possible
- above 50% LEL: EVACUATE IMMEDIATELY;
 Notify proper emergency agency

o OXYGEN METER

- less then 19.5%: Continue inspection with SCBA; Monitoring continuously; Explosimeter readings not valid below 19.5% or above 25% oxygen

o DRAEGER TUBES

- Species dependent: Consult "Dangerous Properties of Industrial Materials," Sax

o RADIATION SURVEY METER

Above background reading: EVACUATE IMMEDIATELY;
 Notify proper agency

Figure 3-11 INITIAL SITE ENTRY ACTION LEVELS .S



Category: GENERAL TECHNICAL 2.2

Revised: JANUARY 1990

FEDERAL STANDARDS FOR RADIATION WORKERS

WHOLE BODY PERMISSIBLE EXPOSURE

TIME

1.25 rem

Per quarter

5.00 rem

Per year

5(N-18)

Lifetime

N- age of person

Figure 3-12 FEDERAL STANDARDS FOR RADIATION WORKERS



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

The team is linked to the command post by radio communications and vill carry all air and radiological monitoring equipment needed to characterize the hazards on site. The members should be constantly alert and vatchful for unstable soil, unstable structures or containers, buried or partially buried drums or debris, vaste pools or piles, enclosed spaces, protruding objects, or any other dangerous or hazardous conditions. Avoidance of travel over or through vaste should be practiced. In no case (unless specified in the work plan and health and safety plan), shall any team member climb onto, or cross-over drums, tanks, waste containers, or confined spaces.

Detailed observations are to be recorded in the field logbook including observed hazards, identified container labels, container condition, instrument readings, and apparent spill or vaste areas. A Polaroid camera is useful in documenting site conditions which can be displayed at the command post.

It is crucial that the monitoring instruments be vatched closely. The team should proceed slowly and cautiously, as the instruments vill indicate hazardous environments before the team members would inadvertently enter one. The team should also keep in mind the evacuation route from the site should an emergency occur.

A checklist for entry into a hazardous waste site is presented in Figure 13.

3.6 EGRESS

Egress from the hazardous site must be carried out as a planned action——not as a panic reaction to low air reserves or other expected or exceptional circumstance. For example, it is not correct egress procedure to vait for the varning bell to ring on the SCBA oxygen tank, before attempting to reach the hot line in time for fresh air supplies. Not only must egress be planned before to entry, but it must also be understood that no team member may egress alone, and that no team member may remain on—site alone. Operations are always carried out according to the buddy system. Figure 14 summarizes some factors to be considered while planning an egress from the hazardous area.

3.7 PDS PROCEDURES (DECONTAMINATION)

The procedures discussed in this section are established to ensure that contamination is not spread to equipment, other team members, unprotected personnel, or the surrounding countryside.

3.7.1 Location of the PDS

The PDS lies in the area referred to as the contamination reduction area and is designed to help ensure that all personnel returning from



Category: GENERAL TECHNICAL 2.2

Revised: JANUARY 1990

CHECKLIST FOR ENTRY INTO HAZARDOUS SITE

- o ACTIONS IN SUPPORT AREA
 - WORK PARTY BRIEFING
 - EQUIPMENT CHECK
 - DONNING OF PROTECTIVE CLOTHING
 - CHECKOUT PROTECTIVE ENSEMBLE
 - COMMUNICATION CHECK
- o ACTIONS IN CONTAMINATION REDUCTION ARIA
 - FINAL COMMUNICATION EQUIPMENT CHECK
 - ENTER EXCLUSION ZONE VIA ACCESS CONTROL POINT
- o ENTRY TO SITE
 - SLOW AND DELIBERATE
 - FOLLOW PREARRANGED ROUTE
 - MAINTAIN BUDDY SYSTEM
 - MAINTAIN CONTACT WITH SAFETY OFFICER
 - MONITOR VIND DIRECTION
 - CONDUCT AMBIENT AIR MONITORING

Figure 3-13 CHECK LIST FOR ENTRY INTO A HAZARDOUS WASTE SITE



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990




Figure 3-14 EGRESS FROM THE HAZAROUS WASTE SITE



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

the site have been completely decontaminated before re-entry into the clean support area. (See Figure 7.)

3.7.2 Level A PDS Organization

Figure 15 is a graphic representation of a typical Level A PDS. It is designed with safety in mind and has been in use by U.S. Army units as a means of controlling chemical or biological contamination from heavily contaminated areas. Although these procedures may appear to represent an "overkill," they are time tested and proven to be effective. Until experience proves other procedures to be better, these will remain the procedures adopted by E & E.

3.7.3 Level A PDS Step-by-Step Procedures

- o Step 1 Equipment Drop. A plastic groundcloth is adequate for the equipment drop.
- o Step 2 Outer Garment Decontamination. Accomplished by PDS operators using sponges, brushes, and fire cans. Ten percent solutions of NaOH, Na2CO3, or Ca(OCI)2 serve as good decontaminants.
- o Step 3 Remove Boot Covers. PDS operators will remove booties and place then in a 10-gallon can lined with plastic.
- o Step 4 Decontaminate Boots and Gloves. Accomplished by team members who step in washtub of decontaminant for boots and dip gloves in bucket of decontaminant. Use decontaminant as in Step 2.
- o Step 5 Rinse Boots and Gloves. Same procedures as Step 4, except that water is used for the rinse.
- o Step 6 Remove Boots and Outer Garments. Accomplished with help from PDS operator. Place boots and suits in a 32-gallon can.
- o Step 7 Remove SCBA. Accomplished with help of PDS operator. Place SCBA on plastic sheet.
- o Step 8 Remove Inner Gloves, Socks, and Cotton Clothes.

 Accomplished with help of PDS operator. Place cotton items in second 32-gallon can lined with plastic bag.
- o Step 9 Field Shover. Any type of field expedient facility allowing for a minimum of a full rinse.



Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990




Figure 16. LEVEL B PDS

35

Category: GENERAL TECHNICAL 2.2

Revised:

JANUARY 1990

| no Uses/Reserve | notruc- Generally has the videst venge of use. Boot choice porti- on elter where conteminant to unhaven or a wide ronge of conteminants enists. | ater, add becom induction of choice for base labile compounds in carbo- such as the organization proticities. Effective in meutralising inorganic acide. Since andimo carbonate is a water softening agent, this choracteristic is an aid in physical removal of conteminants. | To tem politone of vator, and Scalium Mearbonate is amphatoric and can be used to four pounds of coalium bicor- neutralise elther base or seld contemious. Good benete. | triod- | To tem gallone of water, add Cyamide selte D pounds of calcium hype- chlorite | . follow EFFA is a cheleting agent and is decon of choice for heavy metal contoninate. | To ten gollono of water, and Those compounds are cholecting agents and are a decom- four pounds eltric, tertorid of choice for beavy metal conteminants. or smalle acid. |
|-----------------|---|--|---|--|--|--|--|
| Maing Solutions | Pollow the mining instruc- tions written on the parti- cular product label. | To ten gallono of water, add four pounds of sodium tothe- mate. | To ten pollone of we four pende of octive benete. | To ten gellene of water, add appres. I penade of triood- ium phosphote. | To ten gallone of unter, 8 pounds of calcium hypo- chlorite | Commercial product, follow product label. | |
| L. 12 [2] [24 | 100 | tedaling 38 codim carbo acc (taythy) weak- ing mode. | th openess solution on calcula, 38 codim Meer- bears (camby) baking | b. An exercise solution one talking 33 tribudian phosphote (ReyPO ₄) | E. As squares selution control to the training 10% coleins by-pechlorite (CoCl_10_1) | P. Ethylemedicalastatre- acutic acid (EFA, ver- sons, sequesteress) | G. An expense solution controlling 3 to 38 electe. tertarie, smolle selde or their respective so- diss solte. |

Figure 3-17 DECONTAMINATION SOLUTIONS